


**NOTES:**

1. MATERIAL USED FOR SUPPORT BLOCKING SHOULD NOT PREVENT ACCESS TO THE BOLT ASSEMBLY.
2. CONCRETE SHALL MEET THE REQUIREMENTS OF THE SSPWC. REBAR SHALL ONLY BE USED WHEN THE VALVE BOX IS LOCATED OUTSIDE OF PAVED AREAS.
3. VALVE BOXES TO BE SET  $\frac{3}{8}$ "- $\frac{5}{8}$ " BELOW FINISHED ROADWAY SURFACE. INSTALL OPERATING EXTENSION WITH OPERATING NUT RESTRAINING BOLT & TOP CENTERING PLATE. ANCHOR BARS & REDWOOD BLOCKS NOT REQUIRED WHEN OPERATING NUT IS AT GREATER DEPTH THAN 4' FROM FINISHED GRADE.
4. CONCRETE COLLARS IN THE WASHOE COUNTY ROADS SHALL BE BROUGHT TO GRADE ACCORDING TO THEIR RESPECTIVE REQUIREMENTS.

DATE	REVISIONS		STANDARD DETAILS FOR PUBLIC WORKS CONSTRUCTION	SECTION NUMBER:	
					300
				VALVE DETAIL	DRAWING NUMBER:
					W-303
				DATE:	
				2/21/2022	