


TYPICAL INSTALLATION
N.T.S.

NOTES:

1. ALL POSTS SHALL BE METAL.
2. WHERE GUARD RAIL IS TO BE INSTALLED, POST MAY BE OMITTED AND REFLECTOR PLATES SHALL BE INSTALLED ON GUARDRAIL POSTS.
3. WHERE CURB EXISTS, END OF ROAD MARKER SHALL BE INSTALLED 60 FEET FROM FRONT FACE OF CURB.
4. SPACING OF MARKERS TO BE DETERMINED BY THE COUNTY ENGINEER.

DATE	REVISIONS		STANDARD DETAILS FOR PUBLIC WORKS CONSTRUCTION		SECTION NUMBER:
			<h2>END-OF-ROAD MARKER</h2>		400
					DRAWING NUMBER:
					W-430
			DATE:	2/21/2022	