Washoe County Development Application

Your entire application is a public record. If you have a concern about releasing personal information, please contact Planning and Development staff at 775.328.3600.

Project Information	S	Staff Assigned Case No.:	· · · · · · · ·
Project Name:		,	
Incline C	Creek Estates Phase	2	
Project Description:			***************************************
Project Address: 800 Col	lege Drive, Incline V	illage, NV 89451	·
Project Area (acres or square fee	et): 110,821 sq. ft.	(2.54 acres)	
Project Location (with point of re	ference to major cross	streets AND area locator):	
Assessor's Parcel No.(s):	Parcel Acreage:	Assessor's Parcel No(s):	Parcel Acreage:
129-280-21	73,181 sq. ft.		
Section(s)/Township/Range: S	Section 10/Township	16 North Range 18 East	
Indicate any previous Washo Case No.(s).	e County approval	s associated with this applicat	ion:
Applicant	Information (atta	ch additional sheets if necessary)
Property Owner:		Professional Consultant:	
Name: NCP/ICP, LLC		Name: Welsh Hagen Assoc	ates
Address: 264 Village Blvd. S	Suite 104	Address: 250 South Rock Blvd	d. Suite 118
Incline Village, NV	Zip: 89451	Reno, NV	Zip: 89502
Phone:	Fax:	Phone: 775-853-7776	Fax: 775-853-9191
Email:		Email: dhagen@welshhag	en.com
Cell;	Other:	Cell: 775-848-1360	Other:
Contact Person: Brian Helm		Contact Person: David Hage	en .
Applicant/Developer:		Other Persons to be Contact	ed:
Name: NCP/ICP, LLC		Name:	
Address: 264 Village Blvd. Sui	ite 104	Address:	
Incline Village, NV	Zip: 89451		Zip:
Phone:	Fax:	Phone:	Fax:
Email:		Email:	
Cell:	Other:	Cell:	Other:
Contact Person: Brian Helm		Contact Person:	
	For Office	Use Only	
Date Received:	Initial:	Planning Area:	
County Commission District:		Master Plan Designation(s):	
CAB(s):		Regulatory Zoning(s):	

Tentative Subdivision Map Application Supplemental Information

(All required information may be separately attached)

Chapter 110 of the Washoe County Code is commonly known as the Development Code. Specific references to tentative subdivision maps may be found in Article 608, Tentative Subdivision Maps.

1. What is the location (address or distance and direction from nearest

800 College Drive, Incline Village, NV 89451 Cross Street Lucille Drive

2. What is the subdivision name (proposed name must not duplicate the name of any existing subdivision)?

Incline Creek Estates Phase 2

3. Density and lot design:

a. Acreage of project site	110,821 sq. ft.
b. Total number of lots	11 - 10 Single Family Lots and 1 Common Area
c. Dwelling units per acre	5 Single Family Residences
d. Minimum and maximum area of proposed lots	Minimum size - 2,700 sq. ft. Maximum size - 3,000
e. Minimum width of proposed lots	32'
f. Average lot size	2,800 sq. ft.

4. Utilities:

a. Sewer Service	Incline Village General Improvement District (IVGID)
b. Electrical Service	Sierra Pacific Power d/b/a NV Energy
c. Telephone Service	SBC (Nevada Bell) Telephone
d. LPG or Natural Gas Service	Southwest Gas Co.
e. Solid Waste Disposal Service	Incline Village General Improvement District (IVGID)
f. Cable Television Service	Charter Communications (CATV)
g. Water Service	Incline Village General Improvement District (IVGID)

Fo	common open space subdivisions (Article 408), please answer the following:
a.	Acreage of common open space:
	84,651 sq. ft. (1.94 acres)
b.	Development constraints within common open space (slope, wetlands, faults, springs, ridgelines)
	None.
C.	Range of lot sizes (include minimum and maximum lot size):
	Minimum size - 2,707 sq. ft. Maximum size - 3000
d.	Average lot size:
	Average size - 2,800
e.	Proposed yard setbacks if different from standard:
	The Applicant is developing a common open space community to help minimize impacts to the environment by maximizing open space. In this type of community, the parcel lines and building footprints are identical or very close to identical so there are no traditional setbacks. The issue instead is minimum building separation, which the Applicant is providing.
f.	Justification for setback reduction or increase, if requested:
	The Applicant will maintain a minimum building separation of 10 feet between units. The minimum building separation maintains the intent of the setbacks, since the County's five foot side setback requirement equals ten feet between buildings.
g.	Identify all proposed non-residential uses:
	None.

5.

	Protect and preserve existing natural vegetation and trees with the addition of trees, plants and vegetation to the back of lots abutting the common open space. The Applicant's landscape plan utilizes the least amount of water possible, compliments the natural environment and utilizes plants from TRPA's approved plant list.
i.	Describe or show on the tentative map any public or private trail systems within common open space of the development:
	N/A
j.	Describe the connectivity of the proposed trail system with existing trails or open space adjacent to or near the property:
	N/A
k.	If there are ridgelines on the property, how are they protected from development?
	N/A
l.	Will fencing be allowed on lot lines or restricted? If so, how?
	N/A - No fencing.

h. Improvements proposed for the common open space:

	m. Identify the party r	esponsible for maintenan	ce of the common open space:	
	Incline Creek	Estates Homeowners	s Association	
6.	adopted April 27, 19	99 Presumed Public Ro	acted by "Presumed Public Roads" as shown coads (see Washoe County Engineering websitering.htm). If so, how is access to those features.	e at
	The project is not	adjacent to public lan	ds or impacted by Presumed Public Roa	ds.
7.	Is the parcel within the	Truckee Meadows Servi	ce Area?	
	☐ Yes		Ø No	
8.	Is the parcel within the	Cooperative Planning Ar	ea as defined by the Regional Plan?	
	☐ Yes ☐ No	If yes, within what cit	y?	
9.		mit be required for utility submitted with the applica	y improvement? If so, what special use permitation package?	s are
	The Applicant will	not need a special us	e permit for utility improvements.	
;			-	
	Has an archeological : were the findings?	survey been reviewed an	nd approved by SHPO on the property? If yes,	what
	N/A			
			·	

a. Permit #	See Will Serve Letter	acre-feet per year	
b. Certificate #		acre-feet per year	
c. Surface Claim #		acre-feet per year	
d. Other#		acre-feet per year	
	hts (as filed with the State Er onservation and Natural Resou	ngineer in the Division of Wat urces):	er Resources of the
See Will Serve Le	etter		
With the second			
::	·		
Describe the aspects	of the tentative subdivision tha	at contribute to energy conserv	vation:
Describe the aspects LEED Building De		at contribute to energy conserv	ration:
<u> </u>		at contribute to energy conserv	vation:
<u> </u>		at contribute to energy conserv	vation:
<u> </u>		at contribute to energy conserv	ration:
<u> </u>		at contribute to energy conserv	vation:
<u> </u>		at contribute to energy conserv	ration:
<u> </u>		at contribute to energy conserv	ration:
LEED Building De	esign	Planning and Development as	
LEED Building De	esign rty In an area identified by rare or endangered plants a		s g habitat, migration
LEED Building De	rty in an area identified by rare or endangered plants a e? If so, please list the speci-	Planning and Development as	s g habitat, migration
Is the subject proper potentially containing routes or winter range taken to prevent adve	rty in an area identified by rare or endangered plants a e? If so, please list the speci-	Planning and Development as	s g habitat, migration
Is the subject proper potentially containing routes or winter range taken to prevent adve	rty in an area identified by rare or endangered plants a e? If so, please list the speci-	Planning and Development as	s g habitat, migration

14. If private roads are proposed, will the community be gated? If so, is a public trail system easement provided through the subdivision?

The roads within the subdivision will be private and gated. No public trails are required or needed because the adjacent properties are residential lots. These sites do not have trails through them, and the Tahoe Area Plan does not show proposed trails through the Applicant's property. Public access through this area appears to be provided along a portion of Village Blvd. via a bike path/sidewalk and a future planned bike/pedestrian trail along College Drive and additional segments of Village Blvd.

15. Is the subject property located adjacent to an existing residential subdivision? If so, describe how the tentative map complies with each additional adopted policy and code requirement of Article 434, Regional Development Standards within Cooperative Planning Areas and all of Washoe County, in particular, grading within 50 and 200 feet of the adjacent developed properties under 5 acres and parcel matching criteria:

The subject property is located within a developed area. The property to the north and west is low density urban, and the property to the northeast is high density suburban. The property to the south is across College Drive and is medium density suburban. Article 434 standards, therefore, do not apply to this project regarding parcel size matching and buffering. The additional parcel abuts a subdivision designated low density urban, so height limitations do not apply. The already approved Phase 1 subdivision abuts high-density suburban, which has a maximum height of 35 feet. The Applicant will abide by all conditions of approval for Phase 1 final map.

16. Are there any applicable policies of the adopted area plan in which the project is located that require compliance? If so, which policies and how does the project comply?

The Applicant is complying with the applicable policies of the Tahoe Are	a Plan.

17. Are there any applicable area plan modifiers in the Development Code in which the project is located that require compliance? If so, which modifiers and how does the project comply?

There are no plan modifiers in the Development Code that the Applicant must comply with except for TRPA standards on maximum height and removal of abandoned structures. Phase I and II comply with the TRPA height standards. The mobile homes and four wooden structures on Phase I and II have already been removed.

18.	. Will the project be completed in one phase or is phasing planned? If so, please provide that phasing plan:
	The overall project consists of two phases. Phase 1 Final Map was recorded on 8/1/2005 as Document #3254166, Subdivision Tract Map 4526.
19.	Is the project subject to Article 424, Hillside Development? If yes, please address all requirements of the Hillside Ordinance in a separate set of attachments and maps.
	☐ Yes ☐ No If yes, include a separate set of attachments and maps.
20.	Is the project subject to Article 418, Significant Hydrologic Resources? If yes, please address Specia Review Considerations within Section 110.418.30 in a separate attachment.
	☐ Yes ☑ No If yes, include separate attachments.
	Grading
imi cui yar per	ildings and landscaping; (2) More than one thousand (1,000) cubic yards of earth to be ported and placed as fill in a special flood hazard area; (3) More than five thousand (5,000) bic yards of earth to be imported and placed as fill; (4) More than one thousand (1,000) cubic ds to be excavated, whether or not the earth will be exported from the property; or (5) if a rmanent earthen structure will be established over four and one-half (4.5) feet high: How many cubic yards of material are you proposing to excavate on site?
	Cut = 1,306
22.	How many cubic yards of material are you exporting or importing? If exporting of material is anticipated, where will the material be sent? If the disposal site is within unincorporated Washoe County, what measures will be taken for erosion control and revegetation at the site? If none, how are you balancing the work on-site?
	Fill=800 cu. yds, A net of 500 cu. yds will be hauled off site and out of the Tahoe Basin. A BMP plan has been incorporated into the plans to accommodate for material storage during construction.

	Tree coverage is dense surrounding the area. College Drive will be the most exposed. Construction activities will be limited on the frontage road.
24.	What is the slope (Horizontal:Vertical) of the cut and fill areas proposed to be? What methods will be used to prevent erosion until the revegetation is established?
	BMPs such as construction entrance, silt fencing and fiber rolls will be used to mitigate sediment transport.
25.	Are you planning any berms and, if so, how tall is the berm at its highest? How will it be stabilized and/or revegetated?
	Berms are not proposed for Phase 2. Infiltration basins will be constructed by excavation only. In Phase 1, several berms were constructed up to 3' in height which have all been landscaped and revegetated.
	excavation only. In Phase 1, several berms were constructed up to 3' in height
26.	excavation only. In Phase 1, several berms were constructed up to 3' in height which have all been landscaped and revegetated. Are retaining walls going to be required? If so, how high will the walls be, will there be multiple walls.
:6.	excavation only. In Phase 1, several berms were constructed up to 3' in height which have all been landscaped and revegetated. Are retaining walls going to be required? If so, how high will the walls be, will there be multiple wal with intervening terracing, and what is the wall construction (i.e. rockery, concrete, timber
26.	excavation only. In Phase 1, several berms were constructed up to 3' in height which have all been landscaped and revegetated. Are retaining walls going to be required? If so, how high will the walls be, will there be multiple wal with intervening terracing, and what is the wall construction (i.e. rockery, concrete, timber manufactured block)? How will the visual impacts be mitigated?

	Construction of Phase 2 will require the removal of 36 trees, primarily Jeffrey F
	ranging in size from 6" dbh to 33" dbh.
28.	What type of revegetation seed mix are you planning to use and how many pounds per acre intend to broadcast? Will you use mulch and, if so, what type?
•	TRPA approved seed mix.
29	How are you providing temporary irrigation to the disturbed area?
-	How are you providing temporary irrigation to the disturbed area? A water tender for fugitive dust abatement will be onsite for the duration of the
	How are you providing temporary irrigation to the disturbed area? A water tender for fugitive dust abatement will be onsite for the duration of the Project.
	A water tender for fugitive dust abatement will be onsite for the duration of the
	A water tender for fugitive dust abatement will be onsite for the duration of the
	A water tender for fugitive dust abatement will be onsite for the duration of the
	A water tender for fugitive dust abatement will be onsite for the duration of the
30.	A water tender for fugitive dust abatement will be onsite for the duration of the Project. Have you reviewed the revegetation plan with the Washoe Storey Conservation District? If ye
30. [A water tender for fugitive dust abatement will be onsite for the duration of the Project.
30. [A water tender for fugitive dust abatement will be onsite for the duration of the Project. Have you reviewed the revegetation plan with the Washoe Storey Conservation District? If ye you incorporated their suggestions?
30. [A water tender for fugitive dust abatement will be onsite for the duration of the Project. Have you reviewed the revegetation plan with the Washoe Storey Conservation District? If ye you incorporated their suggestions?

Tahoe Basin

Please complete the following	a additional questions if the p	project is within the Tahoe Basin

31.	Wh ext	o is the ension?	Tahoe Region	onal Planning Agency (TRPA) project planner and what is his/her TRPA
	Pa	ul Niels	en - 775/58	39-5269. TRPA #990121
32.	ls t	ne projec	t within a Cor	nmunity Plan (CP) area?
		Yes	Ø No	If yes, which CP?
33.	Sta	te how yo	ou are addres	ssing the goals and policies of the Community Plan for each of the following
	a.	Land Us	e:	
		See Sh	neet Attach	ed
	b.	Transpor	rtation:	
		See Sh	eet Attach	ed
				·
	C.	Conserva	ation:	
		See Sh	neet Attach	ed
		E		

d.	Recreation:
	N/A
e.	Public Services:
	See Sheet Attached
34. Ide	ntify where the development rights for the proposed project will come from:
Th	ey are banked from APN 129-280-20 (10 units) - TRPA #2006-0214.
35. Will	this project remove or replace existing housing?
	Yes 🖸 No If yes, how many units?
36. Hov	v many residential allocations will the developer request from Washoe County?
N	one.
	scribe how the landscape plans conform to the Incline Village General Improvement Districtions and security security is a security of the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Districtions are security to the Incline Village General Improvement Distriction (Incline Village General Improvement Districtions are security to the Incline Village General Improvement Distriction (Incline Village General Improvement Dist
Fir	e Landscape Plan (included). nal plan will conform to the Incline Village General Improvement District ndscaping requirements.
· L	

ITEM 16

Conservation:

- a) The proposed design scheme, building materials, colors, finishes and total site area blends in with the surrounding environmental backdrop of Lake Tahoe. The architectural style is mountain craftsman. The structures are not massive structures that might overwhelm existing developments or block views. The wood exterior provides mountain feel one would expect in Lake Tahoe region and maintain the resort area feel.
- b) Open spaces will be landscaped and any area disturbed during construction will be replanted (see Landscape Plan). The applicant is endeavoring to reduce wildfire hazards by implementing defensible spaces around each structure. The Fire Department has already reviewed and approved the defensible space plan.
- c) There are old growth trees on site, and the Applicant is working with TRPA to preserve and protect these trees. The Applicant's layout ensures the maximum number of trees are saved. Trees have already been removed in Phase 1 and the reconfiguration will not increase the number of trees that needed to be removed.
- d) The Applicant's landscape plan utilizes the least amount of water possible, complements the natural environment and utilizes plants from TRPA's approved plant list.

Land Use and Transportation:

a) The existing transportation network can accommodate the planned traffic volumes for the project. College Drive and Village Blvd. are established roads, and this type of density is expected in this area.

Public Services and Facilities:

a) The policies for this section are directed toward Washoe County.

Property Owner Affidavit

Applicant Name: NCP/ICP, LCC
The receipt of this application at the time of submittal does not guarantee the application complies with all requirements of the Washoe County Development Code, the Washoe County Master Plan or the applicable area plan, the applicable regulatory zoning, or that the application is deemed complete and will be processed.
STATE OF NEVADA)
COUNTY OF WASHOE)
I, Hod Her Bacon, as Manager of Incline Creek, LLC, Which (please print name) manager of NCP/ICP, LLC being duly swom, depose and say that I am the owner* of the property or properties involved in this application as listed below and that the foregoing statements and answers herein contained and the information herewith submitted are in all respects complete, true and correct to the best of my knowledge and belief. I understand that no assurance or guarantee can be given by members of Planning and Development.
(A separate Affidavit must be provided by each property owner named in the title report.)
Assessor Parcel Number(s): 129-28021
Printed Name Heather Bacon, Manager
Signed
Address
Subscribed and sworn to before me this heterna FLORES (Notary Public Notary Public In and for said county and state My commission expires: Mar. 1, 2019
*Owner refers to the following: (Please mark appropriate box.) Owner Corporate Officer/Partner (Provide copy of recorded document indicating authority to sign.) Power of Attorney (Provide copy of Power of Attorney.) Owner Agent (Provide notarized letter from property owner giving legal authority to agent.) Property Agent (Provide copy of record document indicating authority to sign.) Letter from Government Agency with Stewardship

Washoe County Treasurer P.O. Box 30039, Reno, NV 89520-3039 ph: (775) 328-2510 fax: (775) 328-2500 Email: tax@washoecounty.us

Washoe County Treasurer Tammi Davis

Account Detail

Back to Search Results

Change of Address

Print this Page

Account Detail

Washoe County Parcel Informa	tion	
Parcel ID	Status	Last Update
12928021	Active	4/15/2016 2:10:23 AM
Current Owner: NCP/ICP LLC	SITUS 800 CO INCL N	OLLEGE DR
PO BOX 6622 INCLINE VILLAGE, NV 89450		
Taxing District 5200	Geo C	D:
	Legal Description	
SubdivisionName _UNSPECIFIED S	ection 10 Township 16 Range	± 18

Tax Bill (C	lick on desired	tax year for du	e dates and fur	ther details	
Tax Year	Net Tax	Total Paid	Penalty/Fees	Interest	Balance Due
2015	\$2,582.07	\$2,582.07	\$0.00	\$0.00	\$0.00
2014	\$2,576.40	\$2,576.40	\$0.00	\$0.00	\$0.00
2013	\$2,573.76	\$2,969.33	\$0.00	\$0.00	\$0.00
2012	\$2,582.42	\$3,349.88	\$0.00	\$0.00	\$0.00
2011	\$2,536.14	\$3,193.13	\$0.00	\$0.00	\$0.00
And the file of th	unter entreuer sensival incretaurantener fina dur enterior fina durante under enterior de la constitución de l Se		ner staden er en	Total	\$0.00

Important Payment Information

- ALERTS: If your real property taxes are delinquent, the search results displayed may not reflect the correct amount owing. Please contact our office for the current amount due.
- For your convenience, online payment is available on this site. E-check payments are accepted without a fee. However, a service fee does apply for online credit card payments. See Payment Information for details.

Pay Online

No payment due for this account.

\$0.00

Pay By Check

Please make checks payable to: WASHOE COUNTY TREASURER


Mailing Address: P.O. Box 30039 Reno, NV 89520-3039

Overnight Address: 1001 E. Ninth St., Ste D140 Reno, NV 89512-2845










The Washoe County Treasurer's Office makes every effort to produce and publish the most current and accurate information possible. No warranties, expressed or implied, are provided for the data herein, its use, or its interpretation. If you have any questions, please contact us at (775) 328-2510 or tax@washoecounty.us

This site is best viewed using Google Chrome, Internet Explorer 11, Mozilla Firefox or Safari.





CONDITIONAL WILL SERVE LETTER Dedication to IVGID Required

April 15, 2016

NCP/ICP, LLC. 264 Village Blvd. #104 Incline Village, NV 89451

RE:

Incline Creek Estates Phase II, 800 College Drive, APN 129-280-21

Dear NCP/ICP LLC:

This letter serves to notify you that the subject development is within the jurisdictional boundaries of the Incline Village General Improvement District (IVGID, or District), and that the District will serve the proposed project with water and sewer service and solid waste removal subject to the project's final utility plans meeting design, material, and installation requirements of the District, and subject to the assignment of water rights to IVGID in accordance with IVGID's Water Rights Dedication Procedures. In addition:

- (1) Water rights associated with this property, if any, shall be assigned to the District.
- (2) All requirements shall be met regarding STANDARD SPECIFICATIONS FOR IVGID's WATER, SEWER, AND PRIVATE COMMUNAL UTILITY SYSTEMS.
- (3) Meters and control manholes shall be placed off the property as approved by IVGID.
- (4) Cost for additional water storage or delivery capacity shall be borne by Applicant.
- (5) Separately owned parcels shall not be served by the same service connection.
- (6) All taxes and assessments on the parcel are current and shall remain current.

The subject parcel previously had multiple buildings used by Sierra Nevada College and had an average water use of 2.5 acre-feet (AF) for 2002, 2003, and 2004 calendar years. The applicant for the subject project is proposing to construct 10 new free standing condominiums with an annual water requirement of 0.56 acre-feet (AF) per year per unit or a total of 5.6 AF for all 10 units. This would also include typical landscaping in accordance with the IVGID landscaping ordinance for a single family residence. Landscaping that is substantially different from that specified in the requirements will require additional water rights to be provided to meet the landscaping irrigation demand. The Applicant for the subject project described is required to assign additional water rights to the District in the amount of 3.1 AF as a condition of issuance of a Final Will Serve Letter and project approval. This is in accordance with IVGID's Water Management Plan and Policies and is contingent upon existing permitted water rights and sewer capacities, including any action brought against the District contesting such permitted rights or capacities.

In the event additional water service demand is required by future change in service requests, additional water rights issues shall be addressed at that time.

The Applicant agrees to hold IVGID harmless from any costs, damages, or expenses incurred by the Applicant in the event IVGID fails to be able to supply water or sewer connections, or for any delays to the Applicant's project schedule caused by IVGID's review and approval procedures.

Very truly yours,

Joseph J Pomroy, P.E.

Director of Public Works

Attachments

Will Serve file

TENTATIVE MAP

FOR

INCLINE CREEK ESTATES - PHASE 2

INCLINE VILLAGE, NV WASHOE COUNTY

APN: 129-280-21 APRIL 2016

LEGEND **EXISTING PROPOSED** HYDRANT UTILITY POLE SPOT ELEV. A.C. PAVEMENT P.C.C. SIDEWALK or GUTTER TO BE REMOVED AGG. BASE RIP-RAP CONTOUR UTILITY LINES FENCE PROPERTY LINE OR R/W LINE SECTION LINE CONTROL POINT SOIL TEST PIT WATER VALVE GAS VALVE SANITARY SEWER MANHOLE TELEPHONE MANHOLE TELEPHONE BOX WATER METER GAS METER POWER VAULT CATCH BASIN EXISTING TREE EXISTING TREE TO BE REMOVED

GRADEBREAK

DETAIL REFERENCE

ORANGE CONSTRUCTION FENCE ------

SILT FENCE / SEDIMENT ROLL -O-O-O-

CHAIN LINK CONST. FENCE — Δ Δ

BASIS OF BEARING:


THE MERIDIAN OF THIS SURVEY IS IDENTICAL TO EDGEWOOD PARK SUBDIVISION, TRACT NO. 792, WASHOE COUNTY OFFICIAL RECORDS, THE BEARING N64°04'18"W, AS SHOWN.


BASIS OF ELEVATION:

THE BASIS OF ELEVATION FOR CONSTRUCTION ON THIS PROJECT IS:

BENCH MARK
NUMBER MARK
ELEVATION 6734.00'DATUM
DESCRIPTION BOLT IN A/C
FLIGHT CROSS PROJECT BENCH FROM MAP TITLED "SITE PLAN FOR SIERRA

NEVADA COLLEGE", ARNETT & ASSOC.





SHEET INDEX:

TITLE SHEET ———————————————————————————————————	C1 C2
DEMO PLAN	С3
SITE PLAN ————————————————————————————————————	C4
COVERAGE CALC'S/LINE AND CURVE TABLE ————————————————————————————————————	C5
GRADING PLAN —	
BMP PLAN ————————————————————————————————————	C7
UTILITY PLAN	C8
UTILITY PLAN —	
DETAIL SHEET ———————————————————————————————————	D1
DETAIL SHEET ———————————————————————————————————	D3
DETAIL SHEET -	D.5
DETAIL SHEET —	D6
DETAIL SHEET —	D7
DETAIL SHEET	D8

OWNER/DEVELOPER:

NCP/ICP, LLC 264 Village Blvd. Suite 104 Incline Village, NV 89451

CIVIL ENGINEER:

250 S. Rock Blvd. - Suite 118 Reno, Nevada 89502 (775) 853-7776 www.welshhagen.com

APPROVED BY:

DAT
DAT
DAT

LAND USE DATA:

11 TOTAL LOTS - 110,821 SF (2.54 Ac.) 10 RESIDENTIAL LOTS - 2,802 SF / LOT (AVG.) 1 COMMON AREA - 84,651 SF (1.94 Ac.)

> TENTATIVE MAP SUBMITTAL





ICE-PH2

SHEET

DRAWN BY: DESIGNED BY: CHECKED BY: JOB NO.: ICE-PH2

GENERAL NOTES

1. BEFORE COMMENCING WORK, ALL PLANS, SCHEDULES, AND SUBMITTALS MUST BE SUBMITTED AND APPROVED IN CONFORMANCE WITH REQUIREMENTS OF THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, (ORANGE BOOK) LATEST EDITION, AND PROJECT SPECIAL PROVISIONS. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE WASHOE COUNTY DEPARTMENT OF PUBLIC WORKS 48 HOURS IN ADVANCE OF THE TIME OF COMMENCEMENT OF WORK.

> WASHOE COUNTY PUBLIC WORKS RENO OFFICE: (775) 328-2041 INCLINE VILLAGE OFFICE: (775) 832-4125 KIMBLE CORBRIDGE, P.E.

OTHER AGENCIES TO BE NOTIFIED A MINIMUM OF 48 HOURS PRIOR TO COMMENCEMENT:

UNITED STATES FOREST SERVICE (530) 544-3481SUÉ NORMAN

TAHOE REGIONAL PLANNING AGENCY (775) 588-4547 EXT. 252 JEAN MCNAMARA

SOUTHWEST GAS CO.

INCLINE VILLAGE GENERAL IMPROVEMENT DISTRICT (IVGID) (775) 832-1274 URSULA LIPKOWITZ ENGINEERING

(775) 887-2857MATT HELMERS

SBC (NEVADA BELL) TELEPHONE (INCLINE VILLAGE) (775) 687 - 7954JOHN BENKERT

SIERRA PACIFIC POWER (530) 546-1737TIM HUTTON

CHARTER COMMUNICATIONS (CATV) (530) 546-8555 JOE PARME

- 2. WATER AND SANITARY SEWER FACILITIES SHALL BE RELOCATED AS A PART OF THIS CONTRACT. GAS AND TELEPHONE FACILITIES WILL BE RELOCATED BY SOUTHWEST GAS AND SBC. CONTRACTOR SHALL POTHOLE GAS AND TELEPHONE SUFFICIENTLY AHEAD OF PROPOSED STORM DRAIN CONSTRUCTION SO THAT THESE UTILITIES HAVE A MINIMUM OF 10 DAYS NOTICE TO RELOCATE THEIR FACILITIES. CONTRACTOR SHALL COORDINATE THIS RELOCATION WORK WITH THE RESPECTIVE UTILITY.
- 3. REASONABLE EFFORT HAS BEEN MADE TO LOCATE AND DELINEATE ON THESE PLANS ALL UNDERGROUND UTILITY MAINS, CONDUITS AND STRUCTURES THAT MAY BE AFFECTED BY CONSTRUCTION. THE TYPES, LOCATIONS, SIZES, EXTENT, AND/OR DEPTHS OF EXISTING UNDERGROUND IMPROVEMENTS SHOWN HEREIN WERE OBTAINED FROM SOURCES OF VARYING RELIABILITY. ONLY ACTUAL EXCAVATION WILL REVEAL THE CORRECT INFORMATION. THE ENGINEER CAN ASSUME NO RESPONSIBILITY FOR THE COMPLETENESS OR ACCURACY OF ITS DELINEATION OF UNDERGROUND UTILITIES NOR FOR THE EXISTENCE OF OTHER BURIED OBJECTS OR UTILITIES WHICH MAY BE ENCOUNTERED, BUT WHICH ARE NOT SHOWN ON THESE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING ALL UTILITY AGENCIES FOR LOCATIONS OF ALL UNDERGROUND FACILITIES PRIOR TO ANY EXCAVATIONS AND FOR THE PROTECTION OF AND REPAIR OF ANY DAMAGE TO THEM. CALL "UNDERGROUND SERVICE ALERT" 1-800-227-2600 AT LEAST 48 HOURS PRIOR TO ANY EXCAVATION. CONTRACTOR SHALL POTHOLE EXISTING UTILITIES AT ALL STORM DRAIN CROSSING POINTS PRIOR TO CONSTRUCTING STORM DRAIN. THERE SHALL BE NO DIRECT PAYMENT FOR THIS WORK.
- 4. CONSTRUCTION SHALL CONFORM TO THE SPECIAL PROVISIONS, THESE PLANS AND THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION LATEST EDITION. IN CASE OF CONFLICT BETWEEN THESE DOCUMENTS, THE ORDER OF PRECEDENCE SHALL BE AS INDICATED IN THE SPECIAL PROVISIONS. WHERE REFERENCE IS MADE HEREIN TO A TYPE OF STRUCTURE, IMPROVEMENT, STANDARD DRAWING, OR SPECIFICATION SECTION, IT IS THESE DOCUMENTS BEING REFERRED TO.
- 5. IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR WILL BE SOLELY AND COMPLETELY RESPONSIBLE FOR THE CONDITIONS OF THE JOB SITE INCLUDING SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND SHALL NOT BE LIMITED TO NORMAL WORKING HOURS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN AND CONSTRUCTION OF PROPER SHORING OF TRENCHES IN ACCORDANCE WITH OCCUPATIONAL SAFETY LAWS. THE DUTIES OF THE PROJECT CIVIL ENGINEER DO NOT INCLUDE REVIEW OF THE ADEQUACY OF THE CONTRACTORS SAFETY IN. ON. OR NEAR THE CONSTRUCTION SITE.
- 6. SHOULD IT APPEAR THAT THE WORK TO BE DONE, OR ANY MATTER RELATIVE THERETO, IS NOT SUFFICIENTLY DETAILED OR EXPLAINED ON THESE PLANS, THE CONTRACTOR SHALL CONTACT THE ENGINEER FOR SUCH FURTHER EXPLANATIONS AS MAY BE NECESSARY.
- 7. MOBILIZATION AREAS ARE TO BE SECURED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF MOBILIZATION SITES, INCLUDING PLACEMENT AND MAINTENANCE OF BMP'S, AS DESCRIBED IN NOTE NO.
- 8. ALL WORK SHALL BE DONE WITHIN THE COUNTY RIGHT-OF-WAY UNLESS AN EASEMENT OR CONSTRUCTION PERMIT HAS BEEN ACQUIRED BY THE COUNTY, IN WHICH CASE THE LIMITS OF WORK ARE AS SPECIFIED ON THE DRAWINGS. ANY DAMAGE DONE BY THE CONTRACTOR OR HIS SUB-CONTRACTORS TO PRIVATE PROPERTY AND/OR OUTSIDE OF THE NOTED LIMITS OF WORK IS SOLELY THE RESPONSIBILITY OF THE CONTRACTOR AND/OR HIS SUB-CONTRACTORS.
- 9. PRIOR TO STARTING WORK, THE CONTRACTOR SHALL INSTALL TEMPORARY BMP MEASURES AT LOCATIONS WHERE NEEDED TO CONTROL EROSION AND WATER POLLUTION DURING THE CONSTRUCTION OF THE PROJECT. THE BMP MEASURES SHALL REMAIN IN PLACE, AND SHALL BE MAINTAINED IN A FUNCTIONAL CONDITION, FOR THE DURATION OF THE CONSTRUCTION. SEDIMENT ROLLS ARE REQUIRED AT ALL DRAIN INLETS. SILT FENCE OR SEDIMENT ROLLS ARE REQUIRED AT OTHER LOCATIONS AS SHOWN ON THE DRAWINGS OR STAKED IN THE FIELD BY THE ENGINEER. ALL EROSION CONTROL MEASURES SHALL MEET OR EXCEED TRPA REQUIREMENTS. ALL TEMPORARY BMP MEASURES SHALL BE REMOVED WHEN CONSTRUCTION IS COMPLETED.
- 10. THE LOCATIONS SHOWN FOR PROPOSED CONSTRUCTION (BOTH HORIZONTALLY AND VERTICALLY) WERE DETERMINED PRIMARILY FROM THE SURVEY PERFORMED BY WELSH HAGEN AND ASSOCIATES, INC. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY IF CONFLICTS ARE EVIDENT OR WILL BE CREATED BY THE PROPOSED DESIGN AS SOON AS THEY ARE IDENTIFIED. ANY SUBSTANTIAL DEVIATION FROM THE APPROVED DESIGN SHALL FIRST BE COORDINATED WITH, AND APPROVED BY WASHOE COUNTY.
- 11. ANY EXISTING VEGETATED AREA DISTURBED BY CONSTRUCTION OPERATIONS SHALL BE RESTORED AS CLOSELY AS POSSIBLE TO ITS PREEXISTING CONDITION AT THE CONTRACTOR'S EXPENSE. IF THIS DISTURBANCE OCCURS IT IS RECOMMENDED THAT THE EXISTING LANDSCAPING/ VEGETATION BE SALVAGED AND REPLACED. IF THIS IS NOT POSSIBLE, DISTURBED AREAS SHALL BE REVEGETATED AT THE EXPENSE OF THE CONTRACTOR TO THE SATISFACTION OF THE ENGINEER. BMP'S TO PROTECT VEGETATION SHALL BE INSTALLED BY THE CONTRACTOR IF REQUIRED BY TRPA.
- 12. APPROXIMATE QUANTITIES OF VEGETATIVE COVER ITEMS OF WORK ARE INDICATED ON THE PLAN SHEETS OF THE CONSTRUCTION DRAWINGS. VEGETATIVE COVER SHALL BE INSTALLED IN THE VICINITY OF OTHER ITEMS OF WORK IDENTIFIED ON THE DRAWINGS. ACTUAL LOCATION FOR LIMITS OF EACH COVER TYPE WILL BE STAKED IN THE FIELD BY THE ENGINEER.
- 13. CONTRACTOR SHALL REMOVE, STORE & REINSTALL ANY CONFLICTING STREET SIGNS, SIGNS, MAIL BOXES, EDGE OF PAVEMENT DELINEATORS AND ANY OTHER STREET FURNITURE IMPACTED BY THE PROPOSED CONSTRUCTION.
- 14. ASPHALT REPLACEMENT SHALL INCORPORATE A MINIMUM OF 4% AND A MAXIMUM OF 6% CROSS SLOPE BETWEEN THE SAWCUT AND THE NEW ROADSIDE TREATMENT. NEW ROADSIDE FLOW CONVEYANCES SHALL INCORPORATE SUCH GRADE AS NECESSARY TO GUARANTEE WATER CONTINUES TO FLOW IN THE PRESENT DIRECTION, WITHOUT PONDING OR BREAKOUTS.
- 15. UNLESS SPECIFICALLY STATED OTHERWISE, THE CONTRACTOR SHALL PROVIDE SMOOTH TRANSITIONS OF CURB AND GUTTER AND/OR SWALES, TO ANY EXISTING DRIVEWAYS AND CULVERTS TO REMAIN.
- 16. CONTRACTOR SHALL VERIFY ELEVATIONS & LOCATIONS OF PROPOSED MANHOLES, CATCH BASINS, AND SEDIMENT TRAPS PRIOR TO ORDERING MATERIALS. SINCE THIS PROJECT REQUIRES A SUBSTANTIAL AMOUNT OF FIELD ADJUSTMENT, THE CONTRACTOR SHALL ORDER MATERIALS IN THE MOST SIMPLIFIED MODULAR CONFIGURATION POSSIBLE AND WITH THE BROADEST RANGE OF APPLICATION IN ORDER TO ELIMINATE THE NECESSITY OF REORDERING MATERIALS. THE EXPENSE OF REORDERING MATERIALS SHALL BE BORNE SOLELY BY THE CONTRACTOR.
- 17. ALL SANITARY SEWER CLEANOUTS, WATER VALVES AND METERS AND ANY YARD BOXES WHATSOEVER DISTURBED OR ENCOUNTERED WITHIN THE DEPICTED AREAS OF CONSTRUCTION ARE TO BE ADJUSTED AS NECESSARY TO GRADE WITHIN TRAFFIC AREAS AND 0.5 INCHES BELOW FINISH GRADE WHETHER SPECIFICALLY IDENTIFIED ON THE PLANS TO BE ADJUSTED OR NOT.
- 18. THE ENGINEER WILL PROVIDE ONE SET OF CONSTRUCTION STAKES AT THE COUNTY'S EXPENSE. ADDITIONAL CONSTRUCTION STAKES WILL BE PROVIDED AT THE CONTRACTOR'S EXPENSE. LIMITS FOR ALL ITEMS OF WORK SHALL BE STAKED IN THE FIELD BY THE ENGINEER. THESE LIMITS AND THE RESULTING TREATMENT LENGTH/AREAS MAY VARY FROM THOSE SHOWN ON THE DRAWINGS. PAYMENT FOR ITEMS
- OF WORK WILL BE MADE FOR THE AMOUNT AUTHORIZED BY THESE FIELD STAKED LIMITS AND THE SPECIAL REVISIONS 19. VEGETATION SHALL BE CLEARED AND GRUBBED ONLY IN THE AREAS SHOWING PROPOSED IMPROVEMENTS ON THE PLANS AND/OR BOUNDED BY THE MARKINGS IN THE FIELD BY THE ENGINEER. THE CONTRACTOR SHALL PROTECT ALL TREES, SHRUBS, AND OTHER VEGETATION IDENTIFIED TO NOT BE DISTURBED DURING CONSTRUCTION. PROTECTION METHODS SHALL BE BY METHODS DESCRIBED IN THE T.R.P.A. <u>HANDBOOK OF BEST MANAGEMENT PRACTICES</u>., VOLUME II, DATED NOVEMBER 1988 AND THE T.R.P.A. PERMIT REQUIREMENTS. FALLEN BRANCHES, LOOSE DEBRIS, AND OTHERWISE DEAD MATERIAL SHALL BE REMOVED.
- 20. DESIGN DRAWINGS, SPECIFICATIONS AND IMPROVEMENTS INDICATED HEREIN SHALL COMPLY WITH ALL APPLICABLE PROVISIONS OF THE WASHOE COUNTY DEVELOPMENT CODE.

TAHOE REGIONAL PLANNING AGENCY (TRPA) NOTES

- 1) PLACEMENT OF TEMPORARY BEST MANAGEMENT PRACTICES (BMP's) TO PREVENT SEDIMENT TRANSPORT DOWNSLOPE OF ALL EXCAVATED AREAS. EROSION CONTROL DEVICES SHALL BE PLACED EVERY 100 FEET IN EXCAVATED TRENCHES AND DITCHES. TEMPORARY EROSION CONTROL DEVICES SHALL BE MAINTAINED UNITL SITE IS STABILIZED.
- 2) THE PERMITEE SHALL IDENTIFY THE LOCATION OF ALL EQUIPMENT AND MATERIAL STAGING AREAS ON THE PROJECT PLANS. ALL STAGING AND STORAGE AREAS SHALL BE LOCATED ON PREVIOUSLY DISTURBED LAND OR PAVED SURFACES, AND SHALL BE FITTED WITH TEMPORARY BMP's, INCLUDING CONSTRUCTION LIMIT FENCING. TEMPORARY STAGING AND STORAGE AREAS NOT LOCATED ON PAVED SURFACES SHALL BE IDENTIFIED ON THE SITE THROUGH USE OF VEGETATION PROTECTION FENCING AND EROSION CONTROL FENCING WHERE APPROPRIATE AND SHALL NOT BE LOCATED WITHIN THE SEZ OR SEZ SETBACKS
- 3) WITHIN SEZ AREAS, VEGETATION PROTECTION FENCING SHALL BE PLACED ALONG THE LIMITS OF GRADING TO ENSURE THAT CONSTRUCTION ACTIVITY IS CONFINED TO THE DEFINED AREAS OF CONSTRUCTION.
- 4) THE INSTALLATION OF ROCK SLOPE PROTECTION (RIPRAP) SHALL INCLUDE THE FOLLOWING:
- 1) EDGES OF RIPRAP AREAS SHALL BLEND WITH ADJACENT NON-RIPRAP AREAS.
- 2) EXISTING SHRUBS AND TREES 500 mm OR GREATER IN HEIGHT SHALL BE RETAINED AND PROTECTED DURING RIPRAP INSTALLATION.
- 3) RIPRAP SHALL BE KEYED INTO AND AROUND EXISTING BEDROCK AND VEGETATION.
- 5) THE PERMITEE SHALL SUBMIT A PROJECT COMPLETION SCHEDULE TO TRPA. THE CONSTRUCTION SCHEDULE SHALL INCLUDE COMPLETION DATES FOR EACH ITEM OF CONSTRUCTION, AS WELL AS TEMPORARY BMP INSTALLATIONS FOR THE ENTIRE PROJECT AREA. THE CONSTRUCTION
- SCHEDULE SHALL INDICATE THAT EXCAVATION WILL BE PHASED TO MINIMIZE THE POTENTIAL FOR EROSION. 6) AN ONSITE INSPECTION BY TRPA STAFF IS REQUIRED PRIOR TO ANY CONSTRUCTION OR GRADING ACTIVITY.
- 7) ALL CONSTRUCTION EQUIPMENT WORKING IN OR NEAR STREAM ENVIRONMENT ZONES (SEZ) AREAS MUST BE STEAM CLEANED PRIOR TO MOBILIZAION AT THTE PROJECT SITE AND MAINTAINED IN CLEAN AND GOOD WORKING ORDER WITH MAINTENANCE LOGS MADE AVAILABLE TO TRPA AT THEIR
- SEE SUPPLEMENTAL TAHOE REGIONAL PLANNING AGENCY NOTES BELOW:
- 1) ALL BARREN AREAS AND AREAS DISTURBED BY CONSTRUCTION SHALL BE REVEGETATED IN ACCORDANCE WITH THE TRPA <u>HANDBOOK OF BEST MANAGEMENT PRACTICES</u> APPLICATION OF A MULCH MAY ENHANCE VEGETATIVE ESTABLISHMENT.
- 2) ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE MULCHED WITH A 2 TO 3 INCH LAYER OF PINE NEEDLES OR WOOD CHIPS AS DUST CONTROL MEASURES. THIS MULCH SHALL BE MAINTAINED FROM COMPLETION OF THE INITIAL GRADING THROUGH PROJECT COMPLETION.
- 3) INSTALL A 3 INCH LAYER OF GRAVEL (1 TO 2 INCH DRAIN ROCK) UNDER ALL RAISED DECKS AND STAIRS.
- 4) STANDARD WORK DAYS SHALL BE MONDAY THROUGH SATURDAY. SUNDAYS MAY BE WORKED ON OCCASION ONLY TO MAKE UP FOR WEATHER DELAYS OR OTHER SCHEDULE DELAYS. NOISE GENERATING ACTIVITIES WILL BE LIMITED TO THE HOURS OF 8:00 AM TO 6:30 PM.
- 5) NOISE SHALL BE REDUCED BY THE MANDATORY USE OF MUFFLERS ON ALL CONSTRUCTION VEHICLES AND EQUIPMENT. WHERE FEASIBLE, SOLENOIDAL PAVEMENT BREAKERS WILL BE USED IN LIEU OF AIR POWERED JACK HAMMERS NOISE GENERATING ACTIVITIES WILL BE LIMITED TO THE HOURS OF 8:00 AM TO
- 6) THE CONTRACTOR SHALL PROVIDE A WATER TRUCK TO WATER AREAS AS NECESSARY TO CONTROL DUST.
- 7) CONTRACTOR SHALL PROVIDE CRUSHED ROCK IN AREAS OF TEMPORARY CONSTRUCTION ACCESS TO MINIMIZE MIGRATION OF SEDIMENT.
- 8) ALL DISTURBED AREAS SHALL BE REVEGETATED WITH NATIVE SPECIES PER TRPA BEST MANAGEMENT PRACTICES (BMP). EXISTING VEGETATION REMOVED DURING CONSTRUCTION SHALL BE CHIPPPED AND MULCHED ON-SITE AND STORED FOR USE DURING REVEGETATION.
- 9) ALL TREES AND NATURAL VEGETATION TO REMAIN ON THE SITE SHALL BE PROTECTED PER TRPA RECOMMENDATIONS.
- 10) SOIL AND CONSTRUCTION MATERIAL SHALL NOT BE TRACKED OFF THE CONSTRUCTION SITE. GRADING OPERATIONS SHALL CEASE IN THE EVENT THAT A DANGER OF VIOLATING THIS CONDITION EXISTS.
- 11) DURING CONSTRUCTION ENVIRONMENTAL PROTECTION DEVICES, SUCH AS EROSION CONTROL, DUST CONTROL AND VEGETATION PROTECTION DEVICES SHALL BE MAINTAINED AT ALL TIMES.
- 12) LOOSE SOIL MOUNDS OR SURFACES SHALL BE PROTECTED FROM WIND OR WATER EROSION BY BEING APPROPRIATELY COVERED WHEN CONSTRUCTION IS NOT IN ACTIVE PROGRESS OR WHEN REQUIRED BY TRPA.
- 13) EXCAVATED MATERIAL SHALL BE STORED UPGRADE FROM THE EXCAVATED AREA WHENEVER POSSIBLE. NO MATERIAL SHALL BE STORED IN ANY STREAM ENVIRONMENT ZONE (SEZ) OR WET AREA.
- 14) ONLY EQUIPMENT OF A SIZE AND TYPE THAT WILL DO THE LEAST AMOUNT OF DAMAGE, UNDER PREVAILING SITE CONDITIONS, AND CONSIDERING THE NATURE OF THE WORK TO BE PERFORMED, WILL BE USED.
- 15) NO WASHING OF VEHICLES OR HEAVY EQUIPMENT, INCLUDING CEMENT MIXERS, SHALL BE PERMITTED ANYWHERE ON THE SUBJECT PROPERTY UNLESS AUTHORIZED BY TRPA IN WRITING.
- 16) NO VEHICLE OR HEAVY EQUIPMENT SHALL BE ALLOWED IN A STREAM ENVIRONMENT ZONE OR WET AREA EXCEPT AS AUTHORIZED BY TRPA.
- 17) ALL CONSTRUCTION SHALL BE WINTERIZED BY OCTOBER 15 TO REDUCE THE WATER QUALITY IMPACTS ASSOCIATED WITH WINTER WEATHER AS FOLLOWS:
 - A) FOR THE SITES THAT WILL BE INACTIVE BETWEEN OCTOBER 15 AND MAY 1: 1) TEMPORARY EROSION CONTROLS SHALL BE INSTALLED

2) TEMPORARY VEGETATION PROTECTION FENCING SHALL BE INSTALLED

- 3) DISTURBED AREAS SHALL BE STABILIZED 4) ONSITE CONSTRUCTION SLASH AND DEBRIS SHALL BE CLEANED UP AND
- 5) WHERE FEASIBLE, MECHANICAL STABILIZATION AND DRAINAGE IMPROVEMENTS SHALL BE INSTALLED
- 6) SPOIL PILES SHALL BE REMOVED FROM THE SITE
- FOR THE SITES THAT WILL BE ACTIVE BETWEEN OCTOBER 15 AND MAY 1, IN ADDITION TO THE ABOVE REQUIREMENTS:
- 1) PERMANENT MECHANICAL EROSION CONTROL DEVICES SHALL BE INSTALLED, INCLUDING PAVING OF THE DRIVEWAYS AND PARKING AREAS. 2) PARKING OF VEHICLES AND STORAGE OF BUILDING MATERIALS SHALL BE
- RESTRICTED TO PAVED AREAS.

ABBREVIATION

AC	ASPHALT CONCRETE	GD	GROUND	REF	REFERENCE
ACP	ASBESTOS CEMENT PIPE	GV	GATE VALVE	RET	CURB RETURN
AGG	AGGREGATE	H	HANDICAPPED	RP	RADIUS POINT
BC	BEGIN CURVE (HORIZONTAL)		HYDRAULIC GRADE LINE	RT	RIGHT
BOW	BACK OF WALK	HORIZ	HORIZONTAL	R/W, ROW	RIGHT-OF-WAY
BF, BOF	BOTTOM OF FOOTING	HP	HIGH POINT	S=	SLOPE (FT./FT.)
BV BV	BUTTERFLY VALVE	ID	INSIDE DIAMETER	5- S	SOUTH
	BEGIN VERTICAL CURVE	IE	INVERT ELEVATION	SD	STORM DRAIN
BVC BW	BOTH WAYS	INFIL	INFILTRATION	SDMH	STORM DRAIN STORM DRAIN MANHOLE
CB	CATCH BASIN	INT	INTERSECTION	SL	STREET LIGHT
cfs	CUBIC FEET PER SECOND	IRR	IRRIGATION	SPEC	SPECIFICATION
C&G		LAT	LATERAL	SS	SANITARY SEWER
<u>C</u>	CENTER LINE	LF	LINEAR FEET	SSCO	SANITARY SEWER CLEAN OUT
CL	CLASS	LT	LEFT	SSMH	SANITARY SEWER MANHOLE
CMP	CORRUGATED METAL PIPE	MAX	MAXIMUM	SSPWC	STANDARD SPEC. FOR PUBLIC WORKS CONST.
COMP	COMPACTION	MDD	MAXIMUM DRY DENSITY	STA	STATION
CONC	CONCRETE	MH	MANHOLE	SW	SIDEWALK
CP	CONCRETE PAD	MIN	MINIMUM	TELE	TELEPHONE
CTV	CABLE TELEVISION	MIN MMD	MAXIMUM MARSHALL DENSITY	TBO	TEMPORARY BLOW OFF VALVE
D.E.	DRAINAGE EASEMENT	MUTCD	MANUAL FOR TRAFFIC CONTROL DEVICES	TC	TOP OF CURB
DI	DROP INLET	N	NORTH	TG	TO GRADE
DIA	DIAMETER	NAP	NOT A PART	TOB	TOP OF BERM
DWY	DRIVEWAY	NIP	NOT IN PROJECT	TF, TOF	TOP OF FOOTING
Ē	EAST	NTS	NOT TO SCALE	TW, TOW	TOP OF WALL
ĒA	EACH	OC	ON CENTER	TS	TRAFFIC SIGNAL
EC	END CURVE (HORIZONTAL)	OD	OUTSIDE DIAMETER	TSCB	TRAFFIC SIGNAL CONTROL BOX
ELL	ELBOW	OH	OVERHEAD	TRANS	TRANSITION
ELEC	ELECTRICAL	PCC	PORTLAND CEMENT CONCRETE	TYP	TYPICAL
ELEV	ELEVATION	PG	PAD GRADE	UG/P	UNDER GROUND POWER
EVC		PI	POINT OF INTERSECTION	U.N.O.	UNLESS NOTED OTHERWISE
	END VERTICAL CURVE	PIVC	POINT OF INTERSECTION POINT OF INTERSECTION VERTICAL CURVE		
EX, EXIST	EXISTING			V ₅	VELOCITY AT 5 YEAR PEAK
EXT	EXTERIOR	PL	PROPERTY LINE	VC	VERTICAL CURVE
FE	FINISH ELEVATION	POCC	POINT OF COMPOUND CURVATURE	VEL	VELOCITY
FF	FINISH FLOOR	POT	POINT OF TANGENCY	VERT	VERTICAL
FFC	FRONT FACE OF CURB	PP	POWER POLE	VG	VALLEY GUTTER
FG	FINISH GRADE	PRC	POINT OF REVERSE CURVE	W	WEST
FH	FIRE HYDRANT	PRVC	POINT OF REVERSE VERTICAL CURVE	W/G	WATER AND GAS
FL	FLOW LINE	PVC	POLYVINYL CHLORIDE	WL	WATER LINE
fps		PVMT	PAVEMENT	WM	WATER METER
FTG	FOOTING	P.U.E.	PUBLIC UTILITY EASEMENT	WS	WATER SURFACE
G	GAS	Q ₅	5 YEAR PEAK FLOW	WV	WATER VALVE
GALV	GALVANIZED	Q100	100 YEAR PEAK FLOW	WWF	WELDED WIRE FABRIC
		_	D A DULIG		

REINFORCED CONCRETE PIPE

GRADE BREAK

TENTATIVE MAP SUBMITTAL





ICE-PH2


Z Ŋ \nearrow \circ $\stackrel{\mathsf{d}}{\mathsf{d}} \not\bowtie \mathsf{Z} \ \widehat{\mathsf{S}}$


> S \Box ÊОШ

> > N N

DRAWN BY: **DESIGNED BY:** CHECKED BY JOB NO.:

APRIL 201 BAMF ICE-PH2





LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTA
BUILDINGS	0	0	12,047	12,04
PATIOS, PORCHES & WALKS	0	0	2,126	2,126
AC PAVING	14	1,325	6,849	8,188
		1,325	21,022	22,36
EXISTING COVERAGE EXISTING COVERAGE - PARCEL :	<u>, ` </u>		OF 9/27/06)	·
EXISTING COVERAGE - PARCEL :	2 (W/ ADJUST	TMENTS AS CLASS 4	OF 9/27/06) CLASS 6	ТОТА
EXISTING COVERAGE - PARCEL : LAND CAPABILITY BUILDINGS	2 (W/ ADJUST CLASS 1b 16,821	TMENTS AS CLASS 4 20,212	OF 9/27/06) CLASS 6 53,799	TOTA 90,83
EXISTING COVERAGE - PARCEL :	2 (W/ ADJUST	TMENTS AS CLASS 4	OF 9/27/06) CLASS 6	TOTA 90,83
EXISTING COVERAGE - PARCEL : LAND CAPABILITY BUILDINGS	2 (W/ ADJUST CLASS 1b 16,821	TMENTS AS CLASS 4 20,212	OF 9/27/06) CLASS 6 53,799	TOTA

TOTAL EXISTING COVERAGE	34,479	48,730	132,163	215,372			
BANKED COVERAGE - TOTAL PROJECT AREA (PARCELS 1 & 2) (PER DEED							
RESTRICTION #3399612 ON FILE				· · · · · · · · · · · · · · · · · · ·			
LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL			
PARCEL 1	0	0	0	0			
PARCEL 2	35,744	12,033	42,210	89,987			
TOTAL EXISTING COVERAGE	35.744	12.033	42.210	89.987			

TOTAL AVAILABLE COVERAGE (E	XISTING AN	D BANKED)	- PROJECT A	AREA
LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
PARCEL 1	14	1,325	21,022	22,361
PARCEL 2	70,209	59,438	153,351	282,998
TOTAL AVAILABLE COVERAGE	70,223	60,763	174,373	305,359

PROPOSED COVERAGE - PARCEL 1							
LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL			
BUILDINGS	0	0	11,998	11,998			
PATIOS, PORCHES & WALKS	0	0	1,148	1,148			
AC PAVING	0	0	9,709	9,709			
TOTAL PROPOSED COVERAGE	0	0	22,855	22,855			

LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
BUILDINGS	0	0	5,053	5,053
PATIOS, PORCHES & WALKS	0	0	492	492
AC PAVING	1,781	0	5,914	7,695
TOTAL PROPOSED COVERAGE	1,781	0	11,459	13,240

PROPOSED COVERAGE - PARCEL	. 2 (WITHIN F	PHASE 2)		
LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
BUILDINGS	0	0	5,053	5,053
PATIOS, PORCHES & WALKS	0	0	492	492
AC PAVING	1,781	0	5,914	7,695
TOTAL PROPOSED COVERAGE	1,781	0	11,459	13,240

TOTAL PROPOSED COVERAGE	34,506	47,405	118,277	200,188					
TOTAL PROPOSED COVERAGE - TOTAL PROJECT AREA (PARCELS 1 & 2)									
LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL					
PARCEL 1	0	0	22,855	22,855					
PARCEL 2	34,506	47,405	118,277	200,188					
TOTAL PROPOSED COVERAGE	34,506	47,405	141,132	223,043					

CLASS 1b CLASS 4 CLASS 6 TOTAL

PROPOSED COVERAGE - ALL OF PARCEL 2

LAND CAPABILITY CLASS 1b

COVERAGE CALCULATIONS FOR ENTIRE PROJECT AREA (PARCELS 1 & 2)
(SEE SHEETS A-1.2 AND A-1.3 OF INCLINE CREEK ESTATES DRAWING SET DATED DECEMBER 2004
FOR COVERAGE CALCULATIONS OF LOTS 1 - 58)

	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
ът <i>1</i>	AREA	2,681	0	0	2,681
OT 1	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	27	0	0	27
	TOTAL COVERAGE	1,960	0	0	1,960
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
OT 0	AREA	2,498	183	0	2,681
OT 2	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	25	37	0	62
	TOTAL COVERAGE	1,910	50	0	1,960
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
o= o	AREA	37	2,299	0	2,336
OT 3	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	460	0	460
	TOTAL COVERAGE	1	1,787	0	1,788
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
о т 4	AREA	0	0	2,681	2,681
OT 4	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	804	804
	TOTAL COVERAGE	0	0	1,960	1,960
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
OT -	AREA	0	0	2,635	2,635
OT 5	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	791	791
	TOTAL COVERAGE	0	0	1,856	1,856
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,568	2,568
LOT 6	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	770	770
	TOTAL COVERAGE	0	0	1,851	1,851
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,635	2,635
OT 7	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	791	791
	TOTAL COVERAGE	0	0	1,856	1,856
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,681	2,681
8 TO	% ALLOWED PER BAILEY	1%	20%	30%	_
	ALLOWABLE COVERAGE PER BAILEY	0	0	804	804
	TOTAL COVERAGE	0	0	1,960	1,960
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,568	2,568
OT 9	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	770	770
	TOTAL COVERAGE	0	0	1,851	1,851
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,568	2,568
OT 10	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	770	770
	TOTAL COVERAGE	0	0	1,850	1,850
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,568	2,568
T 11	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	770	770
	TOTAL COVERAGE	0	0	1,851	1,851
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,568	2,568
OT 12	% ALLOWED PER BAILEY	1%	20%	30%	
_	ALLOWABLE COVERAGE PER BAILEY	0	0	770	770
		0	0	1,851	1,851

	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,719	2,719
LOT 13	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	816	816
	TOTAL COVERAGE	0	0	2,000	2,000
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,568	2,568
LOT 14	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	770	770
	TOTAL COVERAGE	0	0	1,844	1,844
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,681	2,681
LOT 15	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	804	804
	TOTAL COVERAGE	0	0	1,960	1,960
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	313	2,322	2,635
LOT 16	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	63	697	759
	TOTAL COVERAGE	0	64	1,760	1,824
LOT 17	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	2,681	0	2,681
	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	536	0	536
	TOTAL COVERAGE	0	1,923	0	1,923
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	2,681	0	2,681
LOT 18	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	536	0	536
	TOTAL COVERAGE	0	1,893	0	1,893
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	2,635	0	2,635
LOT 19	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	527	0	527
	TOTAL COVERAGE	0	1,782	0	1,782
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	2,681	0	2,681
LOT 20	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	536	0	536
	TOTAL COVERAGE	0	1,913	0	1,913
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	2,681	0	2,681
LOT 21	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	536	0	536
	TOTAL COVERAGE	0	1,897	0	1,897
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	2,635	0	2,635
LOT 22	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	527	0	527
	TOTAL COVERAGE	0	1,783	0	1,783
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	2,681	0	2,681
LOT 23	% ALLOWED PER BAILEY	1%	20%	30%	· · · · · · · · · · · · · · · · · · ·
	ALLOWABLE COVERAGE PER BAILEY	0	536	0	536
	TOTAL COVERAGE	0	1,979	0	1,979
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	2,635	0	2,635
		1%	20%	30%	*
LOT 24	% ALLOWED PER BAILEY	1 /0			
LOT 24	% ALLOWED PER BAILEY ALLOWABLE COVERAGE PER BAILEY	0	527	0	527

	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	2,681	0	2,681
LOT 25	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	536	0	536
	TOTAL COVERAGE	0	1,911	0	1,911
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	2,681	0	0	2,681
LOT 26	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	27	0	0	27
	TOTAL COVERAGE	1,961	0	0	1,961
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	1,516	1,165	2,681
LOT 27	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	303	350	653
	TOTAL COVERAGE	0	1,033	878	1,911
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	2,568	0	2,568
LOT 28	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	514	0	514
	TOTAL COVERAGE	0	1,851	0	1,851
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	2,568	0	2,568
LOT 29	% ALLOWED PER BAILEY	1%	20%	30%	
20120	ALLOWABLE COVERAGE PER BAILEY	0	514	0	514
	TOTAL COVERAGE	0	1,833	0	1,833
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	2,031	537	0	2,568
LOT 30	% ALLOWED PER BAILEY	1%	20%	30%	2,300
LO1 30	ALLOWABLE COVERAGE PER BAILEY	20	107	0	128
	TOTAL COVERAGE	1,435	398	0	1,833
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	
	AREA	2,458	110	0 0	TOTAL 2,568
LOT 32	% ALLOWED PER BAILEY	1%	20%	30%	
LU1 32	ALLOWABLE COVERAGE PER BAILEY	25		-	
	TOTAL COVERAGE	25 1,785	22 66	0	47 1,851
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
					2,635
LOTOO	AREA	2,635	0	0	2,035
LOT 33	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	26	0	0	26
	TOTAL COVERAGE	1,797	0	0	1,797
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	2,635	0	0	2,635
LOT 34	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	26	0	0	26
	TOTAL COVERAGE	1,783	0	0	1,783
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,681	2,681
LOT 35	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	804	804
	TOTAL COVERAGE	0	0	1,948	1,948
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,635	2,635
LOT 36	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	791	791
	TOTAL COVERAGE	0	0	1,856	1,856
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	64	2,617	2,681
LOT 27	% ALLOWED PER BAILEY	1%	20%	30%	
LOT 37		0	13	785	798
LO1 37	ALLOWABLE COVERAGE PER BAILEY	0			

	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	Т
	AREA	0		2.639	
		_	42	_,	2
LOT 38	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	8	792	
	TOTAL COVERAGE	0	30	1,930	
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	T
	AREA	0	2	2,678	
LOT 39	% ALLOWED PER BAILEY	1%	20%	30%	
20100	ALLOWABLE COVERAGE PER BAILEY	0	0	803	
	TOTAL COVERAGE	0	0	1,960	
		=		·	
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	T
	AREA	0	0	2,681	:
LOT 40	% ALLOWED PER BAILEY	1%	20%	30%	<u> </u>
	ALLOWABLE COVERAGE PER BAILEY	0	0	804	
	TOTAL COVERAGE	0	0	1,960	
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	Т
	AREA	0	8	2,626	
LOT 41	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	2	788	
	TOTAL COVERAGE	0	5	1,851	
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	7
I OT 42	AREA	0	45	2,636	
LOT 42	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	9	791	
	TOTAL COVERAGE	0	6	1,953	
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	٦
	AREA	0	0	2,619	
LOT 43	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	786	
	TOTAL COVERAGE	0	0	1,857	
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	1
	AREA	0	0	2,681	
LOT 44	% ALLOWED PER BAILEY	1%	20%	30%	
LOT 44					_
	ALLOWABLE COVERAGE PER BAILEY	0	0	804	
	TOTAL COVERAGE	0	0	1,960	
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	_
	AREA	0	0	2,681	
LOT 45	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	804	
	TOTAL COVERAGE	0	0	1,960	
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	1
	AREA	0	0	2,635	
LOT 46	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	791	
	TOTAL COVERAGE	0	0	1,856	
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	7
	AREA	0	0	2,681	
LOT 47	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	804	
	TOTAL COVERAGE	0	0	1,960	
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	1
	AREA	0	0	2,681	
LOT 48	% ALLOWED PER BAILEY	1%	20%	30%	
_0.40	ALLOWABLE COVERAGE PER BAILEY	0	0	804	
	TOTAL COVERAGE	0	0	1,960	
		_	_		_
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	1
	AREA	0	0	2,681	
LOT 49	% ALLOWED PER BAILEY	1%	20%	30%	
LO148	ALLOWABLE COVERAGE PER BAILEY	0	0	804	
	TOTAL COVERAGE	0	0	1,963	

	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,573	2,573
LOT 50	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	772	772
	TOTAL COVERAGE	0	0	1,960	1,960
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,635	2,635
LOT 51	% ALLOWED PER BAILEY	1%	20%	30%	·
	ALLOWABLE COVERAGE PER BAILEY	0	0	791	791
	TOTAL COVERAGE	0	0	1,856	1,856
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,681	2,681
LOT 52	% ALLOWED PER BAILEY	1%	20%	30%	<u> </u>
20102	ALLOWABLE COVERAGE PER BAILEY	0	0	804	804
	TOTAL COVERAGE	0	0	1,960	1,960
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,681	2,681
LOT 53	% ALLOWED PER BAILEY	1%	20%	30%	2,001
LOT 55	ALLOWED FER BAILET ALLOWABLE COVERAGE PER BAILEY	0	0	804	804
	TOTAL COVERAGE	0	0	1,960	
				· '	1,960
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6 2,681	TOTAL
LOTEA	AREA	_	0	,	2,681
LOT 54	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	804	804
	TOTAL COVERAGE	0	0	1,988	1,988
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	2,319	0	362	2,681
LOT 55	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	23	0	109	132
	TOTAL COVERAGE	1,649	0	294	1,943
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	2,201	0	480	2,681
LOT 56	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	22	0	144	166
	TOTAL COVERAGE	1,601	0	363	1,964
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	1,875	0	806	2,681
LOT 57	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	19	0	242	261
	TOTAL COVERAGE	1,331	0	596	1,927
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	2,037	0	643	2,680
LOT 58	% ALLOWED PER BAILEY	1%	20%	30%	-,
	ALLOWABLE COVERAGE PER BAILEY	20	0	193	213
	TOTAL COVERAGE	1,493	0	487	1,980
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,907	2,907
LOT 59	% ALLOWED PER BAILEY	1%	20%	30%	_,007
LO 1 00	ALLOWABLE COVERAGE PER BAILEY	0	0	872	872
	TOTAL COVERAGE	0	0	2,013	2,013
	LAND CAPABILITY	CLASS 1b	CLASS 4	2,013 CLASS 6	TOTAL
LOTOS	AREA	0	0	3,007	3,007
LOT 60	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	902	902
	TOTAL COVERAGE	0	0	2,013	2,013
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,855	2,855
LOT 61	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	857	857
	TOTAL COVERAGE	0	0	2,013	2,013

	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,821	2,821
LOT 62	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	846	846
	TOTAL COVERAGE	0	0	2,013	2,013
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,854	2,854
LOT 63	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	856	856
	TOTAL COVERAGE	0	0	2,013	2,013
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,748	2,748
LOT 64	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	824	824
	TOTAL COVERAGE	0	0	2,013	2,013
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
LOT 65	AREA	0	0	2,711	2,711
	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	813	813
	TOTAL COVERAGE	0	0	2,000	2,000
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,707	2,707
LOT 66	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	812	812
	TOTAL COVERAGE	0	0	1,930	1,930
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,707	2,707
LOT 67	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	812	812
	TOTAL COVERAGE	0	0	1,957	1,957
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	0	0	2,707	2,707
LOT 68	% ALLOWED PER BAILEY	1%	20%	30%	
	ALLOWABLE COVERAGE PER BAILEY	0	0	812	812
	TOTAL COVERAGE	0	0	1,980	1,980
	LAND CAPABILITY	CLASS 1b	CLASS 4	CLASS 6	TOTAL
	AREA	130,881	69,443	219,337	419,661
COMMON	% ALLOWED PER BAILEY	1%	20%	30%	
AREA	ALLOWABLE COVERAGE PER BAILEY	1,309	13,889	65,801	80,999
	TOTAL COVERAGE	14,853	23,838	60,093	98,784

	LINE TA	BLE
LINE	LENGTH	BEARING
L1	46.70	S26°04'35"W
L4	4.19	N51°02'55"E
L8	10.46	N40°27'14"E
L9	32.34	S70°15'05"E
L10	3.00	S19°44'55"W
L27	16.18	S59°43'45"E
L38	11.26	N40°27'14"E
L39	16.00	N49°32'46"W
L40	28.75	S20°44'02"W
L41	9.27	N12°14'06"E
L42	44.66	N19°00'47"E
L43	22.00	N70°15'05"W
L44	52.72	N70°15'05"W
L45	17.11	S80°02'45"E
L46	15.61	S78°05'37"W
L47	16.49	S86°48'07"E
L48	21.97	S80°02'45"E
L49	17.73	S66°32'26"W
L50	4.35	S23°48'45"E
L51	24.95	N78°05'37"E
L52	17.07	S48°01'01"W
L53	20.77	N66°32'26"E
L54	15.32	S48°01'01"W
L55	9.64	N37°29'34"W
L56	16.88	N48°14'47"E
L57	12.00	S48°14'47"W
L58	6.46	N12°14'06"E
L59	15.69	S59°43'45"E
L60	28.76	S45°54'08"E
L61	13.47	S45°54'08"E
L62	6.51	S19°03'05"W
L63	36.25	S35°13'34"E
L64	12.72	S35°13'34"E
L65	54.45	S26°04'35"W
L66	16.38	S78°05'37"W
L67	18.71	N78°05'37"E
L68	9.35	N21°04'17"W
L69	30.07	S20°44'02"W


CURVE TABLE				
CURVE	LENGTH	RADIUS		
C2	9.28	6.00		
C3	9.58	6.00		
C4	46.56	28.00		
C5	7.76	6.00		
C10	7.26	6.00		
C11	9.42	6.00		
C19	80.33	200.00		
C27	8.47	6.00		
C28	32.67	13.00		
C29	15.02	500.00		
C30	22.48	190.00		
C31	25.92	278.00		
C32	8.91	3.00		
C33	8.63	3.00		
C34	7.88	5.00		
C35	8.18	6.00		
C36	16.91	6.00		
C37	9.90	6.00		
C38	8.98	6.00		
C39	11.3	1 6.00		
C40	6.09	6.00		
C41	12.05	6.00		
C42	5.68	6.00		
C43	12.99	6.00		
C44	27.97	300.00		
C45	10.38	6.00		


TENTATIVE MAP SUBMITTAL


PRELIMINARY
NOT FOR
CONSTRUCTION


COVERAGE CALC'S/LINE AND (FOR INCLINE CREEK ESTATES) **C5** DATE: DRAWN BY: APRIL 2016 BAMF BAMF DLH ICE-PH2 DESIGNED BY: CHECKED BY: JOB NO.: 2 WORKING DAYS
BEFORE YOU DIG CALL USA
DIAL '811'


ICE-PH2

























GENERAL NOTES

- 1. EXISTING PAVEMENT TO BE MATCHED SHALL BE NEATLY CUT. 2. CONCRETE SHALL MEET THE REQUIREMENTS OF SECTION 202.12
- OF THE STANDARD SPECIFICATIONS. 3. IN ALL AREAS, COVERS SHALL BE SET FLUSH WITH FINISHED GRADE
- UNLESS OTHERWISE NOTED. 4. APPLY BLACK COLORANT TO SURFACE OF P.C.C. COLLAR.

MANHOLE COLLAR & TEMPORARY COVER

NO SCALE

1. THE USE OF FLEXIBLE CONNECTIONS IS RECOMMENDED

2. THE COVER SHOULD BE POSITIONED OVER THE CLEANOUT/


3. THIS IS A GENERAL ARRANGEMENT DRAWING CONSULT MANUFACTURER'S

AT THE OUTLET WHERE APPLICABLE.

3. SAND/OIL INTERCEPTOR SHALL BE

REPRESENTATIVE FOR SPECIAL CONDITIONS.

STORMCEPTOR STC450i OR APPROVED EQUAL.



NOTES:

- 1. CONTRACTOR SHALL CONTACT AND COORDINATE WITH
- ALL UTILITIES 48 HOURS PRIOR TO CONSTRUCTION. 2. ALL CONSTRUCTION SHALL CONFORM TO WASHOE COUNTY STANDARDS AND NO BACKFILLING WILL BE ALLOWED UNTIL INSPECTED AND APPROVED BY THE SEWER UTILITY.
- 3. MANHOLE SHALL BE CONSTRUCTED OF PRECAST REINFORCED CONCRETE SECTIONS CONFORMING TO ASTM DESIGNATION C478.
- 4. EXCAVATION FOR MANHOLE MUST BE MADE TO A MINIMUM OF ONE FOOT OUTSIDE OF THE MANHOLE WALL TO PROVIDE FOR ADEQUATE WORKSPACE. SPACE OUTSIDE OF THE MANHOLE SHALL BE BACKFILLED WITH ACCEPTABLE MATERIAL IN UNIFORM LAYERS NOT EXCEEDING 8" IN DEPTH. EACH LAYER SHALL BE THOROUGHLY COMPACTED TO THE DENSITY OF THE EARTH IN THE ADJACENT TRENCH SECTIONS. (MIN. 90% IN EXISTING OR PROPOSED STREET OR ALLEY RIGHTS-OF-WAY).
- 5. CAST IRON FRAME AND COVER SHALL BE 24" DIAMETER (CLEAR OPENING) AND SHALL BE MANUFACTURED FROM GRAY CAST IRON CONFORMING TO ASTM DESIGNATION: A 48, CLASS 30 AND DESIGNED FOR A MINIMUM HS-20 TRAFFIC LOADING. COVERS AND FRAMES SHALL BE MATCH-MARKED IN PAIRS AND SEATING SURFACES MACHINED SO THAT COVER IS NON-ROCKING. COVERS SHALL HAVE ONE PICK HOLE, AND ONE CENTRALLY LOCATED 1" DIG HOLE. COVERS SHALL HAVE NO "THRU" HOLES.
- 6. ALL BASES MUST BE PRECAST UNLESS OTHERWISE APPROVED BY THE SEWER UTILITY.
- 7. ALL JOINTS AND CONNECTIONS TO NEW OR EXISTING MANHOLES SHALL BE WATERTIGHT.

- 8. CONCRETE FOR CAST-IN-PLACE MANHOLE BASE, IF APPROVED BY WASHOE COUNTY FOR USE, SHALL CONFORM TO SECTION 202 OF THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION.
- 9. INVERTS SHALL BE FORMED DIRECTLY IN CONCRETE OF MANHOLE BASE AND SHALL BE SMOOTH AND ACCURATELY SHAPED TO A SEMI-CIRCULAR BOTTOM CONFORMING TO THE INSIDE OF THE ADJACENT STORM DRAIN SECTION.
- 10. STEPS ARE REQUIRED WHERE MANHOLE DEPTH IS 54" (4'- 6") OR GREATER, STEPS SHALL BE ALIGNED VERTICALLY (1" MAX. TOLERANCE) AND HORIZONTALLY (0.5" TOLERANCE) SO AS TO FORM A CONTINUOUS LADDER, AND SHALL CONFORM WITH THE STANDARDS, SECTION 1910.27 (DEPTH IS RIM ELEV. TO TOP OF PIPE).
- 11. WHERE MANHOLES ARE NOT LOCATED IN STREETS, PLACE TOP OF MANHOLE 8" ABOVE EXISTING GROUND UNLESS OTHERWISE REQUIRED BY WASHOE COUNTY. INSTALL THE CONCRETE COLLAR FROM A POINT 6" OUTSIDE THE TOP OF THE COVER FRAME AND EXTEND A MINIMUM OF 6 INCHES BELOW THE SURROUNDING GROUND SURFACE. TAPER THE CONCRETE COLLAR FROM TOP TO BOTTOM AT A 1:1 SLOPE OR FLATTER.
- 12. FOR VACUUM TESTING ALL MANHOLES SHALL BE SEALED THROUGHTHER RING AND COLLAR





STORM DRAIN MANHOLE NO SCALE

ICE-PH2

Ш

Ŋ

 \geq

 \sim

SE

 \circ

INCLIN

D2

DRAWN BY: DESIGNED BY:

CHECKED BY:

JOB NO.:

APRIL 201


BAMF


ICE-PH2

AIL

ALL WORKMANSHIP SHALL CONFORM TO LOCAL, STATE, AND NATIONAL CODES AS APPLICABLE.

TENTATIVE MAP SUBMITTAL





- 1. METER SHALL BE BADGER FIRE SERIES REGISTERING IN GALLONS. 2 RTR'S SUMMATOR SPLITTER TRACE. 2. METER SHALL BE INSTALLED AT A DEPTH OF NOT LESS THAN 36" AND NOT MORE THAN 48" MEASURED FROM THE TOP OF THE METER BOX TO THE TOP OF THE SUPPLY PIPE(SEE DETAIL).
- 3. REQUIRED DISMANTLING JOINT SHALL BE INSTALLED ON THE DOWNSTREAM OF METER AND UPSTREAM OF BYPASS ISOLATION VALVE(SEE DETAIL). ISOLATION VALVES SHALL BE LOCATED IN VAULT.
- 4. METER BYPASS SHALL BE 2" SIDE DISPLACEMENT TYP METER.
- 5. ASSEMBLY SHALL BE EQUIPPED WITH A SUMMATOR OR TOTALIZER.
- 6. METER BOX SHALL BE JENSEN PRE CAST #466TA-1 WITH STEEL H-20 TRAFFIC LOAD #4878AT-TRF LID OR APPROVED EQUIVALENT INSTALLED AT 1-1/2" TO 2" ABOVE FINISHED GRADE IN NON TRAFFIC AREAS OR 1/2" BELOW FINISHED GRADE IN TRAFFIC AREAS (SEE DETAIL). CONTRACTOR SHALL ENSURE THAT METER IS INSTALLED WITHIN THE VAULT WITH ONE FOOT OF CLEAR SPACE ON ALL SIDES OF METER TO THE VAULT WALL.
- 7. ASSEMBLY SHALL HAVE LUG RESTRAINT ON VAULT WALL. VAULT SHALL BE SUPLIED WITH EASY-OPEN LID, SPRING LOADED.
- PIT TRANSPONDER SHALL BE SUPPLIED. ASSEMBLY SHALL OPERATE BY "RADIO READ" TRACE SYSTEM.
- 10. METER VAULT SHALL BE SEALED WATER TIGHT.
- 11. CONTRACTOR SHALL PROVIDE LOCK AND KEYS FOR LID AND FURNISH TO IVGID.
- 12. A 2" UNMETERED BYPASS SHALL BE PROVIDE.
- 14. A SEPARATE COSTOMERS SHUT OFF VALVE SHALL BE INSTALLED UPSTREAM OF THE VAULT FOR EMERGENCY





NOTES:

FINISHED

SUPPLY







- NOTES: 1. RP MUST BE ABOVE GRADE.
- 2. FREEZE PROTECTION (INSULATED ABOVE GROUND VAULT OR HOT BOX AND REDUNDANT HEAT TAPE)
- IS REQUIRED. 3. AN ABOVE GROUND VAULT (SUCH AS A PRECAST CONCRETE VAULT) MUST BE SIZED TO PROVIDE CLEARANCES SHOWN IN PLAN VIEW. A SPRING LOADED LID IS REQUIRED.
- 4. A HOT BOX LID MUST SWING CLEAR OF BACKFLOW ASSEMBLY TO PROVIDE CLEARANCES IN PLAN VIEW.

RP BACKFLOW PREVENTER (

FROM WATER RELIEF PORT AND TESTCOCKS.

PREVENTION ASSEMBLY.


AT PAD LEVEL FOR DRAINAGE.

5. STOP AND WASTE VALVES ARE NOT TO BE USED BETWEEN THE METER AND THE BACKFLOW

6. ABOVE GROUND VAULTS AND HOT BOX MUST


7. ELECTRICAL SUPPLY SOCKETS MUST BE AWAY

PROVIDE ADEQUATELY SIZED DAYLIGHT DRAINS




HEADWALL NOTES: REFER TO NDOT STANDARD PLANS FOR CONSTRUCTION 2001

- 1. CONCRETE SHALL BE CLASS A OR AA. 2. REINFORCING STEEL SHALL BE DEFORMED BARS WITH MAXIMUM SPACING OF 18" SET 2 1/2" CLEAR OF SURFACE OF CONCRETE EXCEPT AS NOTED. BAR ENDS SHALL BE KEPT 1 1/2" CLEAR OF SURFACE OF CONCRETE. REINFORCING BARS MAY BE CUT AND BENT IN FIELD.
- 3. FOOTINGS SHOWN ARE OF MINIMUM DEPTH AND SHALL BE EXTENDED IF SOIL IS UNSUITABLE OR LIABLE TO SCOUR.
- 4. CULVERT PIPES TO BE SET ON A SKEW SHALL BE MITERED WHEN HEADWALLS ARE CONSTRUCTED. WHEN HEADWALLS ARE NOT CONSTRUCTED THE PIPES SHALL NOT BE MITERED EXCEPT IN OVERFLOW SECTION.



CONCRETE HEADWALL DETAIL




1. AIR RELEASE VALVES SHALL BE INSTALLED OUTSIDE PAVEMENT SECTION WHENEVER POSSIBLE. SLOPE GROUND AWAY FROM VALVE BOX OR CONSTRUCT CURBING TO PROTECT FROM FLOODING BY SURFACE WATERS.


- 2. WHEN CONSTRUCTED IN STREET SECTION, CONSTRUCT AIR RELEASE TUBE TO SIDE OF ROADWAY AND CONSTRUCT "GOOSE-NECK" ABOVE SURROUNDING GRADE AS DIRECTED BY THE WATER UTILITY.
- 3. ALL PIPES SHALL BE SLOPED UP TO AIR RELEASE VALVE. 4. 24" USE: JENSEN N36 PRECAST BOX OR EQUIVALENT.
- >24" USE : JENSEN PRECAST 48" I.D. MANHOLE BARREL OR EQUIVALENT. 5. USE N36-610 STEEL CHECKED PLATE COVER MARKED "WATER" W/ HOLD DOWN BOLTS OR

JENSEN PRECAST 48" I.D. FLAT TOP W/ 36" OPENING AND LID AS REQUIRED


AIR RELEASE VALVE ASSEMBL' NO SCALE

ALL WORKMANSHIP SHALL CONFORM TO LOCAL, STATE, AND NATIONAL CODES AS APPLICABLE.






DRIVEWAY APROACH NO SCALE





 \sim S AIL Ш INCLINE


ICE-PH2




DRAWN BY: **DESIGNED BY:** CHECKED BY: JOB NO.:


APRIL 201

ICE-PH2









- 1. FOR PAVEMENT REPLACEMENT SEE PERMANENT PAVEMENT PATCH DETAIL
- 2. PERMANENT PAVEMENT PATCH WILL BE PLACED IN LIFTS WITH A 2" MINIMUM LIFT THICKNESS AND 3" MAXIMUM LIFT THICKNESS
- 3. ALL ROAD SHOULDERS TO BE COMPACTED TO 95% RELATIVE COMPACTION (NO REVEGETATION REQUIRED)
- 4. WATERMAIN DEPTH MINIMUM OF 40" COVER TO TOP OF PIPE TYPICAL. AREAS WHERE MAIN IS SHALLOW TO MISS CULVERTS OR SEWER LINES THE WATERMAIN SHALL BE CONCRETE ENCASED 10 FEET BEYOND BOTH SIDES OF THE INTERSECTION WITH OTHER UTILITY.
- 5. ALL PROTRUDING ROCKS WILL BE REMOVED PRIOR TO PIPE INSTALLATION.





PRELIMINARY

NOT FOR

CONSTRUCTION









NO SCALE

D6



HORIZONTAL THRUST BLOCK DETAILS



ALL WORKMANSHIP SHALL CONFORM TO LOCAL, STATE, AND NATIONAL CODES AS APPLICABLE.


PHA INCLIN


ICE-PH2

Z

 \geq


D6 APRIL 20 DRAWN BY: **DESIGNED BY:** BAMF **CHECKED BY** ICE-PH2 JOB NO.:






1. CONCRETE COLLAR TO BE 2" BELOW FINISHED ASPHALT SURFACE. PLACE 2" OF TYPE 3 ASPHALT PAVING AROUND VALVE BOX. APPLY SS-1 TACK COAT BEFORE PAVING. SEAL AC SURFACE W/ FOG SEAL OR AS REQ'D BY PLANS OR SPECS.


GATE VALVE DETAIL NO SCALE




TENTATIVE MAP SUBMITTAL

PRELIMINARY






1. FLARED OR COMPRESSION TYPE COUPLINGS TO BE USED AT ALL CONNECTIONS. 2. ALL SERVICE TO BE TYPE K COPPER, SIZE TO MATCH EXISTING SERVICE.



1. NO COUPLINGS TO BE USED BETWEEN MAIN AND CONNECT POINT OUTSIDE OF YOKE. 2. ALL SERVICE TO BE TYPE K COPPER. SIZE TO MATCH EXISTING SERVICE, MINIMUM SIZE TO BE 1".

3. TYPICALLY NEW 1" SERVICE WILL CONNECT TO 3/4" YOKE REQUIRING BRASS REDUCER FITTING. SERVICE CONNECTION - 2" AND SMALLER NO SCALE




1. FLARED OR COMPRESSION-TYPE COUPLINGS TO BE USED AT ALL CONNECTIONS. 2. METER YOKE SHALL BE CENTERED IN METER BOX. CURB STOP IN RISER SHALL BE CENTERED FOR EASY OPERATION.

METER SET INSTALLATION

3. METER SUPPLIED BY OWNER.


NO SCALE



SCALE: N.T.S. NOTES:

LOW-FLOW CHANNEL DETAIL NO SCALE





GENERAL WATER SERVICE NOTES:

- 1. WATER SERVICE LINES SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS SET FORTH IN "IVGID REQUIREMENTS TO CONSTRUCT WATER AND SEWER SERVICE LINES".
- 2. <u>SERVICE LINE REQUIREMENTS</u>: FOR each service line upgrade required per the UniFORm Plumbing Code, each lot shall be serviced by a separate service connection of required size from the IVGID main water line to the water meter Fire service and domestic water service shall use the same main line water tap with separation downstream of the tap by a Tee to a water meter and service line to serve the domestic side. The other line shall continue through an Iron body gate valve with a (2") Two inch operating nut through a District approved backflow prevention device at which point this water line becomes the fire service.
- 3. MATERIALS: Water service lines shall be type K copper tubing or ductile iron pipe, all of which shall conFORm to the UniFORm Plumbing Code and applicable AWWA standards. Polyethylene (PE) polybutyl (PB), or type L or M copper pipe shall not be permitted. PVC C-900 is allowable FOR services 4-inch and larger provided no glued joint are used. If copper is used, service lines two inches in diameter and smaller shall be Type K copper conFORming to ASTM B-88. A one-inch service shall be suitable FOR 32 gpm; 1½—inch service suitable FOR 70 gpm; and 2—inch services suitable FOR 140 gpm. Customer service valve boxes must be Christy G-5 or equivalent concrete box with steel lid marked water. Line sizes are to be commensurate with health standards to ensure that no stagnant water will accumulate. Only silver type solder will be allowed. All soldered or brazed joints must be in accordance with UPC installation standards FOR copper plumbing. Solder spools shall be available FOR inspection. All service line fittings shall be flared mechanical compression type or soldered with non-lead UPC approved solder. FROM MAIN LINE TO METER, ONLY FLARED OR MECHANICAL JOINTS WILL BE ALLOWED.
- 4. <u>CURB STOPS</u>: Curb stops FOR copper service lines shall have AWWA thread inlets and compression connection outlets, and shall be FORd ball valve or Mueller Oriseal 2 or equivalent. Curb stops shall be installed to the downstream side of meter setters, with an appropriate valve key and capped enclosure; waste ports shall not be allowed. Fire service valves shall be iron bodied gate valves with a two (2) inch operating nut and shall be immediately adjacent to the water meter box and in its own riser pipe with approved boxed enclosure with a steel lid marked water the interior shall be marked with a warning tape designating fire line, (available from the District).
- 5. <u>INSTALLATION</u>: Where new connections are made to an IVGID water main, the property owner taping the main will be responsible FOR obtaining Washoe County use permits and FOR cutting pavement and excavating the trench to proper depth and grade. All Water taps are the responsibility of the property owner. IVGID will provide instructions on the specifics of location and methods FOR the tap. Property owner is to lay the pipe to the property line, install curb stop upstream of the meter box, set the meter yoke, box (es), lay service line on private property and install curb stop one to three feet downstream of the meter box with appropriate valve key and capped enclosure. FOR existing services, the District will set the meter within one week of customer request if owner has obtained building permit, paid fees, and installed the proper curb stop with accessories. The District will inspect and approve the construction beFORe backfilling. All trenching must
- 6. <u>CATHODIC PROTECTION</u>: Installation of Cathodic protection is required FOR all water services. A 5-pound "high potential" magnesium anode packaged in chemical backfill with 10 feet of #12 lead wire shall be used. The anode shall be buried at a minimum depth of 48 inches. A bronze or brass clamp shall be used to attach the lead wire to the meter yoke. The anode must be a minimum of 36 inches from the meter yoke, service line or water main. If a locating wire is installed on the water service line, Cathodic protection shall be installed a minimum
- of once every 500 feet and at each intersection in that line. 7. TESTING: The Contractor shall provide all labor, tools, and equipment necessary to perFORm the required tests. Any faulty equipment shall be replaced beFORe any test is accepted. Water main line shall be tested as the following: (Joints x Pipesize x Square Root of pressure Divided by 7400).
- 7.1. Chlorine flush shall be perFORmed after pressure test. First flush at 50 ppm. After 24 hours, second flush at 10 ppm. Following Chlorine flush, Chlorine residual test to be perFORmed.
- 7.2. BacT test shall be perFORmed following the Chlorine Flush. 7.3. All testing to be perFORmed per IVGID specifications.

WORKING DAYS BEFORE YOU DIG CALL USA

ALL WORKMANSHIP SHALL CONFORM TO LOCAL, STATE, AND NATIONAL CODES AS APPLICABLE.

S PHA \circ INCLINE **D7** APRIL 201 DRAWN BY: **DESIGNED BY:** BAMF CHECKED BY:


ICE-PH2


Ŋ

Ш

JOB NO.:

ICE-PH2





DESIGNWORKSHOP

P.O. Box 5666 298 Kingsbury Grade, Suite 5 Stateline, Nevada 89449-5666

GEOTECHNICAL INFORMATION



LETTER OF TRANSMITTAL

TO: Scott Prop	D.	ATE: Octob	er 19, 2015	5	JOB#	6178.002		
Internatio	FF	FROM: Mitch Burns						
17341-A F								
Purcellville	e, VA 2013	2	R	E: Inclin	e Creek Esta	ates Pha	se II	
	vid Scordy							
WE ARE SENDING	i:	Via hand delivery	Pick	c-up X	Via MAIL		Other:	
Shop Drawin	gs	Prints	Plar	ns	Samples		Specification	ns
Copy of lette	r	Change Order	X Fie	eld Reports 8	& Test Resu	lts		
QTY	DATE			DES	CRIPTION			
1 10,	/14/2015	Daily Field Report						
	/14/2015	Soil Field Density Rep	ort					
	/14/2015	Moisture Density Cur						
						7		

	,					7		
LL								
THESE ARE TRANS For approva		s checked below:	Approved	as submitte	ed .		Resubmit fo	or approval
X For your use	е		Approved	as noted			Returned fo	or corrections
For review a	and comme	ent 🗍						
		,	0 17	1 -	7 01	0 0	1-1	0 6
REMARKS: Mio	3			welin ,			The	PKISTING
	ice shu	le se sieni	red, a	noisture	Cence, T.	wit	1 any	
1110	mpick	el.						
COPY TO:								
		RECEIVED / DATE:						
■ 9222 Prototype Dri Reno, NV 89521 Tel 775.827.6111 Fax 775.827.6402	ve	800 East College Pa Carson City, NV 89 Tel 775.883.7077 Fax 775.883.7114		178 South M Fallon, NV 8 Tel 775.423. Fax 775.423	9406 .2188	Sta Tel	Kingsbury teline, NV 8 775.588.64 775.588.64	90



_	DATE: 10-14-15	JOB #: 4148.003)_
	PROJECT: Incline Creek	I OCATION:	
4	WORKING DAY:	OWNER:	Oute 8
LUMOS	CONTRACTOR:	SUPERINTENDENT:	
& ASSOCIATES	WEATHER:	TEMPERATURE:	0 ee
	REPORT NUMBER:	PAGE:	*
- 1 0	1		
Prepared For: Incline Cree	<i>Luc</i> [] Fi	eld Report 🔲 Nonconford	nance Report
		earance of Nonconformanc	e Report
			-
		# 1:30 PM and CON	
		e 100HOW I EVEL of	
		5 were at Finish	
the state of the s	2 +MS year I	gathered a sample of	+NQ
• •	_	of the site to com	pace
the dessities taken	TORM TO.		
Jost Reading	Recurred	Result Samo	
	1,9% 90	93%	
	4.9% 90	8970	
		,	
DEFECTIVE WORK TO BE CORRE	ECTED:		
DEI COLLECTION TO DE CONTRE		,	
INSTRUCTIONS GIVEN OR RECE	IVED:		
VISITORS TO PROJECT:			
	SIGNATURE: CHECH	u_	
		0	

9222 Prototype Drive Reno, NV 89521 Tel 775.827.6111 Fax 775.827.6122

800 E. College Parkway Carson City, NV 89706 Tel 775.883.7077 Fax 775.883.7114

178 S. Maine Street Fallon, NV 89406 Tel 775.423.2188 Fax 775.423.5657

225 Kingsbury Grade, Ste. A Stateline, NV 89449 Tel 775.588.6490 Fax 775.588.6479

TEST Š

SOIL FIELD DENSITY REPORT

Scott Properties

CLIENT:

International Supply Consortium

ATTN: David Scordy

888 |ର|ର|ର|ର|ର|ର 8 SPECIFIED RELATIVE **PACTION** (MIN %) 8 8 104 8 88 94 8 93 83 RELATIVE 8 94 8 93 **PACTION** 100 8 6 8 8 122.0 122.0 122.0 122.0 122.0 122.0 122.0 122.0 125.0 125.0 125.0 MAXIMUM DENSITY bs/cu.ft. ZK 12.5 12.5 10.0 10.0 10.0 10.0 MOISTURE 10.0 OPTIMUM CONTENT 8 17341-A Pickwick Drive 8.8 8.9 9.6 8.3 8.4 8.3 MOISTURE 9.7 IN PLACE CONTENT Purcellville, VA 20132 **Incline Creek Estates** 8 126.4 114.3 120.4 115.7 112.6 114.3 109.5 116.5 114.3 119.7 117.0 IN PLACE DENSITY 6178.002 lbs/cu.ft DRY PROJECT NAME: ELEVATION PROJECT NO.: 1' BFG 4' BFG 1' BFG 3' BFG 3' BFG 4' BFG 3' BFG 3' BFG 3' BFG 8|8|8|8 First Lift Fill, Middle of Upper Area Second Lift Fill 49' West of Silt Fence, 88' North of LCP 507 Second Lift Fill 22' West of Silt Fence, 51' North of LCP 507 Second Lift Fill, 78' Northwest of LCP 507, 96' West of Silt Fence Second Lift Fill, 25' Northwest of LCP 507; 45' West of Silt Fence Second Lift Fill, 68' West of Silt Fence, 34' West of Tree Island 30' West of Tree Island Fence, 75' West of Silt Fence First Lift Fill, Northwest Corner of Low Fill Area First Lift Fill, Northeast Corner of Lower Area 49' Northwest of LCP, 60' West of Silt Fence 12' Northwest of LCP, 53' West of Silt Fence LOCATION 71' North of LCP, 34' West of Silt Fence 87' North of LCP, 54' West of Silt Fence First Lift Fill, South Area UMOS & ASSOCIATES Bottom Level of Site Middle Level of Site 09/03/15 09/03/15 09/02/15 09/02/15 09/02/15 09/02/15 09/03/15 09/03/15 09/04/15 09/04/15 09/04/15 09/04/15 09/04/15 10/14/15 TESTED DATE 9 8 <u>_</u> 13 15 91 10 Ξ

valid for locations expressly set forth in this report. No opinion Testing shown hereon was performed at random intervals and continuous observation was not conducted. Test results are of the material consistency is guaranteed or implied. Prefix "A" = Depth above reference level Shut-down, MOR TO WINKE SAIDTEST

Prefix "B" = depth below reference level

FF = FINISH FLOOR

PG = PAD GRADE

FTG = FOOTING GRADE OG = ORIGINAL GRADE

FG = FINISH GRADE

RG = ROUGH GRADE

NOTE

BC = BASE COURSE

SG = SUBGRADE

☐800 East College Parkway Carson City, NV 89706 Tel 775.883.7077 FG - TOMPOSA FINSL Charle

⊠9222 Prototype Drive

REMARKS:

Reno, NV 89521

Tel 775.827.6111 Fax 775.827.6402

Fax 775.883.7114


☐ 178 South Maine Street Fallon, NV 89406 Tel 775.423.2188 Fax 775.423.5657

☐ 225 Kingsbury Grade, Suite A

Stateline, NV 89449 Tel 775.588.6490 Fax 775.588.6479

LUMOS & ASSOCIATES, INC.

REVISED: 10/19/2015 I:YABYTESTFORM/New FLDN





 ⊠ 800 East College Parkway Carson City, NV 89706 Tel 775.883.7077

Fax 775.883.7114


☐ 178 South Maine Street Fallon, NV 89406 Tel 775.423.2188

Fax 775.423.5657

225 Kingsbury Grade, Suite A Stateline, NV 89449 Tel 775.588.6490 Fax 775.588.6479

SOIL SURVEY

Tahoe Basin Area California and Nevada





United States Department of Agriculture
Soil Conservation Service and Forest Service
In cooperation with
University of California
Agricultural Experiment Station
and the
Nevada Agricultural Experiment Station

C2--48 inches, variegated, very dark grayish-brown (10YR 3/2), grayish brown (10YR 5/2), and white (10YR 8/2) decomposed granitic rock, or

The depth to grus ranges from 36 to more than 60 inches. The O horizon of conifer needles is O to 2 inches thick. The volume of gravel, cobblestones, stones, and boulders ranges from 35 to 65 percent. From 15 to 50 percent of the surface area is covered with stones and boulders. Reaction ranges from medium acid to slightly acid.

The A horizon is grayish brown or brown. The A and C horizons are predominantly gravelly loamy coarse sand, but in some profiles range to gravelly loamy sand. The C horizon is light brownish gray or

pale brown.

Graylock soils are similar to Cagwin and Toem soils, but are deeper over grus and have a larger volume of coarse fragments in the underlying layers.

Graylock extremely stony loamy coarse sand, 30 to 50 percent slopes (GsF) .-- This soil is on uplands. It has the profile described as representative of the series.

About 10 to 15 percent of the total acreage of this soil is inclusions of Cagwin loamy coarse sand, Toem loamy coarse sand, and Rock land.

If this Graylock soil is bare of vegetation, surface runoff is rapid and the erosion hazard is high.

This soil is used mainly for timber and wildlife. Capability subclass VIIs.

Inville Series

The Inville series consists of gently sloping to moderately steep, well-drained soils on alluvial fans, terraces, and flood plains. These soils formed in alluvium and outwash derived from mixed volcanic and granitic parent rocks, of which the dominant rock type is andesite. Slopes are 0 to 30 percent. Elevations are 6,200 to 7,000 feet. The average annual precipitation is 20 to 30 inches, most of which is snow. The average annual air temperature is about 41° F., and the frost-free growing season is 50 to 80 days. The vegetation is coniferous forest and an understory of brush.

In a representative profile the surface layer is brown, medium acid stony coarse sandy loam and gravelly coarse sandy loam 4 inches thick. The subsoil is reddish-brown and brown, medium acid gravelly and cobbly sandy loam 31 inches thick. The substratum is brown, medium acid very gravelly and cobbly loamy

coarse sand.

Roots can penetrate to a depth of more than 60 inches. Available water capacity is 3 to 5 inches. Inville soils are used chiefly for urban develop-

Representative profile: Area of urban development in Incline Village approximately 2,200 feet east and 2,200 feet south of the northwest corner of sec. 15, T. 16 N., R. 18 E.

01--2 inches to 0, litter of conifer needles. All--0 to 1 inch, brown (10YR 4/3) stony coarse sandy loam, very dark brown (10YR 2/2) moist; moderate, fine and medium, granular structure; soft, very friable, nonsticky and nonplastic; few very fine roots; many very fine interstitial pores; 20 percent gravel; medium acid; abrupt, smooth boundary. 1 to 4 inches thick.

Al2--1 to 4 inches, brown (10YR 5/3) gravelly coarse sandy loam, dark brown (10YR 3/3) moist; weak, medium, subangular blocky and moderate, fine, granular structure; soft, very friable, nonsticky and nonplastic; common very fine, fine, and medium roots; many very fine interstitial pores and few very fine tubular pores; 20 percent gravel; medium acid; clear, smooth

boundary. 3 to 5 inches thick.

B1--4 to 10 inches, brown (10YR 5/3) gravelly coarse sandy loam, variegated with about equal amounts of dark brown (10YR 3/3) and dark yellowish brown (10YR 3/4) moist; weak, medium, subangular blocky structure; soft, very friable, nonsticky and nonplastic; many very fine, fine, medium, and coarse roots; many fine interstitial pores and common very fine tubular pores; few thin clay films in pores; 20 percent gravel; medium acid; clear, wavy boundary. 4 to 8 inches thick.

B21t--10 to 26 inches, reddish-brown (5YR 5/3) cobbly and gravelly sandy loam, reddish brown (5YR 4/3) moist; weak, medium, subangular blocky structure; hard, very friable, slightly sticky and slightly plastic; many very fine, fine, medium, and coarse roots; many very fine interstitial pores and common very fine tubular pores; common thin clay films in pores and few thin clay films on ped faces; 25 percent cobblestones and 35 percent gravel; medium acid; clear, wavy boundary. 10 to 20 inches

thick.

B22t--26 to 35 inches, brown (10YR 5/3) cobbly and gravelly sandy loam, brown (10YR 4/3) moist; dark yellowish brown (10YR 4/4) moist clay films; weak, medium and coarse, subangular blocky structure; slightly hard, very friable, nonsticky and nonplastic; few very fine and fine and common medium roots; many very fine interstitial pores and few very fine tubular pores; few thin clay films coating and bridging sand grains; 35 percent gravel and 35 percent cobblestones; medium acid; clear, wavy boundary. 9 to 18 inches thick.

C--35 to 60 inches, brown (10YR 5/3) dry and moist, cobbly and very gravelly loamy coarse sand; massive; soft, very friable, nonsticky and nonplastic; few very fine, fine, and medium roots; many fine and medium interstitial pores; 50 percent gravel and 35 percent cobblestones;

medium acid; 15 to 30 inches thick.

The thickness of the solum ranges from 27 to 45 inches. The 0 horizon of conifer needles is 0 to 2 inches thick. The volume of gravel, cobblestones, stones, and boulders ranges from 15 to 50 percent in

the A horizon and from 35 to 75 percent in the B and C horizons. From 1 to 5 percent of the surface is covered with cobblestones, stones, and boulders.

The A horizon ranges from medium acid to slightly acid, is brown or dark grayish brown, and is dominantly gravelly coarse sandy loam but ranges to gravelly sandy loam or gravelly loamy coarse sand.

The B horizon is predominantly reddish brown but ranges to light reddish brown or brown in hues of 5YR, 7.5YR, and 10YR. It is dominantly gravelly and cobbly sandy loam but ranges to coarse sandy loam or loam.

The C horizon is very gravelly or cobbly loamy coarse sand or coarse sandy loam and ranges widely in color. In some places there is a weakly silica cemented hardpan at a depth of 40 to 68 inches.

Inville soils are similar to Jabu, Elmira, and Meeks soils. They have a larger volume of coarse fragments in the subsoil than Jabu soils. They also have a larger volume of coarse fragments than Elmira soils and are finer textured. They are warmer and finer textured than Meeks soils.

Inville gravelly coarse sandy loam, 0 to 5 percent slopes (IgB) .-- This soil is on glacial outwash terraces. It has a profile similar to the one described as representative of the series, but its surface layer is 15 to 20 percent gravel and less than 1 percent of the surface area is covered with cobblestones and stones. The subsoil extends to a depth of 40 to 68 inches. It ranges from gravelly, cobbly, very gravelly, or very cobbly coarse sandy loam to light sandy clay loam, and by volume is more than 35 percent coarse fragments. It is underlain by a hardpan, weakly cemented with silica, that is very hard to extremely hard in place, but disintegrates under pressure (pl. II, right).
About 5 percent of the acreage of this soil is

Jabu coarse sandy loam, and 5 percent is Jabu coarse

sandy loam, shallow variant.

Even if this Inville soil is bare of vegetation, it has slow runoff and only a slight hazard of erosion. Roots form a mat on top of the hardpan. Permeability is very slow in the pan.

This soil is used chiefly for urban development. Some areas are used for timber. Capability subclass

Inville stony coarse sandy loam, 2 to 9 percent slopes (IsC) .-- This soil is on alluvial fans, terraces, and flood plains. It has the profile described as representative of the series.

Included with this soil in mapping are areas of Cagwin, Jabu, and Umpa soils; and near Incline Village on the shores of Lake Tahoe, areas of Jabu coarse sandy loam, shallow variant.

Runoff is slow to medium on this Inville soil, and the erosion hazard is slight to moderate. Permeability is moderately rapid.

This soil is used chiefly for urban development. Capability subclass IVe.

Inville stony coarse sandy loam, 9 to 15 percent slopes (IsD) .-- This soil is on alluvial fans and

terraces. About 5 percent of the acreage is Jabu coarse sandy loam and Jabu coarse sandy loam, sha variant.

Unless this Inville soil has a protective cove of vegetation, surface runoff is rapid and the er sion hazard is moderate. Limitations are moderat in reestablishing vegetation. Permeability is mo erately rapid.

This soil is used chiefly for urban developmen

Capability subclass IVe.

Inville stony coarse sandy loam, 15 to 30 perc slopes (IsE) .-- This moderately steep or hilly soi is on alluvial fans and terraces.

Included with this soil in mapping are areas of Jabu coarse sandy loam, Elmira gravelly loamy coa sand, and Meeks very stony loamy coarse sand.

Unless this Inville soil has a protective cove of vegetation, surface runoff is rapid and the er sion hazard is high. Limitations are moderate in reestablishing vegetation. Permeability is moder ately rapid.

The principal use of this soil is urban develo

ment. Capability subclass IVe.

Jabu Series

The Jabu series consists of nearly level to mo erately steep, well drained to moderately well drained soils that are about 40 inches deep over dense fragipan. These soils are on glacial outwa terraces. The parent material is mixed, but is p dominantly granitic alluvium. Slopes are 0 to 2 percent. Elevations are 6,200 to 6,900 feet. The average annual precipitation is 25 to 35 inches, average annual air temperature is about 42° F., a the frost-free season is 50 to 80 days. The vege tion is a coniferous forest and an understory of

In a representative profile the surface layer brown, medium acid coarse sandy loam about 6 inch thick. To a depth of about 45 inches, the subsoi is brown and strong-brown, medium acid and strong acid coarse sandy loam and gravelly coarse sandy loam. Below this is a brittle, dense fragipan ov highly weathered, compacted till.

Permeability is moderate in the subsoil and sl in the pan. In spring and early in summer, water moves laterally along the contact between the frag

pan and the compacted till.

Jabu soils are used for homesites, range, and timber.

Representative profile: Wooded area about 5.5 miles south of Bijou, 15 feet north of Fountain Place road, 0.2 mile east of the southwest corner sec. 23, T. 12 N., R. 18 E.

01--1 inch to 0, fir needles.

A1--0 to 2 inches, brown (7.5YR 5/4) coarse sandy loam, dark brown (7.5YR 3/2) moist; weak, thick, platy structure; soft, very friable, nonsticky and nonplastic; many very fine and few fine roots; common very fine interstitia

TABLE 3. -- ESTIMATES OF SOIL PROPERTIES

Corrosion potential of uncoated steel

Shrink-swell potential

Reaction

Available water capacity

Permea-bility

Plastic index

Liquid

200

No. 40

Ho.

30

No.

Atterberg values

SIGNIFICANT IN ENGINEERING--Continued Percentage less than 3 inches passing sieve-- pH value 5.6-6.5

In./in. of

In./hr.

0.03-0.05

6,3-20

NP

HP.

10-20

20-40

50-70

Percen	No. 4		08-09	50-60	65-75	50-90	30-50	75-85	90-100	95-100 95-100 100	90-100	100	95-100	90-100	75-90	45-55			_
	R	nacijanoskel duske	dan punishing in the control of	promision/bi	eto hitomônimes i	Saction physiology	ok prarote confrante (ich			and the forest to the					patrolini spilani				pro-though
Coarse	fragments greater than 3 inches	Pet.		5-0	6-0	15-50	25-50	0-50	0-50	1 1 1 1 1 1		1-5	!	!	1	5-50		***************************************	
	AASHO		A-1	A-1	A-1	A-1	A-1	A-1 or A-2	A-2	A-2 A-6	A-7	A-4 or A-6 A-7	A-2	A-2	A-1 or A-2	A-1		5	2.
Classification	Unifled		SP-SM or SM	GM or GP-GM	SP-SM or SM	SM or SP-SM	GP-GM or GM	SH	WS		NL or NH	or ML	SM	SM or SC	SIM	GP-CM or GM			
Class	USDA texture		Gravelly loamy coarse sand, extremely stony on surface,	98	sandy loam. Cemented gravelly loamy sand.	cobbly	sandy loam. Cobbly and very gravelly loamy sand.	sandy loam ravelly e sandy loam.	Compact loamy coarse sand.		1	and heavy loam. Sandy clay loam.	Coarse sandy loam	0	Compact gravelly coarse sandy loam,	ndy	gravelly loam.		
	Depth from surface	In.	84-0	0+0	40-68	0-35	35-60	0-45	145-66	17-42			0-11	11-44	16-44	†8-0	8		
Depth to	Seasonal high water table	Ft.	(/ī/)	(1)		(1)		(JaC, JaD)	2-3 (JbD)	9-1	7-7)	3-4			(J)		1-2	
De]	Bed. rock	Pt.	3->5	×		χ.		^		>5	ý		V5 Tob	32-5 Ten)	(15 a)	>5		γ.	_
	Soil series and map symbols		Graylock: GaF	Inville:	IBB	IsC, IsD, ISE		Jabu: JaC, JaD, JbD		Jabu, moderately fine subsoil variant:			Jabu, shallow variant:	, , , , , , , , , , , , , , , , , , , ,		Jorge: JtD, JwD, JwE, JwF.	Mapped only with Tahoma soils. For Tahoma part, see Tahoma series.	Loany alluvial land: Lo- No valid estimates can be made. On- site investigation required.	at the section of the

Low (JaC, JaD), moderate (JbD). Moderate (JbD). Low (JaC, JaD).

Low

5.1-5.5

0.06-0.2

NP

E.

15-30

50-70

80-95

Moderate,

Low-----

Low.

Low-----

5.6-6.5 5.6-6.5 5.6-6.5 5.6-6.0

0.07-0.09

0.63-2.0

Η̈́

0.00

NP

N N

10-20 10-15

20-30 35-45 25-50 15-30

40-50

02-09

Low.

Low.

Low----

0.08-0.10 0.03-0.05

0.63-2.0 0.63-2.0

NP

Ę,

10-25 5-20

40-80 25-40

0-5

15-30

Low.

Low-----

Low----

5.1-6.5

0.07-0.09

0.63-2.0

0-5

20-35

20-30

40-50

65-75

Low. Moderate. High.

Low------Moderate----

5.1-6.0

2.0-6.3 0.08-0.10 0.2-0.63 0.16-0.18 <0.06 0.14-0.16

NP 10-15 10-20

15-25 30-40 45-55 15-35 30-40

25-35 60-70 70-85 25-50 35-50 70-85

60-70 70-85 85-95 62-09 60-85 50-60 55-65 40-60 25-35

85-95 95-100 100

4.5-6.5

0,00

5-10 NP

20-30

25-35 25-35

85-95

70-95

20-30 5-15

70-85 40-50

90.0>

Low.

Low-----

5.1-6.5

0.06-0.08

0.63-2.0

ΝP

NP. 랖

Moderate,

Low-----

5.1-6.0

Moderate----

5.6-6.5

10-20 NP-10

80-100

80-95

NP

NP


6.1-6.5

0.63-2.0 0.08-0.10 0.2-0.63 0.15-0.17 2.0-6.3 0.08-0.10

See footnotes at end of table.


TABLE 6.--SOIL RESOURCE INTERPRETATIONS

Residence of the same of the s		Land					Emogt	Degree of limitation for			
Map symbol	Soil name	capa- bility	tive group	logic group	manage- ment group	Erosion hazard	Frost- heave potential	Road location	Excava- tion	Dwellings	
Be CaD	BeachesCagwin-Rock outcrop complex, 5 to 15 percent slopes.	VIIIs VIs	J B	A C	(<u>1</u> /) 303		Slight Moderate-				
CaE	Cagwin-Rock outcrop complex, 15 to 30	VIs	В	С	303	High	Moderate-	Severe	Severe	Severe.	
CaF	percent slopes. Cagwin-Rock outcrop complex, 30 to 50	VIIs	J	С	3r4	High	Moderate-	Severe	Severe	Severe.	
Со	percent slopes. Celio gravelly loamy coarse sand.	IVw	Е	D	3w 7	Slight	Moderate-	Severe	Severe	Severe.	
EbC	Elmira gravelly loamy coarse sand, 0 to 9 percent slopes.	IVs	В	A	303	Slight	Moderate-	Moderate-	Slight	Slight.	
EbE	Elmira gravelly loamy coarse sand, 9 to 30	IVs	В	A	303	Moderate-	Moderate-	Severe	Slight	Severe.	
EcE	percent slopes. Elmira stony loamy coarse sand, 9 to 30	IVs	В	A	303	Moderate-	Moderate-	Severe	Slight	Severe.	
EfB	percent slopes. Elmira-Gefo loamy coarse sands, 0 to 5	IVs	В	A	303	Slight	Moderate-	Moderate-	Slight	Slight.	
Ev .	percent slopes. Elmira loamy coarse sand, wet variant.	IVw	E	D	3w7	Slight	Moderate-	Severe	Moderate-	Severe.	
Fd FuD	Fill landFugawee very stony sandy loam, 2 to 15 percent slopes.	VIs VIs	B G	A C	(<u>1</u> /) 201		Moderate- Severe				
FuE	Fugawee very stony sandy loam, 15 to 30 percent slopes.	VIs	G	С	201	Moderate-	Severe	Severe	Moderate-	Severe.	
GeC	Gefo gravelly loamy coarse sand, 2 to 9	IVs	В	Α	303	Slight	Moderate-	Moderate-	Slight	Slight.	
GeD	percent slopes. Gefo gravelly loamy coarse sand, 9 to 20 percent slopes.	IVs	В	A	303	Moderate-	Moderate-	Moderate-	Slight	Moderate.	
Gr GsF	Gravelly alluvial land- Graylock extremely stony loamy coarse sand, 30 to 50 per-	IVw VIIs	E J	D A	3w7 5x10		Variable- Moderate-				
IgB	cent slopes. Inville gravelly coarse sandy loam, 0 to 5	ΙVe	В	С	302	Slight	Moderate-	Moderate-	Slight	Slight.	
IsC	sandy loam, 2 to 9	I Ve	В	В	302	Slight	Moderate-	Moderate-	Severe	Severe.	
IsD	percent slopes. Inville stony coarse sandy loam, 9 to 15	I Ve	В	В	302	Moderate-	Moderate-	Moderate-	Severe	Severe.	
IsE	percent slopes. Inville stony coarse sandy loam, 15 to 30 percent slopes.	I Ve	В	В	302	Moderate-	Moderate-	Severe	Severe	Severe.	





TAHOE REGIONAL PLANNING AGENCY



Conceptual Drainage Report for

INCLINE CREEK ESTATES – PHASE 2

Prepared for:

NCP/ICP, LLC 264 Village Blvd. Suite 104 Incline Village, NV 89451

Prepared By:

WELSHOCIATES

250 South Rock Blvd., Suite 118 Reno, NV 89502 (775) 853-7776

April 2016

Submitted to:
Washoe County Community Development

Contents Introduction

1. Int	roduction	
1.1.	Project Location	
1.2.	Existing Site Conditions	
1.3	Proposed Project Description	
2. Pre	e-Development Drainage System	2
2.1.	Major Drainage Basins and Drainage area Characteristics:	
2.2.		
3. Pro	posed Drainage System	
3.1.	Precipitation, Basin Properties and Hydrologic Method	4
3.2.	Runoff Analysis	
	Drainage System Capacity	
4. Infi	Itration Facilities	7
	eas within Flood Hazard Zone	
	nclusions	

1. Introduction

This report provides hydrologic and hydraulic analyses for the proposed development, Incline Creek Estates, located in Incline Village, Nevada. The project will be a residential housing development proposed by NCP/ICP, LLC out of Incline Village NV. Existing and proposed drainage conditions will be thoroughly addressed and recommendations will be incorporated into future design of the development. The criteria set forth in the Washoe County Development Code and the Tahoe Regional Planning Agency (TRPA), "Regional Plan for the Lake Tahoe Basin – Code and Ordinances, Rules and Procedures" provide the basis of the content of this report.

1.1. Project Location

The proposed development is located at 800 College Drive in Incline Village, Nevada. The closest major arterial street is Village Blvd, approximately 400 feet to the East and Mt Rose Highway (SR 431) approximately 1,400 feet to the west, see figure 1. *Vicinity Map.* The proposed Development lies within the SW¼ of Section 10, Township 16N, Range 18E, M.D.M., Washoe County, Nevada.

1.2. Existing Site Conditions

The site consists of two parcels totaling 13.77 acres of moderately sloping land within a residential area in the north central portion of Incline Village. Slopes range between 2% and 15% throughout the site. The area is forested with some ground cover vegetation. The site was previously developed as a mobile home park and community college campus. Most of these mobile homes have been removed, but the community college buildings and most of the paved areas remain. Most of the existing utilities have been abandoned in place. Existing drainage conditions north of Rosewood Creek consist of sheet and overland flow in a southerly direction towards the Rosewood Creek drainage which travels from the northwest to the southeast through the site. Existing drainage conditions south of Rosewood Creek consist of sheet and overland flow in a northerly direction towards the Rosewood Creek drainage. No storm drainage infrastructure exists on site. FEMA Flood Insurance rate maps show no flood hazard areas within the site and there are no sump areas that are prone to flooding.

1.3 Proposed Project Description

The development consists of two parcels, APN 129-280-20 and APN 129-280-21, which will be subdivided in two phases. Phase 1, which is the development of APN 129-280-20 and is currently in construction, subdivided the parcel into 58 smaller parcels for single-family residences with one remaining parcel, which contains roadway, utility and drainage infrastructure as well as open area and a stream environment zone (SEZ) corridor. Phase 2, which is the development of APN 129-280-21, will subdivide the parcel into 10 smaller parcels for single-family residences with one remaining parcel, which will contain roadway, utility and drainage infrastructure and a SEZ corridor. Each of the 68 smaller parcels will contain one single-family home with garage. Improvements to the overall development will consist of an SEZ restoration, grading, paved roads and parking, common areas, landscaping, utilities, drainage facilities and installation of best management practices (BMP's).

2. Pre-Development Drainage System

2.1. Major Drainage Basins and Drainage area Characteristics:

The project site is located within the upper Rosewood Creek drainage. Rosewood Creek enters the site in the northwest portion of the site and continues to the southeast until it exits the site and crosses under College Drive in a 36" culvert. The topography of the drainage basin, overall, is moderate to steep with slopes exceeding 50% in the upper reaches. Some areas of Rosewood Creek exceed 20%. Through the proposed site stream slopes range between 2% and 5% and the surrounding slopes are as steep as 15%.

A HEC I analysis was completed by Harding ESE for Rosewood Creek. The study was completed on December 18, 2002 for Incline Village GID for use stream restoration efforts that occurred in the lower reaches of the stream in 2003.

2.2. Sub-basin and Site Drainage Characteristics

Existing storm runoff generated on site for each phase are tabulated below:

Phase 1		Phase 2			
2yr Storm	7.81cfs	2yr Storm	1.20 cfs		
5yr Storm	17.01cfs	5yr Storm	1.82 cfs		
100yr Storm	41.0cfs	100yr Storm	5.54 cfs		

In general, the Phase 1 site (APN 129-280-20 east of Rosewood Creek) receives some runoff via sheet flow and shallow concentrated flow from the property to the north of the site. This area is referred to as Incline Unit I subdivision. Golfer's Pass Road bounds the sub-basin drainage to the north and Rosewood Creek bounds it to the South. Sub-basin runoff travels primarily via sheet and overland shallow concentrated flow from the north, onto and across the site until it joins Rosewood Creek.

In general, the Phase 2 site (APN 129-280-21 and the portion of Apn 129-280-20 west of Rosewood Creek) receives some runoff via sheet flow and shallow concentrated flow from the property to the west of the site. College Drive bounds the sub-basin drainage to the south and Rosewood Creek bounds it to the north. Sub-basin runoff travels primarily via sheet and overland shallow concentrated flow from the south, across the site until it joins Rosewood Creek. On-site, Rosewood Creek is conveyed through a 24" culvert.

The existing conditions for this site consists primarily of impervious coverage. Please refer to the existing coverage map in the appendices prepared for TRPA. It is expected that with the development of the site, peak flows will be reduced.

Previously, the Phase 1 project site was mostly vacant with the remnants of an abandoned mobile home park. Most mobile homes had been removed, however, other improvements such as driveway paving still remained. These improvements have a minor effect on the re-routing of sheet flow and shallow concentrated flow on site.



NCP/ICP, LLC

Incline Village, NV

Currently, the Phase 2 project site is mostly vacant with community college campus buildings and other improvements such as driveway paving and sidewalks still remaining. These improvements have a minor effect on the re-routing of sheet flow and shallow concentrated flow on site.

Historically, site observation suggests that runoff characteristics were similar to their current state. Some modifications have occurred due to the development of the previous mobile home park but this development did little to modify runoff paths beyond redirection of sheet and overland flow around the mobile homes.

3. Proposed Drainage System

3.1. Precipitation, Basin Properties and Hydrologic Method

The Phase 1 project area is part of a slightly larger drainage basin totaling 15.4 acres in area. This basin is tributary to the Rosewood Creek drainage area and is described in the previous section. Phase 1 divided the basin encompassing APN 129-280-20 east of Rosewood Creek into 12 onsite area sub-basins, which are shown in the drainage map provided in the appendices. These sub-basins consist of the upper and lower areas of the on-site roadway and open areas.

The Phase 2 project area is part of a slightly larger drainage basin totaling 2.83 acres in area. This basin is tributary to the Rosewood Creek drainage area and is described in the previous section. Phase 2 divided the basin encompassing APN 129-280-21 and the portion of APN 129-280-20 west of Rosewood Creek into 7 onsite area sub-basins, which are shown in the drainage map provided in the appendices. These sub-basins consist of the upper and lower areas of the onsite roadway and open areas.

Infiltration requirements are set forth in the TRPA Code. The TRPA requires that infiltration facilities be located on site and that the facilities have the capacity to collect and infiltrate the volume of runoff generated by a 20yr, 1hr storm event on all impervious area located on site. This quantity is equivalent to 1" of water over the entire impervious area. Washoe County Code requires that the increase in the 100yr onsite runoff be detained onsite if it cannot be proven that the downstream capacity of stormdrain infrastructure can accommodate the increase. Normally, this requirement would govern when determining detention storage requirements. However, since the quantity of impervious area on site for both Phases 1 and 2 will decrease as a result of development the Washoe County requirement does not apply. It is understood that Washoe County requirements for detention basins are waived in favor of the more strict TRPA guidelines described above. All sub-basins containing impervious drainage areas convey runoff to a TRPA approved infiltration facility.

Areas "A5," "A6," "A7," and "A11" consist of the road areas of the proposed Phase 1 development, and areas "A15," "A16," and "A17" consist of the road areas of the proposed Phase 2 development. Runoff from these areas is collected in catch basins and conveyed via storm drain pipe to proposed infiltration basins and an underground gallery. Area "A9" collects runoff in the immediate vicinity of the upper detention basin where runoff sheetflows to the basin. Area "A8" sheet flows to the SEZ tributary to Rosewood Creek. The remainder of the Sub-basins convey runoff of rooftops to infiltration ditches and any overflow and open area runoff sheetflows to Rosewood Creek. The infiltration basins and the infiltration gallery are equipped with overflow "spillways" which will allow excess runoff generated by larger storms to safely overflow the basins and be conveyed to the Rosewood drainage and off-site.

Roof runoff is collected and stored in dripline infiltration trenches which are located at each building. Each dripline trench is individually sized to collect, store and infiltrate runoff generated by the rooftop of each building.

Design storm intensities were obtained from the NOAA Atlas 14 available at http://hdsc.nws.noaa.gov. The design rainfall intensities are taken as follows based on the time of concentration shown.



3.2. Runoff Analysis

The Rational Method, TR55 (SCS Technical Release 55) and HEC 1 were used to calculate runoff for each of the above sub-basins for Phase 1. TR55 and HEC-HMS were use to calculate runoff for each of the sub-basins for Phase 2. The NOAA precipitation amounts were used for all onsite basins within the project. Design rainfall intensities, as determined above were used to analyze runoff. Storm runoff rates and volumes for each of the areas in Phase 1 are as follows:

Basin	5-yr Storm	100-yr Storm
A1	0.0162 cfs	0.036 cfs
A2	0.48 cfs	1.32 cfs
A3	1.02 cfs	2.58 cfs
A4	1.9 cfs	2.39 cfs
A5	0.49cfs	1.2 cfs
A6	0.72cfs	1.82 cfs
A7	0.8cfs	2.01 cfs
A8	0.18	0.475 cfs
A9	0.59cfs	1.5cfs
A10	0.54cfs	1.37cfs
A11	0.351cfs	0.88cfs
A12	1.5cfs	3.8cfs
Offsite 1	7.56 cfs	21.5 cfs
Rosewood	19 cfs	175 cfs

Storm runoff rates and volumes for each of the areas in Phase 2 are as follows:

Basin	5-yr Storm	100-yr Storm
A13	0.16 cfs	0.40 cfs
A14	0.02 cfs	0.06 cfs
A15	0.40 cfs	0.98 cfs
A16	0.30 cfs	0.75 cfs
A17	0.34 cfs	0.83 cfs
A18	0.54 cfs	1.32 cfs
A19	0.03 cfs	0.07 cfs

The above flows and volumes are used to size and design storm drainage conveyance facilities. Flows for the 5yr storm were not calculated for basins A5 through A8 because runoff of the 5yr storm from the rooftops is infiltrated in dripline trenches and the remainder of the runoff is conveyed via sheet and overland flow with no infrastructure. Due to the reduction of impervious coverage, peak runoff flows actually are reduced by the proposed development.

3.3. Drainage System Capacity

These flows are used to design and size the various storm drainage improvements required. The Sub-basin flows will be used to size curb and gutter as well as stormdrain and the "offsite" and Rosewood flows will be used to size 100yr culvert crossings for the these two SEZ areas. The Rosewood Creek flows were obtained from the Harding ESE Hydrology Analysis for Rosewood



Creek developed in December of 2002. The following lists the capacities of the various conveyance improvements proposed on site.

Curb and Gutter Capacity	24.73 cfs
Valley Gutter Capacity	7.98 cfs
18" Stormdrain	15.98 cfs
24" Stormdrain	48.61 cfs
36" RCP Culvert	143.04 cfs
Rip Rap overflow channel	35.0 cfs

The above flow capacities were calculated using Flowmaster by Haested Methods, an open channel hydrology calculator. These capacities assume an open channel condition. Since the capacities shown above are sufficient for conveying the generated runoff, hydraulic gradelines were not calculated. The above calculations show that the proposed improvements have the capacity to convey and store the design storm runoff flow and volume for the proposed site.

In general, runoff in Area A1 and A3 will be split between three curb & gutter flow paths and 3 stormdrain routings. The 24" stormdrain will provide the overflow for the Infiltration basin. This is sized to handle the peak 100yr overflow. And the 36" RCP culverts are sized to handle 100yr flows for the two SEZ areas. Based on these designs, all improvements on site and downstream should convey the 100yr storm.

4. Infiltration Facilities

Comparison of the peak flows generated by the design storms for both existing and developed conditions show that the peak runoff actually declines as a result of the proposed development. Washoe County Development Code requires that the difference in runoff volume between the developed and existing conditions for a 100yr storm be detained on site. Since the quantity of runoff actually goes down as a result of development, detention is not required by Washoe County.

The TRPA, however, requires that the volume of runoff generated by all impervious areas from a 20yr 1hr storm be detained and infiltrated on site regardless of the existing conditions. For this reason, infiltration basins are required as part of the design. In Phase 1, the total impervious asphalt area for the developed site is 91,138 SF. The quantity of rainfall generated in the 20yr 1hr storm is one inch. The corresponding required detention volume is therefore 7,595 cubic feet. The total available storage in the infiltration basin and the infiltration gallery is 7,150 cubic feet. Subtracting out the infiltration that occurs during the storm, the two basins provide sufficient storage for containing the 20y 1hr storm.

In Phase 2, the total impervious asphalt area for the developed site is 18,680 SF. The quantity of rainfall generated in the 20yr 1hr storm is one inch. The corresponding required detention volume is therefore 1,557 cubic feet. The total available storage in the infiltration basins is 1,708 cubic feet. Subtracting out the infiltration that occurs during the storm, the seven basins provide sufficient storage for containing the 20y 1hr storm.

Both the infiltration Basins and the Infiltration Gallery are designed to infiltrate their detained water within a 24hr period. The underlying soils in the project area are found to be mainly IsC and IsD, both are Inville stony coarse sandy loam. Both soils are hydrologic group "B" which have a permeability that is moderately rapid. Runoff is slow to medium and the erosion hazard is slight to moderate. These soils have a permeability rate of 0.63 to 2.0 inches per hour. See SCS soils information in the appendices.

Based on the above infiltration rates, we used an infiltration rate of one inch per hr to set infiltration basin depths at 2feet. This gives an infiltration time of 24 hrs using the bottom surface only. This time is conservative because the infiltration that occurs on the sideslopes and walls was not taken into account in the calculation.

For Phase 1, the method of release for the detained water in the detention basin is infiltration and a low flow orifice in the overflow riser. The method of release for the infiltration gallery is infiltration.

The infiltration basin is designed for a 20 yr 1 hour storm. Any storm event which exceeds this detention capacity will be conveyed to Rosewood Creek via an emergency overflow. This overflow will consist of an RCP stormdrain pipe sized to convey the 100yr runoff. An additional rip-rapped spillway will be provided to protect surrounding property. HEC 1 analysis shows that during a 100yr event, the detention basin overflow channel will overflow at a depth of approximately 3in, well within the capacity of the channel.



NCP/ICP, LLC

Incline Village, NV

For Phase 2, the method of release for the detained water in the infiltration basins is infiltration and a low flow orifice in the overflow riser.

The infiltration basins are designed for a 20 yr 1 hour storm. Any storm event which exceeds this detention capacity will be conveyed to Rosewood Creek via an emergency overflow. This overflow will consist of a rip-rapped spillway to the roadside swale along College Drive. HEC 1 analysis shows that during a 100yr event, the detention basin overflow channel will overflow at a depth of approximately 3in, well within the capacity of the channel.

Downstream conveyance of runoff is handled by Rosewood Creek. Because the proposed development does not increase either the 5yr or the 100yr stormflows, downstream capacity is not analyzed. Additionally, the Nevada Tahoe Conservation District, in conjunction with Washoe County, is doing a complete watershed assessment of the Rosewood Creek Drainage. This assessment will address the entire reach of Rosewood Creek for all hydrologic and erosional issues.



5. Areas within Flood Hazard Zone

The FEMA Flood Insurance Rate Map dated September 30, 1994, maps special flood hazard areas for Washoe County. This site is determined to be located in community panel No. 32031 C3225E. The entire site is shown to be in Zone X, "areas outside of the 100-year floodplain." This zone is further defined as containing areas of sheet flooding where depths average less than one foot and where the contributing drainage area is less than one square mile. No BFE's or depths are shown in this area.

The Rosewood Creek drainage is shown in this area as being flood Zone A. It is also further defined as completely contained within its streambanks.

No impacts to onsite or downstream properties are expected.

No special protection is required

The design of this project should comply with FEMA requirements and article 416, Flood Hazards, of the Washoe County Development Code.



Incline Village, NV

6. Conclusions

The offsite runoff can be conveyed through the site safely without any adverse impacts to the property or downstream. On site runoff generated from impervious areas will be detained and infiltrated on site. The volume of this runoff will correspond to that generated by a 20 yr 1 hr storm as required by the TRPA.

The design of this development is intended to comply with the requirements of the Washoe County Development Code and the TRPA. All drainage and water quality facilities are designed to comply with Section 25.5 of the TRPA Code of Ordinances for Best Management Practices.

Development of this project will serve as an overall benefit to water quality and flood safety. Any negative impacts will be mitigated.



NCP/ICP, LLC

April 2016 Incline Village, NV

APPENDICES

100 ICE-PH2 WELSHAZHAGEN Associates Engineering Planing-surveying 250 S. Rock Blvd. - Suite 118 Reng, Novada 89502 7 AREA A18 46,651 SF Q5yr=0.54CFS WATERSHED AREAS EXHIBIT for INCLINE CREEK ESTATES PHASE FT=30.75 / 61 (B) 62 (8) Q100yr=1.32CFS AREA A13 64 (B) 30,010 SF Q5yr=0.16CFS 65 (B) Q100yr=0.40CFS AREA A19 11,866 SF AREA A15 7,023 SF Q5yr=0.40CFS Q100yr=0.98CFS ff=40 68 (A) Q5yr=0.03CFS Q100yr=0.07CFS AREA A16 AREA A17 5,910 SF Q5yr=0.34CFS Q100yr=0.83CFS 5,195 SF Q5yr=0.30CFS Q100yr=0.75CFS AREA A14 16,615 SF Q5yr=0.02CFS <u>k</u> GRAPHIC SCALE
SCALE IN FEET Q100yr=0.06CFS **WSA EX** DATE: DRAWN BY: DESIGNED BY: CHECKED BY; JOB NO.; MARCH 2018 BAMF BAMF DLH (CE-PH2 **PRELIMINARY** NOT FOR CONSTRUCTION

SURVEYOR CERTIFICATE

- I, STEVEN N. BELL, A PROFESSIONAL LAND SURVEYOR, REGISTERED IN THE STATE OF NEVADA CERTIFY:
- 1) THIS IS A TRUE AND ACCURATE REPRESENTATION OF THE LANDS SURVEYED UNDER MY SUPERVISION AT THE INSTANCE OF INCLINE CREEK, LLC.
- 2) THE LANDS SURVEYED LIE WITHIN THE SW 1/4 OF SECTION 10, TOWNSHIP 16 NORTH, RANGE 18 EAST, M.D.B.& M., WASHOE COUNTY, NEVADA AND THE SURVEY WAS COMPLETED ON 3) THIS PLAT COMPUES WITH THE APPLICABLE STATE STATUTES AND ANY LOCAL ORDINANCES IN EFFECT ON THE DATE THE GOVERNING BODY GAVE ITS FINAL APPROVAL.
- 4) THE MONUMENTS SHOWN ON THE PLAT WILL BE OF THE CHARACTER SHOWN AND OCCUPY THE POSITIONS INDICATED BY MICHARD PROPERTY OF THE MONTH PROPERTY OF THE MONTH OF THE MOVIMENTS.
 THE GOVERNING BODY BEFORE RECORDATION TO ENSURE THE INSTALLATION OF THE MOVIMENTS.

STEVEN N. BELL, P.L.S. 11420



OWNER CERTIFICATE

THIS IS TO CERTIFY THAT THE UNDERSIGNED, INCLINE CREEK, LLC, IS THE OWNER OF THE TRACT OF LAND REPRESENTED ON THIS PLAT AND HAS CONSENTED TO THE PREPARATION AND RECORDATION OF THIS PLAT AND THAIT THE SAME IS EXECUTED IN COMPILANCE WITH AND SUBJECT TO THE PROVISIONS OF N.R.S. CHAPTER 278 AND 118, AND THAT THE PRIVATE ROADWAY EASEMENT AND ALL APPURTENANCES THERETO AS SHOWN ARE HERBY GRANTED AND SET APART TO BE USED AS PRIVATE THOROUGHFARES FOREYER, AND HERBY GRANTE OF ALL PUBLIC UTILITIES A BLANKET EASEMENT FOR THE CONSTRUCTION AND MAINTENANCE OF ALL REQUIRED PUBLIC UTILITIES TOCETHER WITH THE RIGHT OF ACCESS THERETO FOREYER OVER THE COMMON AREA SHOWN ON THIS MAP. THE OWNERS AND ASSOCIATED AGREE TO THE USE OF RESIDENTIAL WATER METERS. THE WATER AND SEVER FACILITIES AND ASSOCIATED APPURTENANCES ARE HERBY DEDICATED TO INCLINE VILLAGE GENERAL IMPROVEMENT DISTRICT.

INCLINE VILLAGE, LLC
BY: ROGER WHITTENBERG, MANAGING PARTNER

DATE

COUNTY OF WASHOE STATE OF NEVADA **}** S.S.

ON ______PERSONALLY APPEARED BEFORE ME, A NOTARY PUBLIC, ROGER WHITTENBERG WHO IS MANAGING PARTNER OF INCLINE NILAGE, ILC.
PERSONALLY APPEARED BEFORE ME AND ACKNOWLEDGED TO ME THAT HE DECUTED THE ABOVE INSTRUMNET, IN WITNESS THEREOF I HERETO SET MY HAND AND AFFIX MY OFFICIAL SEAL.

NOTARY PUBLIC MY COMMISSION EXPIRES:


STATE DIVISION OF WATER RESOURCES CERTIFICATE
THIS PLAT IS APPROVED BY THE DIVISION OF WATER RESOURCES OF THE DEPARTMENT OF
CONSERVATION AND NATURAL RESOURCES CONCERNING WATER QUANTITY SUBJECT TO THE
REVIEW OF APPROVAL ON FILE IN THIS OFFICE.

BY: DIVISION OF WATER RESOURCES

DATE

NEVADA DIVISION OF ENVIRONMENTAL PROTECTION THIS FINAL MAP IS APPROVED BY THE NEVADA DIVISION OF ENVIRONMENTAL PROTECTION OF THE DEPARTMENT OF CONSERVATION AND NATURAL RESOURCES. THIS APPROVAL CONCERNS SEWICE DISPOSAL WHERE POLLUTION, WATER QUALITY AND WATER SUPPLY FACULTIES AND IS PREDICATED UPON PLANS FOR A PUBLIC WATER SUPPLY AND A COMMUNITY SYSTEM FOR DISPOSAL OF SEWICE.

NEVADA DIVISION OF ENVIRONMENTAL PROTECTION, BUREAU OF VATER POLLUTION CONTROL DATE



INCLINE VILLAGE GENERAL

IMPROVEMENT DISTRICT CERTIFICATE

THE DISTRICT HEREBY CERTIFIES THAT IT HAS REVIEWED THE MAP SHOWN HEREON, AND WATER AND/OR SEWER SYSTEMS ARE PRESENTLY AVAILABLE AND CONNECTION THERETO WOULD BE ALLOWED UPON PROPER PAPICATION, APPROVAL AND PAYMENT OF APPLICABLE FEES, THIS CERTIFICATION IS SUBJECT TO: 1.) THE AVAILABILITY OF WATER RIGHTS AND ACTIONS BROUGHT IN OPPOSITION TO THOSE WATER RIGHTS, 2.) THE AVAILABILITY OF THE DISTRICT'S WATER RECLAMATION FACILITIES. OPERATION AND MAINTENANCE OF THE WATER AND SEWER SYSTEM ON THE PROPERTY OF THE CONNECTION TO THE INGID MAIN SHALL BE THE RESPONSIBILITY OF THE HOMEOWNERS ASSOCIATION.

JOSEPH J. POMROY P.E., ENGINEERING MANAGER

DATE

TAHOE REGIONAL PLANNING AGENCY CERTIFICATE

THIS FINAL MAP CONFORMS TO TAHOE REGIONAL PLANNING AGENCY REQUIREMENTS.

DATE

WE, THE UNDERSIGNED PUBLIC UTILITIES, ACCEPT AND APPROVE THE PUBLIC UTILITY EASEMENTS AS SHOWN ON THIS PLAT. THIS APPROVAL DOES NOT GUARANEE ACCESSIBILITY FOR SERVICE. TILITY COMPANIES' CERTIFICATE

NV ENERGY

NEVADA BELL TELEPHONE COMPAN' D.B.A., AT&T NEVADA

BY:

WELSH SHAFEN AGEN
ASSOCIATES
ENGREDRO-PLANNING-SUPPETING
2013 LOACH SHA-SSEELES
Reno, Neverda 20202

Drawn By: BELL
Date: 3-3-16
Job: (CE2016
Drawing:: ICE Final Map.dwg

COUNTY RECORDER

TITLE COMPANY CERTIFICATE

THE UNDERSIGNED HEREBY CERTIFIES THAT THIS PLAT HAS BEEN EXAMINED AND THAT INCLINE VILLAGE, LOC, A NEWADA LIMITED THE COMPANY, OWNS OF RECORD OF THE CANDD HAVE SIGNED THE FINAL MAP: THAT NO ONE HOLDS OF RECORD OF THE LAND HAVE SIGNED THE FINAL MAP: THAT NO ONE HOLDS OF RECORD A SECURITY INTEREST IN THE LANDS TO BE REVERTED AND THAT THERE ARE NO LIENS OF RECORD AGAINST THE LANDS DELINEATED HEREON FAR DELINQUENT STATE, COUNTY, MUNICIPAL, FEDERAL, OR LOCAL, TAKES OR ASSESSMENTS COLLECTED AS TAKES OR SPECIAL ASSESSMENTS, AND THAT A GUARANTEE DATED:

FOR THE BENEFIT OF THE COUNTY OF MASSIVE, STATE OF NEVADA, HAS BEEN ISSUED WITH RECARD TO THE ABOVE.

SIGNED	
DATE	
•••	

TILE COMPANY

TAX CERTIFICATE

THE UNDERSIGNED HEREBY CERTIFIES THAT ALL PROPERTY TAXES ON THIS LAND FOR THE FISCAL "FLAR HAVE BEEN PAID AND THAT THE FULL AMOUNT OF ANY DEFERRED PROPERTY TAXES FOR THE CONVERSION OF THE PROPERTY FROM ASSICULTURAL USE HAS BEEN PAID PURSUANT TO N.R.S. 361A.285.

VASHOE COUNTY TREASURER

DATE TA

COMMUNITY DEVELOPMENT CERTIFICATE
THE TENTATIVE MAP OF THE AMENDED MAP FOR THE PURPOSE OF MERGER AND
RESUBDIVISION OF INCLINE VILLAGE ESTATES WAS APPROVED BY THE WASHOE COUNTY
PLANNING COMMISSION ON

THIS FINAL MAP MEETS ALL APPLICABLE STATUTES, ORDINANCES, AND CODE PROVISIONS; IS IN SUBSTANTIAL CONFORMANCE WITH THE TENTATIVE MAP AND ALL CONDITIONS HAVE BEEN MET.

THIS FINAL MAP IS APPROVED AND ACCEPTED FOR RECORDATION THIS OF COUNTY DIVIDING THE WASHOE COUNTY COMMUNITY DEVELOPMENT DIRECTOR.

ADRIAN P. FREUND, AICP COMMUNITY DEVELOPMENT DIRECTOR

DATE

COUNTY SURVEYOR S CERTIFICATE

CERTIFY THAT I HAVE EXAMINED THIS PLAT CONSISTING OF SIX SHEETS, AND THAT I AM SATISTIED SAID MAP IS TECHNICALLY CORRECT AND THAT THE MONUMENTS AS SHOWN WILL BE SET BY


BY: WASHOE COUNTY SURVEYOR DATE

2016 AMENDED SUBDIVISION MAP FOR THE PURPOSE OF MERGER AND RESUBDIVISION SHEET 1 OF 6

INCLINE CREEK ESTATES, TRACT MAP 4526 AND GRANT DEED DOC. #3649640 A PORTION OF THE SW 1/4 OF SECTION 10
Y T.16 N., R.18 E., M.D.B.& M. INCLINE CREEK, LLC

IN THE OFFICIAL RECORDS OF WASHOE COUNTY, NEVADA

FILE NO.
FILED FOR RECORD AT THE REQUEST OF INCLINE CREEK, LIC.
ON THIS _____DAY OF ______





Community Development

"Dedicated to Excellence in Public Service"

Adrian P. Freund, AICP, Community Development Director



ACTION ORDER

January 16, 2008

Incline Creek Estates, LLC Attn: Sloan Gordon P.O. Box 6039 Incline Village, NV 89450

Dear Applicant:

As filed with the Department of Community Development, the Washoe County Planning Commission, at its regular meeting of January 02, 2008, approved the following with seventy-five (75) conditions.

TENTATIVE SUBDIVISION MAP CASE NO. TM07-006 (MERGER OF TWO PARCELS: INCLINE CREEK ESTATES PHASE 2) — To merge a 1.64-acre parcel (former Mountain Campus, Sierra Nevada College) (APN: 129-280-21) with the 8.61-acre existing common open space parcel (APN: 129-290-01) of Incline Creek Estates and subdivide the merged area into 10 new single-family dwelling units and common open space. The 58 existing lots within Incline Creek Estates will not be affected by this action. The project is located at 800 College Drive between State Route 431 and Village Boulevard in Incline Village. In addition, to realign a portion of the existing access for Incline Creek Estates. Rosewood Circle will be realigned to intersect with College Drive and Lucille Drive. The proposed merged ±10.25-acre project area is designated Low Density Urban in the Tahoe Area Plan, and is situated in a portion of Section 10, T16N, R18E, MDM, Washoe County, Nevada. The property is located in the Incline Village/Crystal Bay Citizen Advisory Board boundary and Washoe County Commission District No. 1. (APN 129-280-21 and APN 129-290-01)

The approval of the tentative subdivision map was based on the following findings:

- 1. <u>Plan Consistency.</u> That the proposed map is consistent with the Comprehensive Plan and the Tahoe Area Plan;
- 2. <u>Design or Improvement.</u> That the design or improvement of the proposed subdivision is consistent with the Comprehensive Plan, and the Tahoe Area Plan;
- 3. <u>Type of Development.</u> That the site is physically suited for an additional 10 lot subdivision within a Common Open Space Development;
- 4. <u>Availability of Services.</u> That, as conditioned, the subdivision will meet the requirements of Article 702, Adequate Public Facilities Management System:
- 5. <u>Fish or Wildlife.</u> That neither the design of the subdivision nor any proposed improvements, is likely to cause substantial environmental damage, or substantial and avoidable injury to any endangered plant, wildlife or their habitat:

Incline Creek Estates, LLC

Subject:

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page:

2

- 6. <u>Public Health.</u> That the condominium concept/design is not likely to cause significant public health problems;
- Easements. That the design of the subdivision or the type of improvements will not conflict with easements acquired by the public at large for access through, or use of property within, the proposed subdivision;
- Access. That the design of the subdivision provides any necessary access to surrounding, adjacent lands and provides appropriate secondary access for emergency vehicles;
- Dedications. That any land or improvements to be dedicated to the County is consistent with the Comprehensive Plan;
- 10. <u>Energy.</u> That the design of the subdivision provides, to the extent feasible, for future passive or natural heating or cooling opportunities in the subdivision; and
- 11. That the Planning Commissioners gave reasoned consideration to the information contained within the staff report and information received during the meeting.

Unless appeals are filed in the time period stipulated in the Washoe County Development Code, the decision by the Planning Commission is final.

Yours truly.

Adrian P. Freund, AICP

Director and Secretary to the Planning Commission

APF/DM/cm (TM07-006F1)

xc: Blaine Cartlidge, Esq., District Attorney's Office; Marge Clausen, Assessor's Office (CAAS); Theresa Wilkins, Assessor's Office; David Lindsey, Water Resources; Engineering Division; Incline Village/Crystal Bay Advisory Board, ChairNorth Lake Tahoe Fire Protection District; 866 Oriole Way, Incline Village, NV 89451; Engineering Division; Nevada Division of Environmental Protection, 333 West Nye Lane, Suite 138, Carson City, NV 89706; Incline Village General Improvement District, 893 Southwood Boulevard, Incline Village, NV 89451

Incline Creek Estates, LLC

Subject:

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page:

3

STANDARD CONSIDERATIONS FOR SUBDIVISIONS Nevada Revised Statutes 278.349

Pursuant to NRS 278.349, when contemplating action on a tentative subdivision map, the governing body, or the planning commission if it is authorized to take final action on a tentative map, shall consider:

- (a) Environmental and health laws and regulations concerning water and air pollution, the disposal of solid waste, facilities to supply water, community or public sewage disposal and, where applicable, individual systems for sewage disposal;
- (b) The availability of water which meets applicable health standards and is sufficient for the reasonably foreseeable needs of the subdivision;
- (c) The availability and accessibility of utilities;
- (d) The availability and accessibility of public services such as schools, police and fire protection, transportation, recreation and parks;
- (e) Conformity with the zoning ordinances and master plan, except that if any existing zoning ordinance is inconsistent with the master plan, the zoning ordinance takes precedence;
- (f) General conformity with the governing body's master plan of streets and highways;
- (g) The effect of the proposed subdivision on existing public streets and the need for new streets and highways to serve the subdivision;
- (h) Physical characteristics of the land such as floodplain, slope and soil; and
- (i) The recommendations and comments of those entities reviewing the tentative map pursuant to NRS 278.330 and 278.335.
- (j) The availability and accessibility of fire protection, including, but not limited to, the availability and accessibility of water and services for the prevention and containment of fires, including fires in wild lands.

Incline Creek Estates, LLC

Subject

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page:

Α

CONDITIONS FOR TENTATIVE SUBDIVISION MAP CASE NO. TM07-006 FOR INCLINE CREEK ESTATES PHASE 2 (As Approved by the Washoe County Planning Commission on January 2, 2008)

IMPORTANT — PLEASE READ

<u>INSTRUCTIONS</u>

THE TENTATIVE MAP APPROVAL ALLOWS THE SUBDIVIDER TO PROCEED WITH FULFILLING THE CONDITIONS OF APPROVAL AND RECORD A FINAL MAP FOR ALL, OR PORTIONS OF, THE DEVELOPMENT WITHIN TWO (2) YEARS FROM THE DATE OF THE PLANNING COMMISSION ACTION. FAILURE TO RECORD THE FIRST FINAL MAP WITHIN TWO (2) YEARS OF THE PLANNING COMMISSION ACTION, OR FAILURE TO RECORD THE LATEST MAP IN A SERIES WITHIN ONE (1) YEAR AFTER THE DATE OF THE MOST RECENTLY RECORDED MAP, SHALL TERMINATE ALL PROCEEDINGS CONCERNING THE SUBDIVISION.

UNLESS OTHERWISE STATED, PRIOR TO FINALIZATION OF ANY PORTION OF THE TENTATIVE SUBDIVISION MAP, ALL CONDITIONS MUST BE MET OR FINANCIAL ASSURANCES TO ENSURE COMPLETION OF THE CONDITIONS MUST BE PROVIDED. THE AGENCY RESPONSIBLE FOR DETERMINING COMPLIANCE WITH A SPECIFIC CONDITION SHALL DETERMINE WHETHER THE CONDITION MUST BE FULLY COMPLETED OR WHETHER THE APPLICANT SHALL BE OFFERED THE OPTION OF PROVIDING FINANCIAL ASSURANCES.

A COPY OF ALL AGREEMENTS, EASEMENTS OR OTHER DOCUMENTATION REQUIRED BY THESE CONDITIONS SHALL BE FILED WITH THE DEPARTMENT OF PUBLIC WORKS AND/OR THE DEPARTMENT OF COMMUNITY DEVELOPMENT.

THE DEVELOPER SHALL MEET WITH THE ENGINEERING DIVISION, DEPARTMENT OF WATER RESOURCES AND THE DEPARTMENT OF COMMUNITY DEVELOPMENT STAFF AT LEAST SIXTY (60) DAYS BEFORE THE ANTICIPATED DATE OF THE FINAL MAP RECORDATION TO REVIEW SCHEDULING, REQUIREMENTS, FINAL CONSTRUCTION DRAWINGS, AND DOCUMENTATION NECESSARY TO ADEQUATELY COMPLY WITH THE CONDITIONS OF APPROVAL AND THE APPLICABLE STATUTES, ORDINANCES, RULES, REGULATIONS AND POLICIES.

REQUESTS FOR EXTENSION OF TIME FOR SUBSEQUENT FINAL MAPS MUST BE SUBMITTED TO THE DEPARTMENT OF COMMUNITY DEVELOPMENT AT LEAST SIXTY (60) DAYS PRIOR TO THE EXPIRATION DATE OF THE TENTATIVE SUBDIVISION MAP.

COMPLIANCE WITH THE APPLICABLE STATUTES, ORDINANCES, RULES, REGULATIONS AND POLICIES AND WITH THE CONDITIONS OF APPROVAL OF THIS TENTATIVE MAP IS THE RESPONSIBILITY OF THE DEVELOPER, ITS SUCCESSOR IN INTEREST, AND ALL OWNERS, ASSIGNEES AND OCCUPANTS OF THE PROPERTY, AND THEIR SUCCESSORS IN INTEREST.

Incline Creek Estates, LLC

Subject:

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page:

A COPY OF THE FINAL ORDER FOR THE APPROVAL OF THE TENTATIVE MAP SHALL BE ATTACHED TO ALL PHASES/UNITS SUBMITTALS FOR FINAL MAP REVIEW SIXTY (60) DAYS PRIOR TO RECORDATION.

GENERAL CONDITIONS

COMMUNITY DEVELOPMENT

1.	The applicant/developer shall comply with all requirements of the Incline Village Commercial Community Plan of the Tahoe Area Plan in addition to all applicable code requirements of the Washoe County Development Code. The Department of Community Development shall determine compliance with this condition.
Final	Map Verification: Phase/Unit No.: Date Submitted:
When	e/How Condition is Satisfied:
	The subdivider shall present to Washoe County, a final map, prepared in accordance with the tentative map, for the entire area for which a tentative map has been approved, or one of a series of final maps, each covering a portion of the approved tentative map, within two years after the date of approval of the tentative map or within one year of the date of approval for subsequent final maps. On subsequent final maps, that date may be extended by one year if the extension request is received prior to the expiration date. Map Verification: Phase/Unit No.: Date Submitted:
******	e/How Condition is Satisfied:
3.	Final maps shall be in compliance with all plans and documents submitted with and made part of this tentative map request, as may be amended by action of the final approving authority. Compliance shall be determined by the applicable agency and the Department of Community Development.
	Map Verification: Phase/Unit No.: Date Submitted:

A note shall be placed on all grading plans and construction drawings stating: 4.

NOTE

Should any prehistoric or historic remains/artifacts be discovered during site development, work shall temporarily be halted at the specific site and the State Historic Preservation Office of the Department of Museums, Library and Arts, shall be notified to record and photograph the site. The period of temporary delay shall be limited to a maximum of two (2) working days from the date of notification.

Incline Creek Estates, LLC

Subject:

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page:

6

The Department of Community Development shall be responsible for determining compliance with this condition. Final Map Verification: Phase/Unit No.: _____ Date Submitted: _____ Where/How Condition is Satisfied: The final map shall designate faults that have been active during the Holocene epoch of 5. geological time and the final map shall contain the following note: NOTE No habitable structures shall be located on a fault that has been active during the Holocene epoch of geological time. The Department of Community Development shall determine compliance with this condition. Final Map Verification: Phase/Unit No.: _____ Date Submitted: _____ Where/How Condition is Satisfied: 6. The developer and all successors shall direct any potential purchaser of the site to meet with the Department of Community Development to review conditions of approval prior to the final sale of the site. Any subsequent purchasers of the site shall notify the Department of Community Development of the name, address, telephone number and contact person of the new purchaser within thirty (30) days of the final sale. Phase/Unit No.: _____ Date Submitted: _____ Final Map Verification: Where/How Condition is Satisfied: _____ 7. All existing overhead utility lines shall be placed underground, except electric transmission lines greater than 100 kilovolts, which can remain above ground. The County Engineer shall determine compliance with this condition. Final Map Verification: Phase/Unit No.: _____ Date Submitted: _____ Where/How Condition is Satisfied: 8. The tentative map approval is based on all units being single-family residences. Any changes to the number of units in the development shall require a new tentative map. Phase/Unit No.: _____ Date Submitted: _____ Final Map Verification: Where/How Condition is Satisfied: _____

Incline Creek Estates, LLC

Subject:

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page:

CONDITIONS, COVENANTS AND RESTRICTIONS

- 9. Conditions, covenants, and restrictions (CC&Rs), including any supplemental CC&Rs, shall be submitted to the Community Development staff with all CC&R articles in which the County has interest duly marked, for review and subsequent forwarding to the District Attorney for review and approval. The CC&Rs shall be marked to indicate the page and paragraph of each of the items below or any conditions referencing CC&Rs. The final CC&Rs shall be signed and notarized by the owner(s) and submitted to the Community Development Department with the recordation fee prior to the recordation of the final map. The CC&Rs shall require all phases and units of the subdivision approved under this tentative map to be subject to the same CC&Rs. Washoe County shall be made a party to the applicable provisions of the CC&Rs to the satisfaction of the District Attorney's Office. Said CC&Rs shall specifically address the potential for liens against the properties and the individual property owners' responsibilities for the funding of maintenance, replacement, and perpetuation of the following items, at a minimum:
 - a. Maintenance of public access easements, common areas, and common open spaces. Provisions shall be made to monitor and maintain, for a period of three (3) years regardless of ownership, a maintenance plan for the common open space area. The maintenance plan for the common open space area shall, as a minimum, address the following:
 - b. Vegetation management;
 - c. Watershed management;
 - d. Debris and litter removal:
 - e. Fire access and suppression;
 - f. Maintenance of public access and/or maintenance of limitations to public access.
 - g. All drainage facilities and roadways not maintained by Washoe County shall be privately maintained and perpetually funded by the property owners association.
 - h. All open space identified as common area on the final map shall be privately maintained and perpetually funded by the property owners association. The maintenance of the common areas and related improvements shall be addressed in the CC&Rs to the satisfaction of the District Attorney's Office.
 - The project, if adjacent to undeveloped land, shall maintain a fire fuel break of a minimum 30 feet in width until such time as the adjacent land is developed.
 - j. Locating habitable structures on potentially active (Holocene) fault lines, whether noted on the recorded map or disclosed during site preparation, is prohibited.
 - k. All outdoor lighting on buildings and streets within the subdivision shall be down-shielded.

Incline Creek Estates, LLC

Subject:

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page:

8

- Washoe County will not assume responsibility for maintenance of the private driveway/aisle system of the development nor will Washoe County accept the driveway/aisle for dedication to Washoe County.
- m. Mandatory solid waste collection.
- n. Fence material, height, and location limitations, and re-fencing standards. Replacement fence must be compatible in materials, finish and location of existing fence. (if applicable)
- o. The common open space owned by the property owner's association shall be noted on the final map as "common open space" and the related deed of conveyance shall specifically provide for the preservation of the common open space in perpetuity. The deed shall be presented with the CC&Rs for review by the Community Development staff and the District Attorney, prior to the recordation of the first final map.

Final Map Verification:	Phase/Unit No.:	 Date Submitted:	
Where/How Condition is	Satisfied:		
			The Principle Control of the Control

LANDSCAPING AND COMMON OPEN SPACE

- 10. Prior to any ground disturbing activity or finalization of a final map, the developer shall submit a landscaping/architectural design plan to the Department of Community Development for review and approval by the Design Review Committee. Said plan shall address, but not be limited to: fencing, landscaping material, type and color of building material, general architectural design, (if plant material: type, size at time of planting, maturation size at full growth, period of time between planting and full growth), landscaping location, landscaping irrigation system, and financial assurances that landscaping will be planted and maintained. All landscaping must conform to Washoe County Development Code requirements. The following shall also apply:
 - a. If a new architectural design is brought forward that is different from Phase 1, this too shall be reviewed by the Design Review Committee.

Final Map Verification: Phase/Unit No.: Date Submitted:					
Where/How Condition is Satisfied:					

A certification letter or series of letters by a landscape architect registered in the State of Nevada shall be submitted to the Department of Community Development. The letter(s) shall certify that all applicable landscaping provisions of Articles 408, 410 and 412 of the Development Code have been met. Any landscaping plans and the letter shall be wetstamped.

Incline Creek Estates, LLC

Subject:

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page:

12. The letter shall indicate any provisions of the code that the Director of Community Development has waived. The Department of Community Development shall be responsible for determining compliance with this condition.

	Map Verification: re/How Condition is	Phase/Unit No.: Satisfied:	Date Submitted:
13.	by the property of determining composhall be addressed	all common areas sha owners association. diance with this condi ed in the CC&Rs.	e identified as common. A note on the final map il be privately maintained and perpetually funded The County Engineer shall be responsible for tion. The maintenance of the common areas The District Attorney's Office and Community or determining compliance with this condition.
	Map Verification: e/How Condition is S		Date Submitted:

GENERAL ENGINEERING DIVISION CONDITIONS

Compliance with the following conditions shall be determined by the County Engineer.

General Conditions:

- 14. Final maps and final construction drawings shall comply with all applicable statutes, ordinances, rules, regulations, and policies in effect at the time of submittal of the tentative map or, if requested by the developer and approved by the applicable agency, those in effect at the time of approval of the final map.
- 15. Prior to acceptance of public improvements and release of any financial assurances, the developer shall furnish to the water and sewer provider(s) and Engineering Division a complete set of reproducible as-built construction drawings prepared by a civil engineer registered in the State of Nevada.
- 16. The developer shall be required to participate in any applicable General Improvement District or Special Assessment District formed by Washoe County. The applicable County Department shall be responsible for determining compliance with this condition.
- 17. The developer shall provide written approval from the U.S. Postal Service concerning the installation and type of mail delivery facilities. The system, other than individual mailboxes, must be shown on the project construction plans and installed as part of the onsite improvements. The County Engineer shall determine compliance with this condition.
- 18. All open space shall be identified as common area on the final map. A note on the final map shall indicate that all common areas shall be privately maintained and perpetually

Incline Creek Estates, LLC

Subject:

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page:

10

funded by the Homeowners Association. The County Engineer shall determine compliance with this condition. The maintenance of the common areas shall also be addressed in the CC&Rs to the satisfaction of the District Attorney's Office.

- 19. Any existing easements or utilities that conflict with the development shall be relocated, quitclaimed, and/or abandoned, as appropriate. The County Engineer shall determine compliance with this condition.
- 20. Any easement documents recorded for the project shall include an exhibit map that shows the location and limits of the easement in relationship to the project. The County Engineer shall determine compliance with this condition.
- 21. A complete set of construction improvement drawings, including an onsite grading plan, shall be submitted to the County Engineer for approval prior to finalization of any portion of the tentative map. Grading shall comply with best management practices (BMPs) and shall include detailed plans for grading and drainage for lots, project roadways, erosion control (including BMP locations and installation details), slope stabilization and mosquito abatement. A conceptual grading and drainage scheme shall be indicated for each lot on the grading plan. If drainage from one lot to another is proposed, then appropriate drainage easements shall be provided. Disposal of any excavated material onsite shall be indicated on the grading plans. The County Engineer shall determine compliance with this condition.
- 22. If the Engineering Division does not inspect the subdivision improvements, prior to release of any financial assurances for the private improvements, the development shall provide the Engineering Division with a letter prepared by a civil engineer licensed in the State of Nevada, certifying that the private improvements have been constructed in accordance with the approved plan. The County Engineer shall determine compliance with this condition.
- 23. The following note shall be added to the final construction drawings: Any revisions made by TRPA, IVGID and/or the North Lake Tahoe Fire Protection District to the Washoe County approved set of construction drawings must be approved by the design engineer and Washoe County. The County Engineer shall determine compliance with this condition.
- 24. A design level geotechnical report shall be submitted prior to the finalization of the final map. The County Engineer shall determine compliance with this condition.

DRAINAGE/GRADING (COUNTY CODE 110.420)

- 25. The conditional approval of this tentative map shall not be construed as final approval of the drainage facilities shown on the tentative map. Final approval of the drainage facilities will occur during the final map review and will be based upon the final hydrology report.
- 26. Prior to finalization of the first final map, a master hydrology/hydraulic report and a master storm drainage plan shall be submitted to the County Engineer for approval.

Incline Creek Estates, LLC

Subject:

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page:

11

- 27. Prior to finalization of any portion of the tentative map, a final, detailed hydrology/hydraulic report for that unit shall be submitted to the County Engineer. All storm drainage improvements necessary to serve the project shall be designed and constructed to County standards and specifications and/or financial assurances in an appropriate form and amount shall be provided. The County Engineer shall determine compliance with this condition.
- 28. Any increase in stormwater runoff resulting from the development and based on the 100 year storm shall be detained. The County Engineer shall determine compliance with this condition.
- 29. Standard reinforced concrete headwalls or other approved alternatives shall be placed on the inlet and outlet of all drainage structures, and grouted rock riprap shall be used to prevent erosion at the inlets and outlets of all culverts to the satisfaction of the Engineering Division.
- 30. The developer shall provide pretreatment for petrochemicals and silt for all storm drainage leaving the site to the satisfaction of the Engineering Division.
- 31. The owner shall obtain from the Nevada Division of Environmental Protection a Stormwater Discharge Permit or Waiver for construction and submit a copy to the Engineering Division prior to issuance of a grading permit.
- 32. (The Truckee Meadows Regional Stormwater Quality Management Program Construction Permit Submittal Checklist and Inspection Fee shall be submitted with each final map. The County Engineer shall determine compliance with this condition.
- 33. A note on the final map shall indicate that all drainage facilities not maintained by Washoe County shall be privately maintained and perpetually funded by a homeowners association. As an alternative to a homeowners association, the developer may request the establishment of a County Utility Service Area under which fees would be paid for maintenance of the proposed storm drainage detention facility. The fee amount will be based on the additional service above that normally provided by the County to maintain new stormwater facilities dedicated by the developer (i.e., curb and gutter, drop inlets and piping). The County Engineer shall determine compliance with this condition. The maintenance and funding of these drainage facilities shall also be addressed in the CC&Rs to the satisfaction of the District Attorney's Office.
- 34. The maximum permissible flow velocity (that which does not cause scour) shall be determined for all proposed channels and open ditches. The determination shall be based on a geotechnical analysis of the channel soil, proposed channel lining and channel cross section, and it shall be in accordance with acceptable engineering publications/calculations. Appropriate linings shall be provided for all proposed channels and open ditches such that the 100-year flows do not exceed the maximum permissible flow velocity. The County Engineer shall determine compliance with this condition.
- 35. Prior to issuance of a grading permit or approval of the affected final map, the developer shall obtain a permit from the COE for any work within the wetlands/waters of the U.S.,

Incline Creek Estates, LLC

Subject:

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page: 1:

or a letter from the COE indicating that a permit is not required. A copy of the permit/letter shall be submitted to the County Engineer.

- 36. All slopes steeper than 3:1 shall be mechanically stabilized to control erosion. As an alternative to riprap, an engineered solution (geofabric, etc.) may be acceptable. The County Engineer shall determine compliance with this condition.
- Maintenance access and drainage easements shall be provided for all existing and proposed drainage facilities. The County Engineer shall determine compliance with this condition.
- 38. Drainage easements shall be provided for all storm runoff that crosses more than one lot. The County Engineer shall determine compliance with this condition.
- 39. The infiltration basin shall be designed to safely function during a 100 year, 24 hour storm event with 1 foot minimum of freeboard capacity. The infiltration basin shall be designed with an emergency escape way and the subdivision designed to safely pass emergency overflow drainage. The County Engineer shall determine compliance with this condition.

TRAFFIC AND ROADWAY (COUNTY CODE 110.436)

- 40. All roadway improvements necessary to serve the project shall be designed and constructed to County standards and specifications and/or financial assurances in an appropriate form and amount shall be provided. The County Engineer shall determine compliance with this condition.
- 41. Street name and numbers shall be reviewed and approved by the Washoe County Address Coordinator.
- 42. Proposed landscaping and/or fencing along street rights-of-way and within median islands shall be designed to meet American Association of State Highway and Transportation Officials (AASHTO) sight distances and safety guidelines. No tree shall overhang the curb line of any public street. The County Engineer shall determine compliance with this condition.
- 43. For any utilities placed in existing County streets, the streets shall be repaired to the satisfaction of the County Engineer. At a minimum, this will require full depth removal and replacement of asphalt for half the street width, or replacement of non-woven pavement reinforcing fabric with a 2" asphalt overlay for half the street width. Type II slurry seal is required for the entire street width with either option. Full width street improvements may be required if the proposed utility location is too close to the centerline of the existing street.
- 44. Streetlights shall be constructed to Washoe County standards at locations to be determined at the final design stage. The County Engineer shall determine compliance with this condition.

Incline Creek Estates, LLC

Subject:

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page:

13

- 45. The conditions, covenants and restrictions (CC&Rs) shall prominently note to the satisfaction of the District Attorney's Office and the County Engineer that Washoe County will not assume responsibility for maintenance of the development's private street system or accept the streets for dedication to Washoe County unless the streets meet those Washoe County standards in effect at the time of the offer of dedication. The County Engineer shall determine compliance with this condition.
- 46. Adequate snow storage easements shall be identified on the final plat. The County Engineer shall determine compliance with this condition.
- 47. All retaining walls that are adjacent to, provide support for or retain soil from the County right-of-way shall be constructed of reinforced masonry block or reinforced concrete and designed by an engineer licensed in the State of Nevada. The County Engineer shall determine compliance with this condition.
- 48. No retaining walls that retain soil from the County right-of-way or private right-of-way shall be located within a plowed snow storage easement. The County Engineer shall determine compliance with this condition.
- 49. A minimum onsite stacking length of 50 feet and an adequately sized turnaround outside the gate is required prior to any security gate. Vehicle stacking at a gate shall not back up into the adjacent street right-of-way. The County Engineer shall determine compliance with this condition.
- 50. Project roadways shall meet minimum County Code requirements including, but not limited to, a minimum right-of-way width of 36 feet, a minimum of 22 feet of AC paving, and sidewalk installed on one side of the street. Also, with the effective project density being less than 1.5 acres per parcel, concrete curb and gutter for the private streets is required. Rolled curb and gutter on one side given the proposed super-elevated road section would be acceptable. An acceptable AC paving edge treatment (e.g. redwood header, concrete header curb, etc.) shall be installed at the non curb and gutter side. The County Engineer shall determine compliance with this condition.
- 51. The diameter of the "roundabout" island and anything located within the island, such as landscaping, parking, etc., shall be designed to provide safe sight distances and an adequate turning radius for garbage trucks, moving vans, and fire trucks shall be provided. Prior to final map approval, the engineer shall demonstrate adequate turning movement through the "roundabout" is available for the referenced vehicles. The County Engineer shall determine compliance with this condition.
- 52. Letters from the fire agency and the garbage company approving the proposed street width and configuration shall be submitted to the County Engineer prior to approval of the first final map. The County Engineer shall determine compliance with this condition.
- 53. The paving width of the access road shall be 36 feet measured at the right-of-way and shall be smoothly transitioned into the standard street section within the property. The roadway easement within the property shall be adjusted accordingly. The County Engineer shall determine compliance with this condition.

Incline Creek Estates, LLC

Subject:

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page:

14

- 54. "No Parking" signs shall be posted on both sides of the private road. The County Engineer shall determine compliance with this condition.
- 55. Project roadways shall be designed to meet minimum horizontal curve radii using a minimum design speed of 15mph (54' radius). The County Engineer shall determine compliance with this condition.
- 56. The secondary access (western road) road shall meet, the following requirements:
 - a) If the access road will serve as an emergency access facility only, emergency access control gates shall be provided adjacent to College Drive.
 - b) If the access road will serve as a secondary ingress/egress roadway, the intersection with College Drive shall be aligned with Lucille Drive.

The County Engineer shall determine compliance with this condition.

HEALTH

Compliance with the following conditions shall be determined by the District Health Department.

- 57. Construction plans for the development must be submitted to the Health Division for approval. The construction drawings must conform to the State of Nevada Regulations concerning Review of Plans for Subdivisions, Condominiums and Planed Unit Developments, and any applicable requirements of the District Health Department.
- 58. Prior to approval of each final map, the applicant shall submit a final map fee.
- A completed dust control plan must be submitted to the Health Department for review and approval prior to the issuance of a building permit. This plan must be in conformance with Washoe County District Board of Health Regulations Governing Air Quality Management, Section 040.030.
- 60. All land disturbing activities during construction phases, such as, but not limited to, grading, excavation, cut and fill, etc., must be done with effective dust control measures consistent with Washoe County District Board of Health Regulations Governing Air Quality Management, Section 040.030. Disturbances greater than 1 acre in size must obtain an approved dust control plan prior to beginning work.
- A Water System Facility Plan must be submitted to the District Health Department prior to approval of the first final map. The Water System Facility Plan must be prepared by the water purveyor and include the network hydraulic analysis, service area and pressure zone boundaries, facilities necessary to serve developments within these boundaries, and the location and timing of the necessary facility improvements. The Water System Facility Plan must be in compliance with NAC 445A.65505 through 445A.6731 and approved by the District Health Department prior to review of any final map or the proposed subdivision. The appropriate plan review fee will also be required.

Incline Creek Estates, LLC

Subject:

Tentative Subdivision Map Case No. TM07-006

Date:

January 16, 2008

Page:

62. Before final approval will be considered, a "Commitment for Water Service" letter from the water purveyor committing adequate water service to this proposal must be submitted to the Washoe County District Health Department. A letter of approval must be submitted from IVGID for this proposal.

- 63. A letter from IVGID committing sewer service to this proposal must be submitted. This letter shall indicate that the treatment facility will not be brought beyond its permitted capacity by this service.
- 64. The Nevada Division of Environmental Protection must submit a letter to the Health Department certifying their approval of the final map.
- 65. Prior to approval of a final map for the referenced proposal, the design engineer shall submit to the satisfaction of the District Health Department a plan for periodic inspection of the construction of the systems for water supply and community sewerage. The design engineer shall, pursuant to the approved inspection plan, periodically certify in writing to the District Health Department that the improvements are being installed in accordance with the approved plans and recognized practices of the trade.

IVGID CONDITIONS

Compliance with the following conditions shall be determined by IVGID.

- 66. This plan must clearly identify all locations of water and sewer utilities systems.
- 67. This plan must show all water and sewer utilities lines, easements, encroachments etc.
- 68. This plan must identify all APN numbers for each unit as well as common ground areas.
- 69. This plan must show all or any main line extensions for IVGID board approval.
- 70. This plan must be in compliance with all local and state regulations and IVGID ordinance.
- 71. This plan must be stamped by a Nevada licensed engineer.
- 72. All water rights issues must be approved by the Incline Village General Improvement District
- 73. No certificate of occupancy shall be submitted to owner until project has IVGID approval.
- 74. Copy of CC&Rs and Final Map Jurat submitted to the Incline Village General Improvement District before request of any final.
- 75. No work shall begin until all plans have been approved by the Incline Village General Improvement District and all permits have been obtained.

END OF CONDITIONS