

# Ophir Hill

Application to Washoe County for a:

## ***Special Use Permit***

Prepared by:



John F. Krmpotic, AICP  
KLS Planning & Design Group  
1 East 1<sup>st</sup> Street, Suite 1400  
Reno, Nevada 89501  
(775) 852-7606



Edward Thomas, P.E., LEED AP  
Lumos & Associates  
9222 Prototype Drive  
Reno, NV 89523  
(775) 827-6111

Prepared for:

Linda Burdick  
Burdick Excavating Co., Inc.  
PO Box 22330  
Carson City, NV 89721  
(775) 297-4566

**September 8, 2022**

## **Table of Contents**

Project Request .....	1
Project Location .....	1
Land Use and Zoning.....	3
Project Description .....	5
Hillside Development Analysis.....	7
Special Use Permit Findings.....	10
South Valleys Plan Analysis .....	11

## **List of Figures**

Figure 1 – Vicinity Map .....	1
Figure 2 – Existing Parcel Map .....	2
Figure 3 – Washoe County Master Plan Land Use .....	3
Figure 4 – Washoe County Zoning Map .....	4
Figure 5 – Conceptual Development Plan .....	6
Figure 6 – Slope Map.....	7

## **Appendix A**

### **Application Materials**

Washoe County Development Application  
 Property Owner Affidavit  
 Special Use Permit – Supplemental Information  
 Special Use Permit for Grading – Supplemental Information  
 Washoe County Fee Schedule  
 Washoe County Treasurer – Tax Payment Records  
 Integrated Noxious Weed Management Plan  
 Reduced Civil Plan Set

## **Appendix B**

### **Civil Reports/Studies**

Conceptual Drainage Report  
 Geotechnical Investigation Report

### **Civil & Landscape Plan Set (full size sheets – 24" x 36")**

C1 Existing Conditions  
 C2 Preliminary Grading Plan  
 C3 Preliminary Cross Sections  
 C4 Slope Analysis Map  
 C5 Cut Fill Analysis Map  
 L1 Preliminary Landscape Plan



## Project Request

This application contains a request for a **Special Use Permit** for grading meeting the thresholds defined in Washoe County Development Code Section 110.438.35(a).

## Project Location

The site is composed of three parcels (APN: 046-032-02, -04, -05) totaling 11.29 acres and is located adjacent to Old US 395 near Ophir Hill Road in Washoe Valley, about .75 miles south of Davis Creek Park Road. The site currently contains a single-family residence and one building for aggregate processing. Current primary access to the site is via Ophir Hill Road.



Figure 1 – Vicinity Map







## Land Use and Zoning

The site is adjacent to vacant land to the east and south, and residential to the west and north. Rural Residential (RR) was established for the site's land use in the Washoe County Master Plan, and regulatory zoning is High Density Rural (HDR) (See Figures 3 and 4 below). The site is adjacent to similar rural or rural residential land uses on all sides. The site is part of the South Valleys Area Plan within its West Washoe Valley Rural Character Management Area.



Figure 3 – Washoe County Master Plan




Figure 4 – Washoe County Zoning Map



## **Project Description**

This is informally noted as a restoration project that involves a grading request for 29,600 cubic yards of cut, all of which will be used as fill. There is no export needed and the site will balance based on preliminary engineering.

The total project area of 11.29 acres will include a four-lot subdivision with a shared driveway to serve them (see Figure 5 below). The parcels range from 2.5 to 3.5 acres in size. Grading will be used to create the proposed driveway and elevate building pads, as well as to route runoff to a stormwater basin.

On April 8, 2021, the Washoe County Parcel Map Review Committee approved a tentative parcel map for the property described by assessor's parcel numbers (APN's) 046-032-02, 04, and 05. The tentative parcel map (WTM21-0002) divided the property into four parcels. The tentative parcel map conditions of approval included one to submit new grading plans showing how the property will be regraded to adequately accommodate future residential use. That is the primary purpose of this SUP application.

The .82-acre area to the south of the property line for APN 046-032-02 extends from the south property line to an existing ranch fence. This area is part of the BLM land of the project site and was previously cleared as a part of the aggregate operation. This area will be re-graded and re-vegetated as a part of the Ophir Hill restoration effort, but is not a part of the subdivision.

As a residential use, landscape area is not required for the project per Washoe County Code Article 412. However, a landscaped buffer area of approximately .68 acres is provided to reduce noise and traffic impacts from Old US 395. In addition, 72 trees are provided with 1 tree per 20 linear feet along the north and south buffer and 1 tree per 50 linear feet along the highway frontage, and any trees onsite with greater than 6" DBH are preserved. A native seed mix will be used for revegetation, and a Noxious Weed Management program is provided for in Appendix A of this application.





Figure 5 – Conceptual Site Plan



## Hillside Development Analysis

Per Washoe County Development Code Section 110.424.05(a)(1), properties with 15 percent or greater slope on 20 percent or more of the site is subject to hillside development. This applies to this project but less than 20% of the site has more than 15% slope (see Table 2 below) As a result, this is not a hillside project as the mounds of dirt created from the excavation company operation artificially magnify the slope map. The intent of hillside development is not applicable to man-made piles of dirt and do not constitute slopes per se.

Number	Min. Slope	Max. Slope	Area (SF)	Percent of Site	Color
1	0.00%	15.00%	394413.92	80.16%	Green
2	15.00%	20.00%	15554.00	3.16%	Yellow
3	20.00%	25.00%	9182.38	1.87%	Orange
4	25.00%	30.00%	7033.80	1.43%	Red
5	30.00%	100.00%	65848.77	13.38%	Brown




Figure 6 – Slope Map

The Site Development Standards for hillside development per WCD 110.424.30 are all met with the proposed project. In addition to those standards, the grading on the site subjects the project to additional standards of the Washoe County Development Code as stated below. Responses to the standards are written in *italics* below each code section.

**Section 110.424.35 Grading and Drainage Standards.** This section sets forth development standards for grading and drainage of hillside and ridgeline properties.

- (a) Grading. These grading standards are applicable to hillside and ridgeline development only if a special use permit for grading is required pursuant to Washoe County Ordinance 811. The following standards are intended to preserve natural topographic features, foster resource preservation and minimize degradation of the visual character of hillsides:

- (1) Grading shall relate to the natural topography with the natural topography maintained to the greatest extent possible;

*This standard has been met with grading as proposed is really intended to get the site closer to its natural condition. We are moving from disturbance to revegetation and restoration.*

- (2) Where alteration to the natural topography is necessary, graded slopes shall be contoured to provide a smooth and gradual transition of grading and natural slopes, while maintaining the basic character of the terrain;

*All grading (whether in cut or fill areas) is counter graded to provided smooth and gradual transitions. There are no slopes resulting from the grading plan. In addition, restoration of graded areas with revegetation, and planting will help with mitigation.*

- (3) Standard pad grading or terracing which results in grading outside the building footprint and access area shall be discouraged;

*This has been accomplished as there is no terracing of the pads. There in a raised pad replacement of the homes as a flood mitigation measure. However, grading outside of the building footprint is 100 percent imperative for a project like this.*

- (4) Grading of knolls, ridgelines or toes of slopes shall be rounded to conform with the natural grade and to provide a smooth transition to the natural slope;

*The notion of grading of knolls or ridgelines being proposed in the grading plan is not relevant to anything in this grading scenario. The predominant land form characteristic of this site is essentially flat land near the bottom on Washoe Valley that has been graded. All finished slopes are designed with a smooth transition to the natural slope.*

- (5) Grading shall create varying gradients in order to avoid a “manufactured” appearance;

*Similar to above, our approach to vary gradients is to avoid a manufactured appearance in the proposed contours. This will be largely accomplished with the revegetation and planting.*

- (6) Grading in environmentally sensitive habitat areas shall occur only when necessary to protect, maintain, enhance or restore the habitat; and



*There are no environmentally sensitive areas on the site. This grading SUP is intended to simulate a more native condition of the site. This is the key point in the overall grading discussion given there are no significant water ways, drainageways, vegetation including trees and shrubs, wildlife or rock outcroppings on the property.*

- (7) A slope stability and scarring mitigation plan, certificated by the project engineer, shall be reviewed and approved by the Director of Community Development and the Public Works Department prior to initiation of grading.

*There is no issue of slope stability and scarring from this grading plan. The applicant agrees with this requirement.*

- (b) Drainage and Erosion Control. All hillside development shall satisfy current Washoe County Code for drainage and erosion control.

*Th project will satisfy code requirements for drainage and erosion control. We accept that preventive measures on drainage and erosion control that satisfy the applicable articles of the development code can and will be met.*

**Section 110.438.45 Grading of Slopes.** The standards in this section shall apply to all grading for subdivision improvements, special use permits, or other discretionary permits. The standards in this section shall also apply to all grading for building and grading permits upon or adjacent to lots less than or equal to five (5) acres in size, and to all grading within one hundred (100) feet of all property lines on parcels greater than five (5) acres in size.

- (a) Grading shall not result in slopes in excess of, or steeper than, three horizontal to one vertical (3:1) except as provided below:
  - (1) Storm drainage improvements.
  - (2) Cut and fill slopes less than thirty (30) inches in height.
  - (3) Cut slopes proposed to be located behind civic, commercial and industrial buildings, when the cut slope is shorter than and substantially screened by the proposed building. Such slopes are subject to approval of a Director's Modification of Standards by the Director of Community Development.
  - (4) The County Engineer may waive this requirement for up to fifteen (15) percent of the length of the cut and/or fill where the presence of rock or, in his determination, other practical hardships exists.

*This project does not propose any slopes greater than 3:1, thus meeting this standard.*

- (b) Within the required yard setbacks fills shall not differ from the natural or existing grade by more than forty-eight (48) inches (see Figure 110.438.45.1).

*The standard is met with current project design, as the setback fills do not differ from the existing grade by more than 48 inches.*

- (c) Finish grading shall not vary from the natural slope by more than ten (10) feet in elevation. Exposed finish grade slopes greater than ten (10) feet in height may be

allowed upon the approval of a director's modification of standards by the Director of Community Development upon recommendation by the County Engineer.

*This is not applicable as a practical matter as the cuts and fills are due to leveling of stockpiles and not cutting hills, or knolls, or significant landforms. The project will require a maximum cut of 22' and a maximum fill of 8' in height to achieve a uniform finished grade for the building pad locations.*

## **Special Use Permit Findings**

**Section 110.810.30 Findings.** Prior to approving an application for a special use permit, the Planning Commission, Board of Adjustment or a hearing examiner shall find that all of the following are true:

- (a) Consistency. The proposed use is consistent with the action programs, policies, standards and maps of the Master Plan and the applicable area plan;

*The character statement of the South Valleys Area Plan emphasizes large residential parcels in West Washoe Valley, and specifically notes a density of one unit per 2.5 acres for the HDR zone in this CMA. The proposed 2.5- to 3.5-acre lots achieved with the proposed grading meet this standard. These statements make the proposed large lot residential use consistent with the plan's goals and the best fit for the intended vision for the project site.*

- (b) Improvements. Adequate utilities, roadway improvements, sanitation, water supply, drainage, and other necessary facilities have been provided, the proposed improvements are properly related to existing and proposed roadways, and an adequate public facilities determination has been made in accordance with Division Seven;

*One common private driveway will be extended to serve the site as shown in the project site plan. That driveway will be a shared driveway for parcel access. The site will be served by private wells and sewer septic systems. Community systems are not available in the area. Any additional utility improvements needed will be provided upon construction. Drainage improvements are outlined in the attached civil plan set.*

- (c) Site Suitability. The site is physically suitable for the type of development and for the intensity of development;

*The site is essentially flat land, but several scattered areas of manufactured steeper slopes make it impossible to propose residential developments of an appropriate size without grading. It is all residential zoned area and the typical slopes used for residential lots are flat in scale and necessitate grading as requested with this special use permit. However, the four lots in the project design are within the allowable height for the zoning district and all other intensity factors are met as described above.*

- (d) Issuance Not Detrimental. Issuance of the permit will not be significantly detrimental to the public health, safety or welfare; injurious to the property or improvements of adjacent properties; or detrimental to the character of the surrounding area; and

*Issuance of the permit has no conceivable detriment to the public health, safety, or welfare; is not injurious to the property or improvements of adjacent properties; and is not of detrimental character to the surrounding area.*



- (e) Effect on a Military Installation. Issuance of the permit will not have a detrimental effect on the location, purpose or mission of the military installation.

*Issuance of the permit will not have a detrimental effect on the location, purpose, or mission of a military installation.*

### **South Valleys Area Plan Analysis**

Beyond its Washoe County land use designation, the project site is located in the area managed by the South Valleys Area Plan. Further, it is within the West Washoe Valleys Rural Character Management Area. The following sections discuss the themes and policies associated with the project in grading.

#### **Grading Policies**

- SV.2.2 Whenever possible, grading for residential purposes after the date of final adoption of this plan will:
  - Minimize disruption to natural topography.
  - Utilize natural contours and slopes.
  - Complement the natural characteristics of the landscape.
  - Preserve existing vegetation and ground coverage to minimize erosion.
  - Minimize cuts and fills.

*All physical characteristics were considered in the project design and engineering. As a grading specific project, attention was given to the slopes and soil conditions on the site that were evaluated in the design per the geotechnical study recommendations. Slope treatment with revegetation will be utilized to restore slopes and limit erosion and subsequent sedimentation within adjacent storm-water conveyances.*

- SV.12.2 The Washoe County Departments of Community Development and Public Works will establish and oversee compliance and enforcement of design standards for grading that minimize the visual impact of all residential and non-residential hillside development, including road cuts and driveways.

*All design standards for grading will be met as designed and the applicant agrees with this oversight and enforcement standard.*

- SV.12.3 The grading design standards referred to in Policy SV.12.2 will, at a minimum, ensure that disturbed areas shall be finished, and fill slopes will not exceed a 3:1 slope, and that hillside grading will establish an undulating naturalistic appearance by creating varying curvilinear contours.

*All physical characteristics were considered in the project design and engineering. As a grading specific project, attention was given to the slopes and soil conditions on the site that were evaluated in the design per the geotechnical study recommendations. Slope*

*treatment with revegetation will be utilized to restore slopes and limit erosion and subsequent sedimentation within adjacent storm-water conveyances.*

- SV.12.7 At the time of master plan amendment and tentative subdivision map application submittal, and prior to the issuance of grading permits for final maps, an applicant should submit to the Community Development staff, for review and approval, a "developable area analysis" for all portions of a development on slopes greater than 15 percent. The developable area analysis should include the following:
  - An analysis identifying the developable area of a hillside, as evidenced by soils, geotechnical, biological and hydrological studies;
  - Areas underlain with faults that have been active during the Holocene epoch of geological time;
  - Habitat areas of known endangered or rare plant and/or animal species;
  - Significant streams, ravines and/or drainageways; and,
  - A developable area map designed in accordance with the following:
    - Identifying the location;
    - Identifying the amount of total land area suitable for development;
    - Identifying areas of landslide or potential landslide; and,
    - Drawn to a scale appropriate for the project.

*The factors for analysis listed above are all included with this application. This application stems from the need to further analyze the grading associated with a conditionally approved tentative parcel map.*

## **Appendix A**

### **Application Materials**

Washoe County Development Application

Property Owner Affidavit

Special Use Permit – Supplemental Information

Special Use Permit for Grading – Supplemental Information

Washoe County Fee Schedule

Washoe County Treasurer – Tax Payment Records

Integrated Noxious Weed Management Plan

Reduced Civil Plan Set

---



# Washoe County Development Application

Your entire application is a public record. If you have a concern about releasing personal information, please contact Planning and Building staff at 775.328.6100.

<b>Project Information</b>		<b>Staff Assigned Case No.:</b> _____	
Project Name: <b>Ophir Hill Subdivision Special Use Permit</b>			
Project Description: Four lot residential subdivision (WTPM21-0002). Pursuant to Condition No 1.g., grading in excess of Article 438 Major Grading Permit standards must apply for a Special Use Permit			
Project Address: 632 Old US 395, Washoe Valley, NV 89704			
Project Area (acres or square feet): 11.29 ac			
Project Location (with point of reference to major cross streets <b>AND</b> area locator): <b>Old US 395. approximately 3/4 mi. south of Davis Creek Park Rd.</b>			
Assessor's Parcel No.(s):		Parcel Acreage:	
046-032-02		5.29	
046-032-04		2.48	
Assessor's Parcel No.(s):		Parcel Acreage:	
046-032-05		3.58	
Indicate any previous Washoe County approvals associated with this application: Case No.(s). WTPM21-0002			
<b>Applicant Information</b> (attach additional sheets if necessary)			
<b>Property Owner:</b>		<b>Professional Consultant:</b>	
Name: Burdick Excavating Co., Inc.		Name: KLS Planning & Design Group	
Address: P.O. Box 22330		Address: 1 East 1st Street, Suite 1400	
Carson City, NV                      Zip: 89721		Reno, NV                                      Zip: 89501	
Phone: 775-297-4566      Fax:		Phone: 775-852-7606      Fax:	
Email: lburdick@burdickexc.com		Email: johnk@klsdesigngroup.com	
Cell: 530-362-1095      Other:		Cell: 775-857-7710      Other:	
Contact Person: Linda Burdick		Contact Person: John Krmpotic	
<b>Applicant/Developer:</b>		<b>Other Persons to be Contacted:</b>	
Name: Same		Name:	
Address:		Address:	
Zip:		Zip:	
Phone:		Phone:	
Fax:		Fax:	
Email:		Email:	
Cell:		Cell:	
Other:		Other:	
Contact Person:		Contact Person:	
<b>For Office Use Only</b>			
Date Received:		Initial:	
County Commission District:		Planning Area:	
CAB(s):		Master Plan Designation(s):	
		Regulatory Zoning(s):	

## Special Use Permit Application Supplemental Information

(All required information may be separately attached)

1. What is the project being requested?

Special Use Permit for grading that exceeds Major Grading Permit Thresholds per Article 438 of Washoe County Development Code. Grading will be for a four-unit residential subdivision

2. Provide a site plan with all existing and proposed structures (e.g. new structures, roadway improvements, utilities, sanitation, water supply, drainage, parking, signs, etc.)

This is provided in the 4 lot subdivision design which is the site plan.

3. What is the intended phasing schedule for the construction and completion of the project?

This is a single phase project. Construction timeline has not been established yet.

4. What physical characteristics of your location and/or premises are especially suited to deal with the impacts and the intensity of your proposed use?

Proposed project is of a similar nature to neighboring residential properties. Slopes are negligible and grading in the spirit of restoration will be required to prepare the site for development.

5. What are the anticipated beneficial aspects or affects your project will have on adjacent properties and the community?

Improved visual impacts, reduction of dust, reduction of noise, reduction of truck traffic.

6. What are the anticipated negative impacts or affect your project will have on adjacent properties? How will you mitigate these impacts?

There are only POSITIVE impacts created with such a project as this. This will menace livability of adjacent properties.

7. Provide specific information on landscaping, parking, type of signs and lighting, and all other code requirements pertinent to the type of use being purposed. Show and indicate these requirements on submitted drawings with the application.

There is 29,600 cy of dirt being graded.

8. Are there any restrictive covenants, recorded conditions, or deed restrictions (CC&Rs) that apply to the area subject to the special use permit request? (If so, please attach a copy.)

<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No
------------------------------	--

9. Utilities:

a. Sewer Service	Private
b. Electrical Service	NVE
c. Telephone Service	None
d. LPG or Natural Gas Service	None
e. Solid Waste Disposal Service	Waste Management
f. Cable Television Service	Charter
g. Water Service	Private

For most uses, Washoe County Code, Chapter 110, Article 422, Water and Sewer Resource Requirements, requires the dedication of water rights to Washoe County. Please indicate the type and quantity of water rights you have available should dedication be required.

h. Permit #	n/a	acre-feet per year	
i. Certificate #	n/a	acre-feet per year	
j. Surface Claim #	n/a	acre-feet per year	
k. Other #	na	acre-feet per year	

Title of those rights (as filed with the State Engineer in the Division of Water Resources of the Department of Conservation and Natural Resources).

**Not applicable at this time**

10. Community Services (provided and nearest facility):

a. Fire Station	Truckee Meadows Fire Station 32
b. Health Care Facility	Saint Mary's Galena Urgent Medical Center
c. Elementary School	Pleasant Valley Elementary School
d. Middle School	Herz Middle School
e. High School	Damonte Ranch High School
f. Parks	Davis Creek Regional Park
g. Library	South Valleys Library
h. Citifare Bus Stop	Herz Boulevard / Mount Rose Highway



**Special Use Permit Application  
for Grading  
Supplemental Information**  
(All required information may be separately attached)


1. What is the purpose of the grading?

To prepare the site for the construction of single family residences, to construct a shared-access driveway, and to route runoff to a stormwater detention basin.

2. How many cubic yards of material are you proposing to excavate on site?

**There is 29,600 cy of dirt being graded.**

3. How many square feet of surface of the property are you disturbing?

The entire site is being graded (restored is more appropriate) which is 491,792 sq. ft. 

4. How many cubic yards of material are you exporting or importing? If none, how are you managing to balance the work on-site?

There is 0 cy of export/import. The site will be graded in a manner that balances earthwork.

5. Is it possible to develop your property without surpassing the grading thresholds requiring a Special Use Permit? (Explain fully your answer.)

No, it is not. The site is 11.29 acres in size and was previously operated as an aggregate processing facility and mass graded for that operation. The entire site must be re-graded to accommodate a residential development.

6. Has any portion of the grading shown on the plan been done previously? (If yes, explain the circumstances, the year the work was done, and who completed the work.)

No.

7. Have you shown all areas on your site plan that are proposed to be disturbed by grading? (If no, explain your answer.)

Yes all areas in this case mean 100% of the site.

8. Can the disturbed area be seen from off-site? If yes, from which directions and which properties or roadways?

Yes. The disturbed area can be seen from the west from Old US 395, from the south from 3280 Old US 395. and from the north from 3220 Old US 395 and 3210 Ophir Hill Road

9. Could neighboring properties also be served by the proposed access/grading requested (i.e. if you are creating a driveway, would it be used for access to additional neighboring properties)?

No. A shared access driveway will serve only the four proposed single family parcels that is exclusive for this project.

10. What is the slope (horizontal/vertical) of the cut and fill areas proposed to be? What methods will be used to prevent erosion until the revegetation is established?

Cut and fill slopes are typically 5:1 maximum. Fiber rolls will be primarily employed to prevent erosion until revegetation is established

11. Are you planning any berms?

Yes	NoX	If yes, how tall is the berm at its highest?
-----	-----	--

12. If your property slopes and you are leveling a pad for a building, are retaining walls going to be required? If so, how high will the walls be and what is their construction (i.e. rockery, concrete, timber, manufactured block)?

Retaining walls are not designed or needed for this project.

13. What are you proposing for visual mitigation of the work?

Landscape buffering is proposed along the Old US 395 frontage and along the boundaries with adjacent residential properties.

14. Will the grading proposed require removal of any trees? If so, what species, how many and of what size?

No, we are preserving trees as noted in the narrative.

15. What type of revegetation seed mix are you planning to use and how many pounds per acre do you intend to broadcast? Will you use mulch and, if so, what type?

Refer to attached revegetation seed mixture.

16. How are you providing temporary irrigation to the disturbed area?

Yes thru available water sources and irrigation technology.

17. Have you reviewed the revegetation plan with the Washoe Storey Conservation District? If yes, have you incorporated their suggestions?

We have not but expect to in this process.

18. Are there any restrictive covenants, recorded conditions, or deed restrictions (CC&Rs) that may prohibit the requested grading?

Yes	No X	If yes, please attach a copy.
-----	------	-------------------------------

## Property Owner Affidavit

**Applicant Name:** Burdick Excavating Company

The receipt of this application at the time of submittal does not guarantee the application complies with all requirements of the Washoe County Development Code, the Washoe County Master Plan or the applicable area plan, the applicable regulatory zoning, or that the application is deemed complete and will be processed.

STATE OF NEVADA     )  
                                  )  
COUNTY OF WASHOE    )

I, Linda T. Burdick  
(please print name)

being duly sworn, depose and say that I am the owner\* of the property or properties involved in this application as listed below and that the foregoing statements and answers herein contained and the information herewith submitted are in all respects complete, true, and correct to the best of my knowledge and belief. I understand that no assurance or guarantee can be given by members of Planning and Building.

**(A separate Affidavit must be provided by each property owner named in the title report.)**

Assessor Parcel Number(s): 046-032-02

Printed Name Linda Burdick, Burdick Excavating Company, Inc.

Signed [Signature]


Address 2613 04 22330  
CARSON CITY, NV 89721

Subscribed and sworn to before me this  
5<sup>th</sup> day of July, 2022.

(Notary Stamp)

Ryan James Kellogg  
Notary Public in and for said county and state

My commission expires: 3/2/24



\*Owner refers to the following: (Please mark appropriate box.)

- ☒ Owner
- ☒ Corporate Officer/Partner (Provide copy of record document indicating authority to sign.)
- ☐ Power of Attorney (Provide copy of Power of Attorney.)
- ☐ Owner Agent (Provide notarized letter from property owner giving legal authority to agent.)
- ☐ Property Agent (Provide copy of record document indicating authority to sign.)
- ☐ Letter from Government Agency with Stewardship



## Property Owner Affidavit

**Applicant Name:** Burdick Excavating Company

The receipt of this application at the time of submittal does not guarantee the application complies with all requirements of the Washoe County Development Code, the Washoe County Master Plan or the applicable area plan, the applicable regulatory zoning, or that the application is deemed complete and will be processed.

STATE OF NEVADA     )  
                                  )  
COUNTY OF WASHOE    )

I, Linda T Burdick  
(please print name)

being duly sworn, depose and say that I am the owner\* of the property or properties involved in this application as listed below and that the foregoing statements and answers herein contained and the information herewith submitted are in all respects complete, true, and correct to the best of my knowledge and belief. I understand that no assurance or guarantee can be given by members of Planning and Building.

**(A separate Affidavit must be provided by each property owner named in the title report.)**

Assessor Parcel Number(s): 048-032-04 and 05

Printed Name Linda Burdick, Boulder Creek Enterprises

Signed [Signature]


Address 80 Boy 22330  
CRKSON CITY, NV 89721

Subscribed and sworn to before me this  
5<sup>th</sup> day of July, 2022.

Ryan James Kellogg  
Notary Public in and for said county and state

My commission expires: 3/2/24

(Notary Stamp)



\*Owner refers to the following: (Please mark appropriate box.)

- ☒ Owner
- ☒ Corporate Officer/Partner (Provide copy of record document indicating authority to sign.)
- ☐ Power of Attorney (Provide copy of Power of Attorney.)
- ☐ Owner Agent (Provide notarized letter from property owner giving legal authority to agent.)
- ☐ Property Agent (Provide copy of record document indicating authority to sign.)
- ☐ Letter from Government Agency with Stewardship



July 7, 2022

**TO:** Washoe County Community Services, Planning & Building  
**RE:** Burdick Excavating Company, APNs 046-032-02, -04, & 05  
**INTEGRATED NOXIOUS WEED MANAGEMENT PLAN OPHIR HILL SUBDIVISION**

Every property owner in Nevada is responsible for removing noxious weeds from their land, according to the State Legislature. Noxious weeds are identified by the Nevada Department of Agriculture. Weed species change over time, depending on conditions in the field. The "Weed Warriors" program developed by the University of Nevada Cooperative Extension identifies most noxious weeds and the best methods for control. Weed control recommendations frequently change – it is the responsibility of the landscape management company to contact the Cooperative Extension's Educator for updates.

Most noxious weed seeds will be carried in with the wind or in the soil after grading operations. The landscape management company for the developer will be responsible for weed management on the site.

The Cooperative Extension outlines various levels of controls. The best action is preventing weeds from becoming established by planting native species that can out-compete weeds over a period of time.


**Control levels include:**

1. Eradication – or the killing of an entire weed population, this control is most applicable to Military 8 and involves the removal of all weeds an area so they will not reoccur. This is only feasible for small new invasions and the area must be re-vegetated.
2. Weakening weeds.
3. Thinning weeds.
4. Eliminating seed production by damaging the top growth.


**Weed removal includes the following methods:**

1. Pulling weeds by uprooting with the hands (applicable for the project)
2. Mowing and cutting – this works best for large relatively flat and dry areas (applicable for the project). In some areas a weed trimmer could be used to cut down weeds such as cheatgrass before they set seed. This also reduces fire danger along roadways
3. Prescribed burning (not applicable for the project).
4. Cultural controls (applicable for the project). Controls include large restoration projects and re-establishing native plant communities on disturbed areas. This is the method used by the -- project which includes seeding native plants in areas disturbed by grading and the planting of native and adaptive native trees and shrubs in developed areas, that are then irrigated by a drip system. The intent is to out-compete the weeds before they can establish themselves.
5. Biological control by cattle grazing (not applicable for the project).
6. Herbicides, which are chemicals that kill or injure weeds (applicable to the project). These work best for eradication of certain weed species in certain situations, and are most effective on a single weed type where pulling is not effective or feasible. Timing of applications is critical to success. Drawbacks of herbicides include the potential for damaging or killing non-target plants.


Sincerely,  
**Marc Chapelle, PLA**  
*Nevada Professional Landscape Architect #622*  
**L.A. STUDIO NEVADA, LLC**




L:\AP\01\0103.002 - Ophir Hill Grading Sub\DWG\Sheets\EXISTING CONDITIONS.dwg, EXISTING CONDITIONS, 06/23/2022 11:32 am c:\p\p\p



VICINITY MAP



EXP. 6/30/2024



9222 PROTOTYPE DRIVE  
RENO, NV 89521  
TEL: 775.827.6111  
WWW.LUMOSINC.COM  
INFO@LUMOSINC.COM

© LUMOS & ASSOCIATES, INC. THIS DRAWING IS THE PROPERTY OF LUMOS & ASSOCIATES, INC. USE OR REPRODUCTION OF THIS DRAWING, IN WHOLE OR IN PART, WITHOUT THE WRITTEN PERMISSION OF LUMOS & ASSOCIATES, INC. IS STRICTLY PROHIBITED. THIS DRAWING IS NOT TO BE USED FOR ANY PROJECT OTHER THAN THE PROJECT FOR WHICH IT WAS PREPARED.

BURDICK EXCAVATING

OPHIR HILL SUBDIVISION  
SPECIAL USE PERMIT  
EXISTING CONDITIONS

NEVADA

WASHOE COUNTY

WASHOE VALLEY

REV	DATE	DESCRIPTION

BAR IS 1 INCH ON ORIGINAL DRAWING

IF NOT ONE INCH ON THIS SHEET,  
ADJUST SCALES ACCORDINGLY

C1


DRAWN BY: CVJ  
DESIGNED BY: CVJ  
CHECKED BY: ECT  
JOB NO.: 9103.002

PRELIMINARY  
FOR SUP REVIEW  
JULY 2022



## LEGEND

	EXISTING AC PAVEMENT
	PROPOSED AC PAVEMENT
	LAWN
	RIP RAP



EXP. 6/30/2024


## GENERAL NOTES

- TO THE BEST OF MY KNOWLEDGE, BELIEF, AND ABILITY THESE PLANS ARE IN COMPLIANCE WITH WASHOE COUNTY DEVELOPMENT CODE.
- IF A DISTURBED AREA IS LEFT UNDEVELOPED FOR MORE THAN THIRTY (30) DAYS, THE AREA SHALL BE REVEGETATED WITH A NATIVE SEED MIXTURE.

## EARTHWORK

	AREA	CUT	FILL	NET
TOTAL EARTHWORK	12.11 AC	29,600 CY	29,620 CY	20 CY (FILL)
EARTHWORK OUTSIDE EXEMPTED AREAS	11.11 AC	29,500 CY	24,450 CY	5050 CY (CUT)
ONSITE PARCEL AREA	11.29 AC			
ONSITE DISTURBED AREA	11.29 AC			
OFFSITE AREA	0.82 AC			
OFFSITE DISTURBED AREA	0.82 AC			

L:\AP\9103.002 - Ophir Hill Grading, Sup\DWG\Sheets\Grading Plan.dwg, GRADING PLAN, 06/23/2022 11:32 am c:\pines

9222 PROTOTYPE DRIVE  
RENO, NV 89521  
TEL: 775.827.6111WWW.LUMOSINC.COM  
INFO@LUMOSINC.COM

© LUMOS & ASSOCIATES, INC.; THIS DRAWING IS THE PROPERTY OF LUMOS & ASSOCIATES, INC. USE OR REPRODUCTION OF THIS DRAWING, IN WHOLE OR IN PART, WITHOUT THE WRITTEN PERMISSION OF LUMOS & ASSOCIATES, INC. IS STRICTLY PROHIBITED. THIS DRAWING IS NOT TO BE USED FOR ANY PROJECT OTHER THAN THE PROJECT FOR WHICH IT WAS PREPARED.

BURDICK EXCAVATING

OPHIR HILL SUBDIVISION  
SPECIAL USE PERMIT  
PRELIMINARY GRADING PLANWASHOE COUNTY  
WASHOE VALLEY  
NEVADA

REV.	DATE	DESCRIPTION

PRELIMINARY  
FOR SUP REVIEW  
JULY 2022

BAR IS 1 INCH ON ORIGINAL DRAWING

22x34 SHEETS: 1" = 40'

11x17 SHEETS: 1" = 80'



IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY

C2

DRAWN BY: CVJ  
DESIGNED BY: CVJ  
CHECKED BY: ECT  
JOB NO.: 9103.002



L:\AP\01\0103.002 - Ophir Hill Grading Sup\DWG\Sheets\Grading Plan.dwg,PROFILES,  
06/23/2022 11:32 am c:\pynes



EXP. 6/30/2024

0 40' 80'  
22x34 SHEETS: 1" = 40'  
11x17 SHEETS: 1" = 80'



9222 PROTOTYPE DRIVE  
RENO, NV 89521  
TEL: 775.827.6111  
WWW.LUMOSINC.COM  
INFO@LUMOSINC.COM

© LUMOS & ASSOCIATES, INC.; THIS DRAWING IS THE PROPERTY OF LUMOS & ASSOCIATES, INC. USE OR REPRODUCTION OF THIS DRAWING, IN WHOLE OR IN PART, WITHOUT THE WRITTEN PERMISSION OF LUMOS & ASSOCIATES, INC. IS STRICTLY PROHIBITED. THIS DRAWING IS NOT TO BE USED FOR ANY PROJECT OTHER THAN THE PROJECT FOR WHICH IT WAS PREPARED.

BURDICK EXCAVATING  
OPHIR HILL SUBDIVISION  
SPECIAL USE PERMIT  
PRELIMINARY CROSS SECTIONS  
NEVADA  
WASHOE COUNTY  
WASHOE VALLEY

REV	DATE	DESCRIPTION

BAR IS 1 INCH ON ORIGINAL DRAWING  
0 1


IF NOT ONE INCH ON THIS SHEET,  
ADJUST SCALES ACCORDINGLY

C3

DRAWN BY: CVJ  
DESIGNED BY: CVJ  
CHECKED BY: ECT  
JOB NO.: 9103.002

PRELIMINARY  
FOR SUP REVIEW  
JULY 2022

L:\APR\9103.002 - Ophir Hill Grading\Sup\DWG\Sheets\SLOPE ANALYSIS MAP.dwg,SLOPE ANALYSIS MAP,  
06/23/2022 11:33 am c:\pynes



EXP. 6/30/2024

SLOPES TABLE				
Number	Minimum Slope	Maximum Slope	Area	Color
1	0.00%	15.00%	394413.92	Green
2	15.00%	20.00%	15554.00	Yellow
3	20.00%	25.00%	9182.38	Orange
4	25.00%	30.00%	7033.80	Red
5	30.00%	650.00%	65848.77	Brown



9222 PROTOTYPE DRIVE  
RENO, NV 89521  
TEL: 775.827.6111

WWW.LUMOSINC.COM  
INFO@LUMOSINC.COM

© LUMOS & ASSOCIATES, INC.; THIS DRAWING IS THE PROPERTY OF LUMOS & ASSOCIATES, INC. USE OR REPRODUCTION OF THIS DRAWING, IN WHOLE OR IN PART, WITHOUT THE WRITTEN PERMISSION OF LUMOS & ASSOCIATES, INC. IS STRICTLY PROHIBITED. THIS DRAWING IS NOT TO BE USED FOR ANY PROJECT OTHER THAN THE PROJECT FOR WHICH IT WAS PREPARED.

BURDICK EXCAVATING

OPHIR HILL SUBDIVISION  
SPECIAL USE PERMIT  
SLOPE ANALYSIS MAP

NEVADA

WASHOE COUNTY

WASHOE VALLEY

REV	DATE	DESCRIPTION	BY

PRELIMINARY  
FOR SUP REVIEW  
JULY 2022


BAR IS 1 INCH ON ORIGINAL DRAWING

0 1

IF NOT ONE INCH ON THIS SHEET,  
ADJUST SCALES ACCORDINGLY

C4

DRAWN BY: CVJ  
DESIGNED BY: CVJ  
CHECKED BY: ECT  
JOB NO.: 9103.002


















**AREA OF FILL GREATER THAN 6' DEPTH**  
**AREA = 23 SF**

**AREA OF FILL GREATER THAN 6' DEPTH  
AREA = 72 SF**

**AREA OF FILL GREATER  
THAN 6' DEPTH  
AREA = 255 SF**

**AREA OF FILL GREATER  
THAN 6' DEPTH  
AREA = 300 SF**

CUT/FILL DEPTH TABLE				
NUMBER	MIN DEPTH	MAX DEPTH	AREA	COLOR
1	-22.00	-20.00	338.35	
2	-20.00	-18.00	959.28	
3	-18.00	-16.00	949.15	
4	-16.00	-14.00	2123.86	
5	-14.00	-12.00	4724.90	
6	-12.00	-10.00	6790.70	
7	-10.00	-8.00	13584.35	
8	-8.00	-6.00	23620.91	
9	-6.00	-4.00	27437.38	
10	-4.00	-2.00	33742.72	
11	-2.00	0.00	78911.59	
12	0.00	2.00	140878.73	
13	2.00	4.00	140613.85	
14	4.00	6.00	51838.31	
15	6.00	8.00	767.99	

REV	DATE	DESCRIPTION	BY

**PRELIMINARY**  
FOR SUP REVIEW  
JULY 2022

**PRELIMINARY**  
**FOR SUP REVIEW**  
**JULY 2022**

BAR IS 1 INCH ON ORIGINAL DRAWING

IF NOT ONE INCH ON THIS SHEET,  
ADJUST SCALES ACCORDINGLY.

**C5**

DRAWN BY: CVJ  
DESIGNED BY: CVJ  
CHECKED BY: ECT  
JOB NO.: 9103.002



© LUMOS & ASSOCIATES, INC.: THIS DRAWING IS THE PROPERTY OF LUMOS & ASSOCIATES, INC. NO USE OR REPRODUCTION OF THIS DRAWING, IN WHOLE OR IN PART, WITHOUT THE WRITTEN PERMISSION OF LUMOS & ASSOCIATES, INC. IS STRICTLY PROHIBITED. THIS DRAWING IS NOT TO BE USED FOR ANY PROJECT OTHER THAN THE PROJECT FOR WHICH IT WAS PREPARED.

BURDICK EXCAVATING

OPHIR HILL SUBDIVISION  
SPECIAL USE PERMIT  
CUT FILL ANALYSIS MAP

WASHOE VALLEY	WASHOE COUNTY	NEVADA
---------------	---------------	--------



DECIDUOUS SHADE TREES

EVERGREEN TREES

LANDSCAPE AREA

REVEGETATION AREAS

SITE AREA: +/- 527,512 SQ FT (12.11 ACRES, 11.29 AC. ON & 0.82 AC. OFF-SITE)  
JURISDICTION: WASHOE COUNTY  
ZONING: HIGH-DENSITY RURAL (HDR)

REQUIRED LANDSCAPE AREA = EXEMPT PER 110.412.  
• (0% OF TOTAL SITE AREA)

PROVIDED LANDSCAPE AREA = BUFFER AREAS, +/- 29,565 SQ FT MIN.


REQUIRED TREES = 72 MIN.

- (1 TREE PER 20 LF OF PROPOSED 1,247 LF OF RESIDENTIAL 'BUFFER' NORTH & SOUTH) = 63
- (1 TREE PER 50 LN FT OF 422 LF OF PERIMETER STREET FRONTAGE) = 9


REQUIRED SHRUBS = 432 MIN.

- (6 SHRUBS PER REQUIRED TREE)


- 1) ALL PLANTING AND IRRIGATION SHALL BE INSTALLED PER LOCAL GOVERNING CODES.
- 2) DISTURBED AREAS THAT ARE TO REMAIN VACANT FOR MORE THAN ONE YEAR SHALL RECEIVE TEMPORARY REVEGETATION SEEDING PER 110.412.67
- 3) TREES:
  - DECIDUOUS TREES SHALL HAVE A MINIMUM CALIPER OF 2 INCHES.
  - EVERGREEN TREES SHALL HAVE A MINIMUM HEIGHT OF 7 FEET.
  - ADDITIONAL TREES, BEYOND THOSE REQUIRED BY CODE, MAY BE REDUCED IN SIZE AT INSTALLATION.
- 3) FINAL PLANT SELECTION AND LAYOUT WILL BE BASED ON SOUND HORTICULTURAL PRACTICES RELATING TO MICRO-CLIMATE, SOIL, AND WATER REGIMES. ALL TREES WILL BE STAKED SO AS TO REMAIN UPRIGHT AND PLUMB FOLLOWING INSTALLATION. PLANT SIZE AND QUALITY AT TIME OF PLANTING WILL BE PER THE AMERICAN STANDARD FOR NURSERY STOCK (ANSI Z60.1-1990).
- 4) ALL SHRUB BEDS WILL RECEIVE 4" DEPTH MULCH WITH WEED CONTROL.
- 5) ALL LANDSCAPING WILL BE AUTOMATICALLY IRRIGATED. CONTAINER PLANTINGS WILL BE DRIP IRRIGATED BASED ON THE SPECIFIC HORTICULTURAL REQUIREMENTS OF EACH SPECIES. A REDUCED-PRESSURE-TYPE BACKFLOW PREVENTER WILL BE PROVIDED ON THE IRRIGATION SYSTEM AS REQUIRED PER CODE.
- 6) PLAN IS CONCEPTUAL. PLANT QUANTITIES INDICATED ARE PER WASHOE COUNTY CODE REQUIREMENTS. PLANT LOCATIONS, FINAL SPECIES SELECTION, AND SIZE AT PLANTING SHALL BE DETERMINED DURING DEVELOPMENT OF THE FINAL CONSTRUCTION DOCUMENTS.



Know what's below.  
**Call before you dig.**



Scale in Feet



No.	Revision Date
A No:	874-502-06-22
Designed:	MAC
Drawn:	MAC
Checked:	RWH
Date:	7/7/2022



CONCEPTUAL DRAINAGE REPORT  
For  
OPHIR HILL SUBDIVISION  
SPECIAL USE PERMIT



EXP. 6/30/2024

Prepared For:

Burdick Excavating Co., Inc.

Prepared By:

Edward C. Thomas, P.E.



Lumos & Associates, Inc.  
9222 Prototype Drive  
Reno, NV 89521  
(775) 827-6111

JN 9103.002

June 2022

## TABLE OF CONTENTS

<b>1.</b>	Introduction .....	1
1.1.	Existing Site Description .....	2
1.2.	Proposed Project Description .....	3
1.3.	FEMA FIRM Panels .....	3
<b>2.</b>	Methodology .....	3
<b>3.</b>	Historic Drainage System.....	6
<b>4.</b>	Proposed Drainage System.....	9
<b>5.</b>	Water Quality .....	15
<b>6.</b>	Conclusions .....	15
<b>7.</b>	References .....	15

## LIST OF FIGURES

Figure 1: Vicinity Map.....	1
-----------------------------	---

## LIST OF TABLES

Table 1: Selected Rational C Values .....	4
Table 2: Old US 395 Culvert (Pre-development) .....	6
Table 3: Offsite Areas Draining onto Project Site (Pre-development) .....	7
Table 4: On-site Area Draining to North (Pre-development) .....	7
Table 5: Onsite Areas Draining onto BLM Lands (Pre-development) .....	8
Table 6: Drainage Summary (Pre-development) .....	9
Table 7: Offsite Areas Draining onto Project Site (Proposed) .....	10
Table 8: On-site Area Draining to North (Proposed) .....	10
Table 9: On-site Areas Draining to Detention Pond (Proposed) .....	11
Table 10: Un-detained Onsite Areas Draining onto BLM Lands (Proposed) .....	12
Table 11: Drainage Summary (Proposed) .....	13



## TABLE OF APPENDENICES

### A Background Data

A.1 FEMA FIRM Panel

A.2 NOAA Rainfall Intensity

### B Hydrologic Calculations

### C Drainage Exhibits

## 1. INTRODUCTION

This document is presented as a Conceptual Drainage Report in support of the proposed 11.35-acre Ophir Hill residential subdivision in Washoe Valley. This report provides support for the Special Use Permit (SUP) for the developed area as required by Washoe County.

On April 8, 2021, the Washoe County Parcel Map Review Committee approved a tentative parcel map for the property described by assessor's parcel numbers (APN's) 046-032-02, 04, and 05. The tentative parcel map (WTM21-0002) divided the property into four parcels. The tentative parcel map approval was subject to conditions of approval. **Condition h. states that, "As an alternative to condition g. above, the property owner may submit new grading plans showing how the property will be regraded to adequately accommodate future residential use..."** The developer wishes to apply for a grading permit in accordance with the alternative described in condition h. According to the guidelines described in Article 438 of the Washoe County Development Code, the proposed grading will result in earthwork volume and disturbance area exceeding the threshold for a major grading permit. In accordance with Article 438, an SUP application must be approved prior to applying for a grading permit. This Conceptual Drainage Report supports the SUP application.



Figure 1: Vicinity Map



### 1.1. Existing Site Description

The site is located at the base of the Carson Range near the terminus of Ophir Creek in Washoe Valley in unincorporated Washoe County, Nevada (SW  $\frac{1}{4}$ , Section 34, Township 17 North, Range 19 E, Mount Diablo Meridian). It is bound on the west by Old US 395, on the north by residentially zoned property, and on the southwest by a residential parcel. The east side and the eastern half of the southern property boundary abuts Bureau of Land Management (BLM) lands. There are two existing structures located on site; one construction shop and one residence. Nearly 100% of the site has been cleared for use as an aggregate processing and stockpiling operation. The site is currently accessed from Old US 395 via Ophir Hill Road. Old US 395 is a Nevada State Maintained Highway (Alt US 395). Ophir Hill road is a dirt driveway that enters at the north boundary of the site. An un-permitted dirt driveway accesses the site directly from Old US 395 along the **property's southern border. This driveway has been gated to prevent use by the gravel** operation. There are currently rock and soil stockpiles on the site and some processing equipment remains on the site. For purposes of this report, it has been assumed that the segregated rock stockpiles will be removed prior to development but that the soil stockpiles will remain. The site generally slopes from west to east with an overall grade of approximately 4%.

An existing 36-inch diameter corrugated metal pipe (CMP) culvert conveys runoff from the hills to the west of the project site under Old US 395 and discharges within the Old US 395 near the northwest corner of the site. The flowline of drainage channel downstream of the culvert passes just north of the northwest property corner before continuing in a northeasterly direction across the property to the north of the project site. The southern side slope of the drainage channel extends onto the project site. A small portion of the project site drains to the north and into this existing drainage channel. A small portion of the Old US 395 right-of-way drains directly onto the project site along the southern half of the Old US 395 frontage. Roughly 2/3 of 3280 Old US 395 drains directly onto the project site across the southwestern property line. Small. A small portion of 3210 Ophir Hill Road drains onto the site across the **project's northern border. The** majority of the project site drains by sheet flow onto the BLM lands to the south and east of the project site. Runoff eventually flows into Washoe Lake.

There is a 0.82-acre area to the south of the property line for APN 046-032-02 that extends from the south property line to an existing ranch fence. This area is part of the BLM land to the south of the project site and was previously cleared as a part of the aggregate operation. This area will be re-graded and re-vegetated as a part of the Ophir Hill Subdivision project, but is not a part of the subdivision. It is therefore not included in the hydrology calculations.

## 1.2. Proposed Project Description

The proposed 11.35-acre site will be developed into four residential parcels. The parcels will range in size from 2.5 acres to 3.5 acres. The project will be accessed directly from Old US 395 via a proposed shared access driveway. A preliminary grading plan has been prepared which indicates the proposed driveway, parcel access, building pads, drainage swales, drainage culverts, detention pond, and existing and finish contours. The intent of the grading plan is to demonstrate proposed drainage patterns and stormwater detention requirements. A small portion of the project site at its northwestern corner will continue to drain into the existing outfall channel for the Old US 395 culvert, but the amount of runoff reaching this channel will be reduced. The project will continue to receive runoff from a small portion of Old US 395, a small portion of 3210 Ophir Hill Rd., and roughly 2/3 of 3280 Old US 395. Portions of the developed site will be allowed to drain, un-detained, onto the BLM Property. Runoff from paved areas and proposed houses will be collected in drainage swales and culverts and routed to a detention pond. The pond has been designed to reduce the developed peak runoff to existing levels prior to discharge onto the BLM land.

## 1.3. FEMA FIRM Panels

Based on a review of the Federal Emergency Management Agency (FEMA) Flood Insurance Rate Map (FIRM) panel 32031C3350G dated 3/16/2009, part of the southern portion of the site lies within Special Flood Hazard Area A. Zone A is defined as an area subject to inundation by the 1% annual chance flood with no base flood elevations determined. The remainder of the site lies within Zone X (unshaded). Zone X is defined as areas determined to be outside the 0.2% annual chance floodplain. A FIRMette of the project site is included in Appendix A.

## 2. METHODOLOGY

According to the drainage guidelines for Washoe County Development Code and Truckee Meadows Regional Drainage Manual (TMRDM), the Rational Formula Method was used to generate peak discharges for all drainage hydrologic basins [1]. The peak discharges for the project were calculated using the Rational Method. The Rational Method determines peak runoff by expressing the ground cover, site gradient, and soil type as a ratio relative to a completely impervious site. Rainfall intensity is derived from the NOAA Atlas 14 for 24-hour duration storms (See Appendix A). The Rational Method uses the following equations to compute peak runoff:

$$Q = CiA$$

Where,  
 $Q$  = Peak Runoff (cfs)  
 $C$  = Runoff Coefficient (unitless)  
 $i$  = Rainfall Intensity (in/hr)  
 $A$  = Area of Drainage Basin (ac)

Runoff coefficients for a variety of surface conditions are defined by the Truckee Meadows Structural Controls Design Manual.

The following runoff coefficients were used for the Ophir Hill Subdivision SUP project:

*Table 1: Selected Rational C Values*

Landcover Classification	Runoff Coefficient 5-year ( $C_5$ )	Runoff Coefficient 100-year ( $C_{100}$ )
Pavement	0.88	0.93
Roof	0.85	0.87
Gravel Road	0.25	0.50
Lawn/Landscape	0.05	0.30
Desert/Range	0.20	0.50
Cleared Land	0.35	0.45

**Rainfall intensity is a function of rainfall duration and is computed using NOAA's Point Precipitation Frequency Estimates function available on the NOAA website.** NOAA's system allows for pinpoint precipitation estimates by allowing the user to input the exact coordinates of the project site. The highest rainfall intensity occurs when the rainfall duration is equal to the time of concentration for runoff.

In hydrograph theory, time of concentration is defined as the time from the end of excessive rainfall to the end of direct runoff. In practical calculations, time of concentration is the flow time from the most hydraulically remote point in a drainage basin to the point of discharge. Concentration time is therefore a combination of two related factors: initial overland flow time and concentrated flow time. The initial time is based on the distance travelled over the ground surface prior to concentrating into organized channels (sheet flow). The minimum time of concentration is defined by the Truckee Meadows Structural Controls Design Manual for urbanized areas as 5 minutes.

The initial overland flow time is computed using the following equation:

$$t_i = \left[ \frac{1.8(1.1 - R)L_0^{\frac{1}{2}}}{S^{\frac{1}{3}}} \right]$$

Where,  $t_i$  = Initial overland flow time (min)  
 $R$  = 5- year Runoff Coefficient (unitless)  
 $L_0$  = Length of overland runoff (ft); 500 ft maximum  
 $S$  = Overland slope (%)

Time of concentrated flow is computed using the following equation:

$$t_n = \frac{L_n}{v_n(60 \frac{\text{min}}{\text{in}})}$$

Where,  $t_n$  = Concentrated flow time for segment n (min)  
 $L_n$  = Length of concentrated flow segment n (unitless)  
 $v_n$  = Velocity of concentrated flow in segment n (ft)

Time of concentration ( $t_c$ ) is therefore computed using the following equation:

$$t_c = t_i + \sum_{n=1}^n t_n$$

In urbanized basins, the time of concentration calculated using the above method shall not exceed the time of concentration computed by the following equation:

$$t_c = L/180 + 10$$

Where,  $L$  = watershed length (ft)

When in an urbanized area, whichever equation calculates the shorter time of concentration ( $t_c$ ) value shall be the one used. According to Truckee Meadows Structural Controls Design Manual, the minimum concentration time for urbanized basins is 5 minutes.

According to Truckee Meadows Structural Controls Design Manual, the peak rate of runoff may not be increased as a result of development. Development of a project site will often result in an increase in impervious surfaces and an increase in the efficiency with which runoff is allowed to travel through the site. These increases combine to cause an increase

in peak runoff. In this project, a detention basin is proposed to be used to control the rate of runoff leaving the project site.

The Modified Rational Method was used to estimate the detention volume that would be required to reduce the peak rate of runoff from the developed site to the pre-development rate of runoff. The Modified Rational Method plots the proposed pond inflow runoff hydrograph over a hydrograph, which represents the desired peak rate of discharge. The difference between the areas of under the two hydrographs represents the required storage volume. A sequence of proposed inflow hydrographs is plotted and computed against the desired outflow. The first comparison assumes that the rainfall duration is equal to the time of concentration. In subsequent comparisons, the rainfall duration is increased, which causes peak runoff to decrease as the length of the hydrograph increases. Rainfall durations are increased until the resultant peak storage volume stops increasing and begins to decrease. The duration that results in the greatest peak storage is used to determine the storage volume of the detention pond.

### 3. HISTORIC DRAINAGE SYSTEM

A large area to the west of Old US 395 contributes runoff to the existing 36-inch CMP culvert, which conveys runoff under Old US 395 toward the northwest corner of the project site. This runoff does not actually reach the project site, but it is significant, so it has been calculated for this study. Table 2 describes the runoff reaching the existing NDOT culvert

*Table 2: Old US 395 Culvert (Pre-development)*

Sub-basin ID	Description	Area [ac]	Tc [min]	C <sub>5</sub>	C <sub>100</sub>	I <sub>5</sub> [in/hr]	I <sub>100</sub> [in/hr]	Q <sub>5</sub> [cfs]	Q <sub>100</sub> [cfs]
NDOT Culvert	Offsite	48.60	30.11	0.20	0.50	0.94	2.31	9.18	56.19



Several offsite areas contribute runoff, which enter the Ophir Hill Subdivision site. Table 3 describes the runoff that enters the site from the offsite areas. Please refer to Appendix C for existing sub-basin area descriptions.

*Table 3: Offsite Areas Draining onto Project Site (Pre-development)*

Sub-basin ID	Description	Area [ac]	Tc [min]	C <sub>5</sub>	C <sub>100</sub>	I <sub>5</sub> [in/hr]	I <sub>100</sub> [in/hr]	Q <sub>5</sub> [cfs]	Q <sub>100</sub> [cfs]
A1	From 046-032-01 (North)	3.04	22.79	0.14	0.37	1.11	2.69	0.45	3.02
A2	From 046-032-01 (South)	0.09	10.00	0.14	0.39	1.66	3.97	0.02	0.14
A3	From NDOT	0.23	10.00	0.44	0.65	1.66	3.97	0.17	0.59
A4	From 046-032-08	0.05	10.00	0.20	0.50	1.66	3.97	0.02	0.10

A portion of the existing project site drains onto the private property to the north of the project site and into the outfall swale from the NDOT culvert. Table 4 represents the portion of the project site draining to the north. Please refer to Appendix C for existing sub-basin area descriptions.

*Table 4: On-site Area Draining to North (Pre-development)*

Sub-basin ID	Description	Area [ac]	Tc [min]	C <sub>5</sub>	C <sub>100</sub>	I <sub>5</sub> [in/hr]	I <sub>100</sub> [in/hr]	Q <sub>5</sub> [cfs]	Q <sub>100</sub> [cfs]
B4	To 046-032-06	0.53	10.00	0.35	0.45	1.66	3.97	0.31	0.95

The majority of the Ophir Hill Subdivision site drains onto BLM lands to the east and to the south of the project site. Table 5 breaks the onsite areas into four general sub-basins that drain onto BLM lands. The portion of the project site that drains across the southern boundary with BLM has been separated from the portion of the project site that drains onto BLM land across the eastern boundary. The portion of the site that drains onto BLM land across the eastern boundary has been further broken down into three sub-basins that represent low points on the eastern project boundary. Please refer to Appendix C for existing sub-basin area descriptions.

*Table 5: Onsite Areas Draining onto BLM Lands (Pre-development)*

Sub-basin ID	Description	Area [ac]	Tc [min]	C <sub>5</sub>	C <sub>100</sub>	I <sub>5</sub> [in/hr]	I <sub>100</sub> [in/hr]	Q <sub>5</sub> [cfs]	Q <sub>100</sub> [cfs]
B1	Southern Boundary	0.09	10.00	0.35	0.45	1.66	3.97	0.05	0.16
B2	Eastern Boundary (South)	3.18	20.26	0.35	0.45	1.19	2.87	1.33	4.11
B3	Eastern Boundary (Middle)	6.87	18.60	0.36	0.45	1.24	3.00	3.04	9.35
B5	Eastern Boundary (South)	0.62	16.80	0.35	0.45	1.31	3.14	0.28	0.88

Table 6 represents the combined runoff entering the project site from offsite sources, the total onsite runoff discharged onto neighboring private property, and the total runoff being discharged onto BLM lands from the project site only and from the offsite areas and onsite areas combined.

*Table 6: Drainage Summary (Pre-development)*

Basin Description	Area [ac]	Tc [min]	C <sub>5</sub>	C <sub>100</sub>	I <sub>5</sub> [in/hr]	I <sub>100</sub> [in/hr]	Q <sub>5</sub> [cfs]	Q <sub>100</sub> [cfs]
Offsite Areas Draining onto Project Site	3.41	22.79	0.15	0.39	1.11	2.69	0.58	3.58
Onsite Areas Draining onto Private Lands	0.53	10.00	0.35	0.45	1.66	3.97	0.31	0.95
Onsite Areas Only Draining onto BLM Lands	10.76	18.60	0.35	0.45	1.24	3.00	4.73	14.59
Onsite and Offsite Areas Combined Draining onto BLM Lands	14.17	24.69	0.31	0.44	1.06	2.56	4.58	15.88

All calculations can be found in Appendix B.

#### 4. PROPOSED DRAINAGE SYSTEM

Development of the Ophir Hill Subdivision will consist of four residential parcels that will be accessed from Old US 395 by a shared private driveway. The lots will be graded in a manner that will ensure that runoff from impervious surfaces will be carried in drainage swales and culverts to detention pond located on the southwest parcel. Portions of the project site will be allowed to drain directly onto BLM property without passing through the detention pond. The detention pond will be sized so that the total peak runoff reaching the BLM land from the developed site is no greater than the total peak runoff reaching the BLM land from the pre-development site.

The existing project site has been completely cleared for the aggregate processing and stockpiling operations that previously occurred on the site. Portions of the developed site that will not be developed with houses, driveways, or landscaping will be revegetated with native seed mixtures.

Table 7 represents the offsite basins that drain onto the project site. Please refer to Appendix C for proposed sub-basin area descriptions.

*Table 7: Offsite Areas Draining onto Project Site (Proposed)*

Sub-basin ID	Description	Area [ac]	Tc [min]	C <sub>5</sub>	C <sub>100</sub>	I <sub>5</sub> [in/hr]	I <sub>100</sub> [in/hr]	Q <sub>5</sub> [cfs]	Q <sub>100</sub> [cfs]
C1	From 046-032-01	3.14	18.92	0.16	0.39	1.23	2.97	0.63	3.65
C2	From NDOT	0.23	10.00	0.50	0.69	1.66	3.97	0.19	0.63
C3	From 046-032-08	0.04	10.00	0.20	0.50	1.66	3.97	0.01	0.08

As in the pre-development condition, a small portion of the developed Ophir Hill Subdivision site will drain into the Old US 395 culvert outflow swale on the property to the north of the site. Table 8 represents the portion of the developed project site that drains onto the private property to the north. Please refer to Appendix C for proposed sub-basin area descriptions.

*Table 8: On-site Area Draining to North (Proposed)*

Sub-basin ID	Description	Area [ac]	Tc [min]	C <sub>5</sub>	C <sub>100</sub>	I <sub>5</sub> [in/hr]	I <sub>100</sub> [in/hr]	Q <sub>5</sub> [cfs]	Q <sub>100</sub> [cfs]
D9	To 046-032-06	0.12	10.00	0.20	0.50	1.66	3.97	0.04	0.24

By studying Table 8, it can be seen that the overall area of the developed Ophir Hill Subdivision site that drains onto the private land to the north is reduced below pre-development levels. Additionally, but revegetating the site, the runoff coefficients can be reduced. The result is that the peak runoff being discharged onto the private property to the north of the Ophir Hill Subdivision site is reduced.

Table 9 represents on-site areas that drain into the proposed culverts and swales which contribute to the proposed detention pond. Please refer to Appendix C for proposed sub-basin area descriptions.

*Table 9: On-site Areas Draining to Detention Pond (Proposed)*

Sub-basin ID	Description	Area [ac]	T <sub>c</sub> [min]	C <sub>5</sub>	C <sub>100</sub>	I <sub>5</sub> [in/hr]	I <sub>100</sub> [in/hr]	Q <sub>5</sub> [cfs]	Q <sub>100</sub> [cfs]
D5	South Swale on Parcel D	0.74	6.70	0.44	0.62	1.97	4.73	0.64	2.17
D6	South Culvert Parcel C	1.50	12.94	0.25	0.52	1.46	3.50	0.54	2.75
D7	North Culvert Parcel C	1.77	12.75	0.22	0.50	1.47	3.52	0.57	3.13
D8	North Culvert Parcel A	1.55	11.43	0.25	0.52	1.55	3.72	0.59	3.01
D10	North Swale on Parcel D (Downstream)	1.30	11.63	0.35	0.59	1.54	3.68	0.71	2.82
D11	West Swale Parcel B	1.84	13.41	0.25	0.52	1.44	3.44	0.66	3.31



Table 10 represents the onsite areas draining directly onto BLM lands without passing through the detention pond. Please refer to Appendix C for proposed sub-basin area descriptions.

*Table 10: Un-detained Onsite Areas Draining onto BLM Lands (Proposed)*

Sub-basin ID	Description	Area [ac]	T <sub>c</sub> [min]	C <sub>5</sub>	C <sub>100</sub>	I <sub>5</sub> [in/hr]	I <sub>100</sub> [in/hr]	Q <sub>5</sub> [cfs]	Q <sub>100</sub> [cfs]
D1	Southern Boundary	0.06	10.00	0.20	0.50	1.66	3.97	0.02	0.12
D2	Eastern Boundary (South)	1.74	24.33	0.20	0.50	1.07	2.58	0.37	2.25
D3	Eastern Boundary (Middle)	0.27	10.00	0.50	0.50	1.66	3.97	0.09	0.54
D4	Eastern Boundary (South)	0.44	18.63	0.20	0.50	1.24	2.99	0.11	0.66

By comparing Table 10 to Table 5, it can be seen that the rate of runoff reaching the BLM property via the southern project boundary has been reduced. This is due to a reduction of area draining to the south and revegetation of the proposed basin.

Table 11 represents the combined runoff entering the project site from offsite sources, the total onsite runoff discharged onto neighboring private property, and the total runoff being discharged onto BLM lands from the project site only and from the offsite areas and onsite areas combined.

*Table 11: Drainage Summary (Proposed)*

Basin Description	Area [ac]	Tc [min]	C <sub>5</sub>	C <sub>100</sub>	I <sub>5</sub> [in/hr]	I <sub>100</sub> [in/hr]	Q <sub>5</sub> [cfs]	Q <sub>100</sub> [cfs]
Offsite Areas Draining onto Project Site	3.41	1.8.92	0.19	0.41	1.23	2.97	0.78	4.18
Onsite Areas Draining onto Private Lands	0.12	10.00	0.20	0.50	1.66	3.97	0.04	0.24
Un-detained Onsite Areas Only Draining onto BLM Lands	2.51	24.33	0.20	0.50	1.07	2.58	0.54	3.24
Un-detained Onsite and Offsite Areas Combined Draining onto BLM Lands	5.69	22.79	0.18	0.44	1.11	2.69	1.14	6.73
Onsite and Offsite Areas Draining to Detention Pond	8.97	14.16	0.28	0.54	1.40	3.36	3.50	16.29

The runoff draining from the Ophir Hill Subdivision site onto the private property to the north of the project site has been decreased, but the overall runoff reaching the BLM lands has been increased as a result of development. The increase in runoff reaching the BLM land is due to an increase in the efficiency of the pathways for runoff to reach the discharge points. Washoe County requires that the peak runoff leaving a developed site

may not exceed the pre-development rate of runoff. In order to reduce peak runoff, a detention pond is utilized to allow runoff to be temporarily stored while being released at a prescribed rate.

To determine the required volume of runoff, one must first establish the required discharge rate. In the case of the Ophir Hill Subdivision, a portion of the developed project site will be allowed to flow onto BML land as un-detained sheet flow or moderately confined shallow overland flow. The remainder of the site will pass through the detention pond. These two general areas have different times of concentration, so the peak flows are not directly additive. In order to determine a peak rate of runoff, the hydrographs of the two areas must be added.

The rates of runoff discharging onto BLM lands in the pre-development condition are:

$$Q_5 = 4.58 \text{ cfs}$$
$$Q_{100} = 15.88 \text{ cfs.}$$

By combining hydrographs, the proposed rates of runoff discharging to BLM lands are:

$$Q_5 = 4.15 \text{ cfs}$$
$$Q_{100} = 20.21 \text{ cfs.}$$

As can be seen, the 5-year rate of runoff is decreased slightly from the pre-development condition to proposed condition, but the 100-year rate of runoff has been increased. It is therefore unnecessary to detain runoff from the 5-year storm, but runoff from the 100-year storm must be detained. Therefore the detention pond must be sized to ensure that the proposed peak 100-year runoff does not exceed pre-development levels. Since a portion of the proposed Ophir Hill Subdivision site is allowed to drain directly onto BLM lands, then the runoff routed to the detention pond must be detained to an outlet rate that does not cause an overall increase in runoff.

The total runoff leaving the project site in the 100-year storm must be reduced by 4.33 cfs, which means that the rate of runoff entering the detention pond must be reduced by 4.33 cfs to ensure that the proposed rate of runoff reaching BLM lands does not exceed pre-development levels.

By using the Modified Rational Method, it was determined that a detention pond with a volume of at least 4,806 cubic feet is required to reduce the peak 100-year runoff to the pre-development rate.

## 5. WATER QUALITY

As required by the TMRDM, Low Impact Development (LID) methods of treating runoff will be required to address water quality. Flow-based controls will be designed to treat runoff from the 2-year storm event ( $WQ_F$ ). All areas that are not either paved, covered with a structure, or landscaped will be revegetated using a native seed mixture. Hardscape improvements will drain to proposed vegetated swales which will convey runoff to the detention pond. The swales will remove collected sediments and will be supplemented by the stilling effect of the detention pond to meet the Truckee Meadows Structural Controls Design and Low Impact Development Manual [4]. Swale and riprap calculations will be included in the final design.

## 6. CONCLUSIONS

The Ophir Hill Subdivision project will be constructed on a previously disturbed site. Improvements to the site will include private driveways, four single-family residences, drainage swales, culverts, a detention pond and revegetation of exposed earth. Development of the project will result in no increase in peak runoff over pre-development conditions in the 5-year storm and a small increase in runoff in the 100-year storm. The increase in runoff in the 100-year storm can be easily mitigated by the use of a small detention pond. Runoff from the project site to neighboring private property will be reduced with development, and runoff reaching public lands will be reduced to pre-development levels or less. No adverse effects are expected to downstream lands.

References

- [1] Washoe County, "Truckee Meadows Regional Drainage Manual," Reno, 2009.
- [2] National Oceanic and Atmospheric Administration (NOAA), "Atlas 14 Precipitation-Frequency Atlas," 2018. [Online]. Available: [https://hdsc.nws.noaa.gov/hdsc/pfds/pfds\\_map\\_cont.html?bkmrk](https://hdsc.nws.noaa.gov/hdsc/pfds/pfds_map_cont.html?bkmrk).
- [3] United States Department of Agriculture (USDA), "Web Soil Survey," 2020. [Online]. Available: <https://websoilsurvey.sc.egov.usda.gov/App/WebSoilSurvey.aspx>
- [4] NCE, "Truckee Meadows Structural Controls Design and Low Impact Development Manual," Reno, NV, April 2015.



## APPENDIX A

- FEMA FIRM PANEL
- NOAA RAINFALL INTENSITY



# National Flood Hazard Layer FIRMette

119°49'57"W 39°17'51"N



## Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

### SPECIAL FLOOD HAZARD AREAS

- Without Base Flood Elevation (BFE)  
Zone A, V, AE, AH, VE, AR
- With BFE or Depth  
Zone AE, AO, AH, VE, AR
- Regulatory Floodway

- 0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile  
Zone X
- Future Conditions 1% Annual Chance Flood Hazard  
Zone X
- Area with Reduced Flood Risk due to Levee. See Notes.  
Zone X
- Area with Flood Risk due to Levee  
Zone D

### OTHER AREAS OF FLOOD HAZARD

- NO SCREEN
- Area of Minimal Flood Hazard  
Zone X
- Effective LOMRs
- Area of Undetermined Flood Hazard  
Zone D
- Channel, Culvert, or Storm Sewer
- Levee, Dike, or Floodwall

### OTHER FEATURES

- Cross Sections with 1% Annual Chance Water Surface Elevation
- Coastal Transect
- Base Flood Elevation Line (BFE)
- Limit of Study
- Jurisdiction Boundary
- Coastal Transect Baseline
- Profile Baseline
- Hydrographic Feature

- Digital Data Available
- No Digital Data Available
- Unmapped

The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.

## FEMA FIRMETTE

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards.

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 6/21/2022 at 4:35 PM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.



# APPENDIX A.2 - RAINFALL INTENSITY - OFFSITE AREA



NOAA Atlas 14, Volume 1, Version 5  
 Location name: Washoe Valley, Nevada, USA\*  
 Latitude: 39.2977°, Longitude: -119.8413°  
 Elevation: 5621.51 ft\*\*

\* source: ESRI Maps  
 \*\* source: USGS



## POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sarah Dietz, Sarah Heim, Lillian Hiner, Kazungu Maitaria, Deborah Martin, Sandra Pavlovic, Ishani Roy, Carl Trypaluk, Dale Unruh, Fenglin Yan, Michael Yekta, Tan Zhao, Geoffrey Bonnin, Daniel Brewer, Li-Chuan Chen, Tye Parzybok, John Yarchoan

NOAA, National Weather Service, Silver Spring, Maryland

[PF\\_tabular](#) | [PF\\_graphical](#) | [Maps\\_&\\_aerials](#)

### PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches/hour) <sup>1</sup>										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	1.40 (0.924-1.66)	1.75 (1.52-2.06)	2.32 (1.98-2.74)	2.84 (2.41-3.36)	3.72 (3.07-4.42)	4.52 (3.62-5.42)	5.47 (4.21-6.67)	6.62 (4.88-8.26)	8.46 (5.84-10.8)	10.2 (6.65-13.3)
10-min	1.07 (0.924-1.26)	1.33 (1.16-1.57)	1.76 (1.51-2.08)	2.17 (1.84-2.56)	2.83 (2.34-3.36)	3.44 (2.76-4.13)	4.16 (3.21-5.08)	5.04 (3.71-6.29)	6.44 (4.45-8.26)	7.74 (5.06-10.2)
15-min	0.884 (0.764-1.04)	1.10 (0.956-1.30)	1.46 (1.24-1.72)	1.79 (1.52-2.12)	2.34 (1.94-2.78)	2.85 (2.28-3.42)	3.44 (2.65-4.20)	4.16 (3.07-5.20)	5.32 (3.68-6.82)	6.40 (4.18-8.39)
30-min	0.596 (0.514-0.702)	0.740 (0.644-0.876)	0.980 (0.838-1.16)	1.21 (1.02-1.42)	1.58 (1.30-1.87)	1.92 (1.53-2.30)	2.32 (1.78-2.82)	2.80 (2.07-3.50)	3.59 (2.48-4.60)	4.31 (2.82-5.65)
60-min	0.368 (0.319-0.434)	0.458 (0.398-0.542)	0.607 (0.519-0.718)	0.746 (0.634-0.882)	0.976 (0.806-1.16)	1.19 (0.950-1.42)	1.43 (1.11-1.75)	1.74 (1.28-2.17)	2.22 (1.53-2.84)	2.66 (1.74-3.50)
2-hr	0.246 (0.218-0.278)	0.304 (0.270-0.346)	0.384 (0.339-0.436)	0.454 (0.396-0.515)	0.558 (0.474-0.634)	0.650 (0.538-0.750)	0.757 (0.610-0.888)	0.898 (0.698-1.09)	1.14 (0.844-1.44)	1.36 (0.970-1.77)
3-hr	0.200 (0.179-0.224)	0.248 (0.225-0.279)	0.307 (0.274-0.343)	0.354 (0.315-0.396)	0.419 (0.367-0.473)	0.475 (0.409-0.540)	0.536 (0.453-0.617)	0.628 (0.519-0.735)	0.780 (0.627-0.966)	0.922 (0.722-1.19)
6-hr	0.145 (0.129-0.162)	0.180 (0.161-0.202)	0.221 (0.196-0.248)	0.252 (0.223-0.283)	0.292 (0.255-0.331)	0.323 (0.278-0.368)	0.352 (0.298-0.406)	0.387 (0.322-0.453)	0.440 (0.357-0.522)	0.487 (0.388-0.602)
12-hr	0.097 (0.087-0.109)	0.122 (0.109-0.137)	0.152 (0.135-0.171)	0.175 (0.154-0.198)	0.206 (0.179-0.234)	0.230 (0.197-0.263)	0.254 (0.214-0.293)	0.277 (0.230-0.325)	0.309 (0.249-0.370)	0.333 (0.263-0.406)
24-hr	0.069 (0.061-0.079)	0.086 (0.077-0.099)	0.109 (0.097-0.125)	0.128 (0.113-0.147)	0.154 (0.134-0.177)	0.175 (0.151-0.202)	0.197 (0.169-0.229)	0.221 (0.186-0.258)	0.253 (0.209-0.298)	0.278 (0.226-0.332)
2-day	0.042 (0.036-0.049)	0.053 (0.046-0.062)	0.068 (0.059-0.079)	0.080 (0.069-0.094)	0.098 (0.083-0.115)	0.112 (0.095-0.132)	0.127 (0.106-0.152)	0.143 (0.118-0.172)	0.166 (0.134-0.202)	0.185 (0.145-0.228)
3-day	0.033 (0.029-0.038)	0.042 (0.037-0.049)	0.055 (0.048-0.064)	0.066 (0.057-0.076)	0.081 (0.069-0.094)	0.093 (0.080-0.109)	0.107 (0.090-0.126)	0.122 (0.101-0.144)	0.143 (0.116-0.171)	0.160 (0.127-0.194)
4-day	0.029 (0.025-0.033)	0.037 (0.032-0.042)	0.048 (0.042-0.056)	0.058 (0.051-0.067)	0.072 (0.062-0.084)	0.084 (0.072-0.097)	0.097 (0.082-0.113)	0.111 (0.092-0.129)	0.131 (0.107-0.155)	0.148 (0.118-0.177)
7-day	0.019 (0.017-0.022)	0.025 (0.022-0.029)	0.033 (0.029-0.038)	0.040 (0.035-0.046)	0.050 (0.043-0.058)	0.058 (0.050-0.067)	0.067 (0.056-0.078)	0.076 (0.064-0.089)	0.090 (0.073-0.106)	0.101 (0.081-0.120)
10-day	0.016 (0.013-0.018)	0.020 (0.017-0.023)	0.027 (0.023-0.031)	0.032 (0.028-0.037)	0.040 (0.034-0.046)	0.046 (0.039-0.053)	0.053 (0.045-0.061)	0.060 (0.050-0.070)	0.069 (0.057-0.082)	0.077 (0.063-0.092)
20-day	0.010 (0.009-0.012)	0.013 (0.012-0.015)	0.017 (0.015-0.020)	0.021 (0.018-0.024)	0.026 (0.022-0.029)	0.029 (0.025-0.033)	0.033 (0.028-0.038)	0.037 (0.031-0.043)	0.043 (0.036-0.050)	0.047 (0.039-0.056)
30-day	0.008 (0.007-0.009)	0.010 (0.009-0.012)	0.014 (0.012-0.016)	0.017 (0.015-0.019)	0.020 (0.018-0.023)	0.023 (0.020-0.027)	0.026 (0.022-0.030)	0.029 (0.025-0.034)	0.034 (0.028-0.039)	0.037 (0.030-0.044)
45-day	0.007 (0.006-0.007)	0.008 (0.007-0.010)	0.011 (0.010-0.013)	0.013 (0.012-0.015)	0.016 (0.014-0.018)	0.018 (0.016-0.021)	0.021 (0.018-0.023)	0.023 (0.019-0.026)	0.026 (0.022-0.030)	0.028 (0.023-0.033)
60-day	0.006 (0.005-0.006)	0.007 (0.006-0.008)	0.010 (0.008-0.011)	0.012 (0.010-0.013)	0.014 (0.012-0.016)	0.015 (0.013-0.018)	0.017 (0.015-0.020)	0.019 (0.016-0.021)	0.021 (0.018-0.024)	0.022 (0.019-0.026)

<sup>1</sup> Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).  
 Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.  
 Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

### PF graphical



# APPENDIX A.2 - RAINFALL INTENSITY - ONSITE AREAS



NOAA Atlas 14, Volume 1, Version 5  
Location name: Washoe Valley, Nevada, USA\*  
Latitude: 39.2927°, Longitude: -119.8282°  
Elevation: 5092.55 ft\*\*  
\* source: ESRI Maps  
\*\* source: USGS



## POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sarah Dietz, Sarah Heim, Lillian Hiner, Kazungu Maitaria, Deborah Martin, Sandra Pavlovic, Ishani Roy, Carl Trypaluk, Dale Unruh, Fenglin Yan, Michael Yekta, Tan Zhao, Geoffrey Bonnin, Daniel Brewer, Li-Chuan Chen, Tye Parzybok, John Yarchoan

NOAA, National Weather Service, Silver Spring, Maryland

[PF\\_tabular](#) | [PF\\_graphical](#) | [Maps\\_&\\_aerials](#)

### PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches/hour) <sup>1</sup>										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	1.31 (1.13-1.55)	1.64 (1.42-1.93)	2.17 (1.86-2.57)	2.69 (2.28-3.17)	3.53 (2.90-4.19)	4.31 (3.44-5.16)	5.22 (4.02-6.35)	6.34 (4.67-7.86)	8.11 (5.62-10.3)	9.74 (6.40-12.7)
10-min	1.00 (0.864-1.18)	1.25 (1.08-1.47)	1.66 (1.42-1.96)	2.05 (1.73-2.41)	2.69 (2.21-3.19)	3.28 (2.62-3.92)	3.97 (3.05-4.83)	4.82 (3.55-5.99)	6.17 (4.27-7.87)	7.42 (4.87-9.66)
15-min	0.828 (0.712-0.976)	1.03 (0.892-1.22)	1.37 (1.17-1.62)	1.69 (1.43-2.00)	2.22 (1.83-2.63)	2.71 (2.16-3.24)	3.28 (2.53-3.99)	3.98 (2.94-4.95)	5.10 (3.53-6.50)	6.13 (4.02-7.98)
30-min	0.558 (0.480-0.658)	0.694 (0.600-0.820)	0.922 (0.786-1.09)	1.14 (0.966-1.34)	1.49 (1.23-1.77)	1.82 (1.46-2.18)	2.21 (1.70-2.69)	2.68 (1.98-3.33)	3.44 (2.38-4.38)	4.13 (2.71-5.38)
60-min	0.345 (0.297-0.407)	0.429 (0.372-0.507)	0.570 (0.487-0.674)	0.705 (0.597-0.831)	0.925 (0.762-1.10)	1.13 (0.901-1.35)	1.37 (1.05-1.66)	1.66 (1.22-2.06)	2.13 (1.47-2.71)	2.56 (1.68-3.33)
2-hr	0.230 (0.204-0.262)	0.284 (0.252-0.324)	0.361 (0.318-0.411)	0.428 (0.372-0.486)	0.528 (0.447-0.602)	0.617 (0.510-0.714)	0.720 (0.579-0.846)	0.854 (0.664-1.04)	1.08 (0.804-1.37)	1.29 (0.926-1.68)
3-hr	0.185 (0.166-0.208)	0.230 (0.207-0.259)	0.285 (0.255-0.321)	0.330 (0.293-0.372)	0.393 (0.343-0.445)	0.447 (0.383-0.511)	0.507 (0.426-0.586)	0.594 (0.489-0.698)	0.738 (0.590-0.920)	0.873 (0.680-1.13)
6-hr	0.131 (0.117-0.147)	0.163 (0.146-0.184)	0.201 (0.179-0.226)	0.230 (0.203-0.259)	0.269 (0.234-0.304)	0.298 (0.256-0.339)	0.326 (0.276-0.376)	0.361 (0.299-0.421)	0.413 (0.335-0.490)	0.460 (0.366-0.572)
12-hr	0.086 (0.077-0.097)	0.108 (0.096-0.122)	0.135 (0.120-0.152)	0.156 (0.138-0.176)	0.184 (0.160-0.209)	0.206 (0.176-0.235)	0.227 (0.192-0.263)	0.249 (0.206-0.291)	0.278 (0.224-0.332)	0.301 (0.238-0.366)
24-hr	0.057 (0.051-0.065)	0.072 (0.064-0.082)	0.091 (0.081-0.103)	0.106 (0.094-0.120)	0.127 (0.112-0.145)	0.144 (0.126-0.164)	0.162 (0.140-0.186)	0.181 (0.154-0.209)	0.206 (0.172-0.240)	0.226 (0.186-0.267)
2-day	0.034 (0.030-0.039)	0.043 (0.038-0.050)	0.055 (0.048-0.063)	0.064 (0.056-0.075)	0.078 (0.067-0.091)	0.089 (0.076-0.104)	0.101 (0.085-0.118)	0.113 (0.094-0.134)	0.130 (0.106-0.156)	0.144 (0.115-0.175)
3-day	0.026 (0.023-0.030)	0.033 (0.029-0.038)	0.043 (0.038-0.050)	0.051 (0.045-0.059)	0.063 (0.054-0.072)	0.072 (0.062-0.083)	0.082 (0.070-0.096)	0.093 (0.078-0.109)	0.108 (0.089-0.129)	0.121 (0.097-0.145)
4-day	0.023 (0.020-0.026)	0.029 (0.025-0.033)	0.037 (0.033-0.043)	0.045 (0.039-0.051)	0.055 (0.048-0.063)	0.064 (0.055-0.073)	0.073 (0.062-0.084)	0.083 (0.070-0.096)	0.098 (0.080-0.115)	0.110 (0.089-0.130)
7-day	0.015 (0.013-0.017)	0.019 (0.017-0.022)	0.025 (0.022-0.029)	0.031 (0.027-0.035)	0.038 (0.033-0.043)	0.043 (0.037-0.050)	0.050 (0.042-0.057)	0.056 (0.047-0.065)	0.066 (0.054-0.077)	0.073 (0.060-0.087)
10-day	0.012 (0.010-0.014)	0.015 (0.013-0.017)	0.020 (0.018-0.023)	0.024 (0.021-0.028)	0.030 (0.026-0.034)	0.034 (0.029-0.039)	0.039 (0.033-0.045)	0.044 (0.037-0.051)	0.051 (0.042-0.059)	0.056 (0.046-0.066)
20-day	0.008 (0.007-0.009)	0.010 (0.009-0.011)	0.013 (0.011-0.015)	0.015 (0.014-0.017)	0.019 (0.016-0.021)	0.021 (0.019-0.024)	0.024 (0.021-0.027)	0.027 (0.023-0.031)	0.031 (0.026-0.036)	0.034 (0.028-0.039)
30-day	0.006 (0.005-0.007)	0.008 (0.007-0.009)	0.010 (0.009-0.012)	0.012 (0.011-0.014)	0.015 (0.013-0.017)	0.017 (0.014-0.019)	0.019 (0.016-0.021)	0.021 (0.018-0.024)	0.024 (0.020-0.028)	0.026 (0.022-0.030)
45-day	0.005 (0.004-0.005)	0.006 (0.005-0.007)	0.008 (0.007-0.009)	0.010 (0.008-0.011)	0.012 (0.010-0.013)	0.013 (0.011-0.015)	0.014 (0.013-0.016)	0.016 (0.014-0.018)	0.018 (0.015-0.020)	0.019 (0.016-0.022)
60-day	0.004 (0.004-0.005)	0.005 (0.005-0.006)	0.007 (0.006-0.008)	0.008 (0.007-0.009)	0.010 (0.009-0.011)	0.011 (0.009-0.012)	0.012 (0.010-0.014)	0.013 (0.011-0.015)	0.014 (0.012-0.017)	0.015 (0.013-0.018)

<sup>1</sup> Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).

Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.

Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

### PF graphical



## APPENDIX B

- HYDROLOGIC CALCULATIONS


OPHIR HILL SUBDIVISION HYDROLOGY - NDOT 36" CULVERT INFLOW

		Subbasin ID	E_1
		Drainage Direction	Overall
		Area, A [sf]	2116822.5
		Area, A [ac]	48.60
Coef.	C	Composite C <sub>5</sub>	0.20
		Composite C <sub>100</sub>	0.50
Initial Overland	T <sub>i</sub>	Flow Runoff Coefficient, C <sub>5</sub> "R"	0.05
		Flow Length, L [ft] <sup>1</sup>	500
		Land Slope, s [%]	20.00
		Initial Overland Time: T <sub>i</sub> [min]	15.57
Travel Time	T <sub>t</sub>	Flow Length, L [ft]	3120
		Channel Slope, s [%]	5.13
		Travel Time Coefficient <sup>3</sup>	1.50
		Average Velocity, V <sub>5</sub> [ft/s]	3.40
		Travel Time: T <sub>t</sub> [min]	15.31
ToC & Intensity	T <sub>c</sub>	Time of Concentration, T <sub>c</sub> [min]	30.88
		Required? - Y/N	Y
	Urban. Check	Total Length: L <sub>total</sub> [ft]	3620
		Time of Concentration, Check, T <sub>c,check</sub> [min]	30.1
	T <sub>c,final</sub>	Final ToC, T <sub>c,final</sub> [min]	30.11
	I <sup>2</sup>	2-yr Intensity I <sub>2</sub> [in/hr]	0.72
		5-yr Intensity I <sub>5</sub> [in/hr]	0.94
		100-yr Intensity I <sub>100</sub> [in/hr]	2.31
Flow	Q	2-yr Flow, Q <sub>2</sub> [cfs]	6.96
		5-yr Flow, Q <sub>5</sub> [cfs]	9.18
		Design 100-yr Flow, Q <sub>100</sub> [cfs]	56.19

<sup>1</sup> Maximum of 500 feet  
<sup>2</sup> From NOAA Atlas 14  
<sup>3</sup> From Figure 701 TMRDM

$$T_i = \frac{1.8(1.1 - R)L_o^{1/2}}{S^{1/3}}$$
$$T_{c,check} = \frac{L_{total}^{1/3}}{180} + 10$$

$$T_t = \frac{L}{60V}$$



NOAA Intensity [in/hr]			
Lat: 39.2977°, Long: -119.8413°			
Elevation: 5621.51 ft (USGS)			
Duration [min]	I <sub>2</sub> [in/hr]	I <sub>5</sub> [in/hr]	I <sub>100</sub> [in/hr]
5	1.75	2.32	5.47
10	1.33	1.76	4.16
15	1.1	1.46	3.44
30	0.74	0.98	2.32
60	0.458	0.607	1.43

OPHIR HILL SUBDIVISION RUNOFF COEFFICIENTS - PRE-DEVELOPMENT

Landcover Classification	C <sub>5</sub>	C <sub>100</sub>
Pavement	0.88	0.93
Roof	0.85	0.87
Gravel	0.25	0.50
Lawn/Landscape	0.05	0.30
Desert	0.20	0.50
Cleared Land	0.35	0.45

Subbasin ID	A1	A2	A3	A4	B1	B2	B3	B4	B5	Onsite Total	Offsite Total	Total to BLM	Onsite Only to BLM
Drainage Direction	From 046-032-01 North	From 046-032-01 South	From NDOT	From 046-032-08	To South BLM	To East BLM (South)	To East BLM (Middle)	To 046-032-06	To East BLM (North)		Onto Project Site	To BLM	To BLM
Area, A [ac]	3.04	0.09	0.23	0.05	0.09	3.18	6.87	0.53	0.62	11.29	3.41	14.17	10.76

Composite Areas [ac]	Pavement	0.13	0.00	0.08							0.21	0.21	
	Roof	0.06	0.00				0.07			0.07	0.06	0.13	0.07
	Gravel	0.47	0.04								0.51	0.51	
	Lawn/Landscape	2.38	0.05								2.43	2.43	
	Desert			0.15	0.05						0.20	0.20	
	Cleared Land					0.09	3.18	6.80	0.53	0.62	11.22	10.69	10.69

Area Check	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
------------	---	---	---	---	---	---	---	---	---	---	---	---	---

Composite C <sub>5</sub>	0.13	0.14	0.44	0.20	0.35	0.35	0.36	0.35	0.35	0.35	0.15	0.31	0.35
Composite C <sub>100</sub>	0.37	0.39	0.65	0.50	0.45	0.45	0.45	0.45	0.45	0.45	0.39	0.44	0.45



OPHIR HILL SUBDIVISION HYDROLOGY - PRE-DEVELOPMENT

		Subbasin ID	A1	A2	A3	A4	B1	B2	B3	B4	B5	Onsite Total	Offsite Total	Total to BLM	Onsite Only to BLM
		Drainage Direction	From 046-032-01 North	From 046-032-01 South	From NDOT	From 046-032-08	To South BLM	To East BLM (South)	To East BLM (Middle)	To 046-032-06	To East BLM (North)		Onto Project Site	To BLM	To BLM
		Area, A [sf]	132422.4	3920.4	10018.8	2178	3920.4	138520.8	299257.2	23086.8	27007.2	491792.4	148539.6	617245.2	468705.6
		Area, A [ac]	3.04	0.09	0.23	0.05	0.09	3.18	6.87	0.53	0.62	11.29	3.41	14.17	10.76
Coef.	C	Composite C <sub>5</sub>	0.13	0.14	0.44	0.20	0.35	0.35	0.36	0.35	0.35	0.35	0.15	0.31	0.35
		Composite C <sub>100</sub>	0.37	0.39	0.65	0.50	0.45	0.45	0.45	0.45	0.45	0.45	0.39	0.44	0.45
Initial Overland	T <sub>i</sub>	Flow Runoff Coefficient, C <sub>5</sub> "R"	0.05	0.05	0.88	0.20	0.35	0.35	0.35	0.35	0.35	0.35	0.05	0.05	0.35
		Flow Length, L [ft] <sup>1</sup>	415	38	45	18	73	500	500	133	389	500	415	415	500
		Elevation Change	20	3	2	6	2.3	20	36.4	12	15.5	36.4	20	20	36.4
		Land Slope, s [%]	4.82	7.89	4.44	33.33	3.15	4.00	7.28	9.02	3.98	7.28	4.82	4.82	7.28
		<b>Initial Overland Time: T<sub>i</sub> [min]</b>	22.79	5.85	1.62	2.14	7.87	19.02	15.58	7.48	16.80	15.58	22.79	22.79	15.58
Travel Time	T <sub>t</sub>	Flow Length, L [ft]	0	94	53	0	0	112	399	244	0	399	0	616	399
		Elevation Change		3	5.9			2.2	6	14.5		6		22	6
		Channel Slope, s [%]	-	3.19	11.13	-	-	1.96	1.50	5.94	-	1.50	-	3.57	1.50
		Average Velocity, V <sub>5</sub> [ft/s] <sup>3</sup>		2.90	2.80			1.50	2.20	2.50	0.00	2.20	0.00	2.20	2.20
		<b>Travel Time: T<sub>t</sub> [min]</b>	0.00	0.54	0.32	0.00	0.00	1.24	3.02	1.63	0.00	3.02	0.00	1.90	3.02
ToC & Intensity	T <sub>c</sub>	Time of Concentration, T <sub>c</sub> [min]	22.79	6.39	1.93	2.14	7.87	20.26	18.60	9.11	16.80	18.60	22.79	24.69	18.60
	Urban. Check	Required? - Y/N	N	N	N	N	N	N	N	N	N	N	N	N	N
		Total Length: L <sub>total</sub> [ft]	-	-	-	-	-	-	-	-	-	-	-	-	-
		Time of Concentration, Check, T <sub>c,check</sub> [min]	-	-	-	-	-	-	-	-	-	-	-	-	-
	T <sub>c,final</sub>	<b>Final ToC, T<sub>c,final</sub> [min]</b>	<b>22.79</b>	<b>10.00</b>	<b>10.00</b>	<b>10.00</b>	<b>10.00</b>	<b>20.26</b>	<b>18.60</b>	<b>10.00</b>	<b>16.80</b>	<b>18.60</b>	<b>22.79</b>	<b>24.69</b>	<b>18.60</b>
	I <sup>2</sup>	2-yr Intensity I <sub>2</sub> [in/hr]	0.84	1.17	1.17	1.17	1.17	0.90	0.94	1.17	0.98	0.94	0.84	0.80	0.94
		5-yr Intensity I <sub>5</sub> [in/hr]	1.11	1.66	1.66	1.66	1.66	1.19	1.24	1.66	1.31	1.24	1.11	1.06	1.24
		100-yr Intensity I <sub>100</sub> [in/hr]	2.69	3.97	3.97	3.97	3.97	2.87	3.00	3.97	3.14	3.00	2.69	2.56	3.00
Flow	Q	2-yr Flow, Q <sub>2</sub> [cfs] **	0.34	0.01	0.12	0.01	0.04	1.00	2.28	0.22	0.21	3.73	0.44	3.44	3.56
		5-yr Flow, Q <sub>5</sub> [cfs] **	0.45	0.02	0.17	0.02	0.05	1.33	3.04	0.31	0.28	4.96	0.58	4.58	4.73
		<b>100-yr Flow, Q<sub>100</sub> [cfs] **</b>	<b>3.02</b>	<b>0.14</b>	<b>0.59</b>	<b>0.10</b>	<b>0.16</b>	<b>4.11</b>	<b>9.35</b>	<b>0.95</b>	<b>0.88</b>	<b>15.31</b>	<b>3.58</b>	<b>15.88</b>	<b>14.59</b>

<sup>1</sup> Maximum of 500 feet  
<sup>2</sup> From NOAA Atlas 14  
<sup>3</sup> From Figure 701 TMRDM


OPHIR HILL SUBDIVISION HYDROLOGY - PRE-DEVELOPMENT

$$T_i = \frac{1.8(1.1 - R)L_o^{1/2}}{s^{1/3}} \quad T_t = \frac{L}{60V}$$

$$T_{c,check} = \frac{L_{total}}{180} + 10$$

\*\*Coefficients from IDF regression curves must be manually updated in these columns.

NOAA Intensity [in/hr]			
Lat: 39.2927°, Long: -119.8282°			
Elevation: 5092.55 ft (USGS)			
Duration [min]	I2 [in/hr]	I5 [in/hr]	I100 [in/hr]
5	1.64	2.17	5.22
10	1.25	1.66	3.97
15	1.03	1.37	3.28
30	0.694	0.922	2.21
60	0.429	0.57	1.37



OPHIR HILL SUBDIVISION RUNOFF COEFFICIENTS - PROPOSED

Landcover Classification	C <sub>5</sub>	C <sub>100</sub>
Pavement	0.88	0.93
Roof	0.85	0.87
Gravel	0.25	0.50
Lawn/Landscape	0.05	0.30
Desert	0.20	0.50
Cleared Land	0.35	0.45

Subbasin ID	C1	C2	C3	D1	D2	D3	D4	D5	D6	D7	D8	D9	D10	D11	Onsite Total	Total to BLM Un- Detained	Onsite Only to BLM Un- Detained	Offsite Total	Total to Det. Pond	Onsite Only to BLM Un- Detained
Drainage Direction	From 046-032-01	From NDOT	From 046-032-08	To South BLM	To East BLM (South)	To East BLM (Middle)	To East BLM (North)	To South Swale on Parcel D	South Culvert Parcel C	North Culvert Parcel C	North Culvert Parcel A	To 046-032-06	North Swale on Parcel D (Downstream)	West Swale Parcel B	Onsite Total	Total to BLM Un-detained	Onsite only to BLM Un-Detained	Onto Project Site	To Detention Pond	Onsite Only Undetained to BLM
Area, A [ac]	3.14	0.23	0.04	0.06	1.74	0.27	0.44	0.74	1.50	1.77	1.55	0.12	1.30	1.84	11.32	5.69	2.45	3.41	8.97	2.51

Composite Areas [ac]	Pavement	0.23	0.10						0.26	0.08		0.08		0.27	0.07	0.75	0.23		0.33	0.86	
	Roof	0.09							0.04	0.04	0.08	0.04		0.04	0.08	0.32	0.09		0.09	0.32	
	Gravel	0.46															0.46		0.46		
	Lawn/Landscape	2.36							0.19	0.06	0.13	0.07		0.08	0.08	0.61	2.36		2.36	0.61	
	Desert		0.13	0.04	0.06	1.74	0.27	0.44	0.25	1.32	1.56	1.36	0.12	0.91	1.61	9.64	2.55	2.45	0.17	7.18	2.51
	Cleared Land																				

Area Check	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
------------	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---

Composite C <sub>5</sub>	0.16	0.50	0.20	0.20	0.20	0.20	0.20	0.44	0.25	0.22	0.25	0.20	0.35	0.25	0.26	0.18	0.20	0.19	0.28	0.20
Composite C <sub>100</sub>	0.39	0.69	0.50	0.50	0.50	0.50	0.50	0.62	0.52	0.50	0.52	0.50	0.59	0.52	0.53	0.44	0.50	0.41	0.54	0.50

OPHIR HILL SUBDIVISION HYDROLOGY - PROPOSED

		Subbasin ID	C1	C2	C3	D1	D2	D3	D4	D5	D6	D7	D8	D9	D10	D11	Onsite Total	Total to BLM Un-Detained	Offsite Total	Total to Det. Pond	Onsite Only to BLM Un-Detained
		Drainage Direction	From 046-032-01	From NDOT	From 046-032-08	To South BLM	To East BLM (South)	To East BLM (Middle)	To East BLM (North)	To South Swale on Parcel D	South Culvert Parcel C	North Culvert Parcel C	North Culvert Parcel A	To 046-032-06	North Swale on Parcel D (Downstream)	West Swale Parcel B	Onsite Total	Total to BLM Un-detained	Onto Project Site	To Detention Pond	Onsite Only Undetained to BLM
		Area, A [sf]	136778.4	10018.8	1742.4	2613.6	75794.4	11761.2	19166.4	32234.4	65340	77101.2	67518	5227.2	56628	80150.4	493099.2	247856.4	148539.6	390733.2	109335.6
		Area, A [ac]	3.14	0.23	0.04	0.06	1.74	0.27	0.44	0.74	1.50	1.77	1.55	0.12	1.30	1.84	11.32	5.69	3.41	8.97	2.51

Coef.	C	Composite C <sub>5</sub>	0.16	0.50	0.20	0.20	0.20	0.20	0.20	0.44	0.25	0.22	0.25	0.20	0.35	0.25	0.26	0.18	0.19	0.28	0.20
		Composite C <sub>100</sub>	0.39	0.69	0.50	0.50	0.50	0.50	0.50	0.62	0.52	0.50	0.52	0.50	0.59	0.52	0.53	0.44	0.41	0.54	0.50

Initial Overland	T <sub>i</sub>	Flow Runoff Coefficient, C <sub>5</sub> "R"	0.05	0.88	0.20	0.20	0.20	0.20	0.20		0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.05	0.05	0.20	0.20
		Flow Length, L [ft] <sup>1</sup>	357	54	16	116	500	32	330		237	205	167	58	116	142	500	415	357	237	500
		Elevation Change	24	2.5	6	7	17.5	1.2	13		31	26	24	8.5	4.5	3	17.5	20	24	31	17.5
		Land Slope, s [%]	6.72	4.63	37.50	6.03	3.50	3.75	3.94	-	13.08	12.68	14.37	14.66	3.88	2.11	3.50	4.82	6.72	13.08	3.50
		Initial Overland Time: T <sub>i</sub> [min]	18.92	1.75	1.94	9.58	23.86	5.90	18.63	0.00	10.58	9.95	8.61	5.04	11.10	15.04	23.86	22.79	18.92	10.58	23.86

Travel Time	T <sub>t</sub>	Flow Length, L [ft]		50			50			892	315	306	274	0	177	472	50	0	0	600	50
		Elevation Change		4.5			1.5			41.5	6.37	4.5	3		3	6	1.5			12	1.5
		Channel Slope, s [%]	-	9.00	-	-	3.00	-	-	4.65	2.02	1.47	1.09	-	1.69	1.27	3.00	-	-	2.00	3.00
		Average Velocity, V <sub>s</sub> [ft/s] <sup>3</sup>		2.20			1.75			2.22	2.23	1.82	1.62	0.00	2.18	1.37	1.75	0.00	0.00	2.80	1.75
		Travel Time: T <sub>t</sub> [min]	0.00	0.38	0.00	0.00	0.48	0.00	0.00	6.70	2.35	2.80	2.82	0.00	1.35	5.74	0.48	0.00	0.00	3.57	0.48

ToC & Intensity	T <sub>c</sub>	Time of Concentration, T <sub>c</sub> [min]	18.92	2.12	1.94	9.58	24.33	5.90	18.63	6.70	12.94	12.75	11.43	5.04	12.46	20.79	24.33	22.79	18.92	14.16	24.33
		Required? - Y/N	N	N	N	N	N	N	N	Y	Y	Y	Y	N	Y	Y	Y	N	N	Y	N
	Urban. Check	Total Length: L <sub>total</sub> [ft]	-	-	-	-	-	-	-	892	552	511	441	-	293	614	550	-	-	837	-
		Time of Concentration, Check, T <sub>c,check</sub> [min]	-	-	-	-	-	-	-	15.0	13.1	12.8	12.5	-	11.6	13.4	13.1	-	-	14.7	-
	T <sub>c,final</sub>	Final ToC, T <sub>c,final</sub> [min]	18.92	10.00	10.00	10.00	24.33	10.00	18.63	6.70	12.94	12.75	11.43	10.00	11.63	13.41	13.06	22.79	18.92	14.16	24.33
	I <sup>2</sup>	2-yr Intensity I <sub>2</sub> [in/hr]	0.93	1.17	1.17	1.17	0.80	1.17	0.94	1.49	1.10	1.11	1.17	1.17	1.16	1.08	1.10	0.84	0.93	1.06	0.80
		5-yr Intensity I <sub>5</sub> [in/hr]	1.23	1.66	1.66	1.66	1.07	1.66	1.24	1.97	1.46	1.47	1.55	1.66	1.54	1.44	1.46	1.11	1.23	1.40	1.07
		100-yr Intensity I <sub>100</sub> [in/hr]	2.97	3.97	3.97	3.97	2.58	3.97	2.99	4.73	3.50	3.52	3.72	3.97	3.68	3.44	3.48	2.69	2.97	3.36	2.58

Flow	Q	2-yr Flow, Q <sub>2</sub> [cfs] **	0.48	0.13	0.01	0.01	0.28	0.06	0.08	0.48	0.41	0.43	0.44	0.03	0.53	0.49	3.17	0.86	0.59	2.63	0.40
		5-yr Flow, Q <sub>5</sub> [cfs] **	0.63	0.19	0.01	0.02	0.37	0.09	0.11	0.64	0.54	0.57	0.59	0.04	0.71	0.66	4.21	1.14	0.78	3.50	0.54
		100-yr Flow, Q <sub>100</sub> [cfs] **	3.65	0.63	0.08	0.12	2.25	0.54	0.66	2.17	2.75	3.13	3.01	0.24	2.82	3.31	20.82	6.73	4.18	16.29	3.24

<sup>1</sup> Maximum of 500 feet  
<sup>2</sup> From NOAA Atlas 14  
<sup>3</sup> From Figure 701 TMRDM


OPHIR HILL SUBDIVISION HYDROLOGY - PROPOSED

$$T_i = \frac{1.8(1.1 - R)L_o^{1/2}}{s^{1/3}} \qquad T_t = \frac{L}{60V}$$

$$T_{c,check} = \frac{L_{total}}{180} + 10$$

\*\*Coefficients from IDF regression curves must be manually updated in these columns.

NOAA Intensity [in/hr]			
Lat: 39.2927°, Long: -119.8282°			
Elevation: 5092.55 ft (USGS)			
Duration [min]	I2 [in/hr]	I5 [in/hr]	I100 [in/hr]
5	1.64	2.17	5.22
10	1.25	1.66	3.97
15	1.03	1.37	3.28
30	0.694	0.922	2.21
60	0.429	0.57	1.37







9222 Prototype Drive  
Reno, NV 89521  
(775) 827 6111

178 South Maine Street  
Fallon, NV 89406  
(775) 423 2188

308 N. Curry Street, Ste. 200  
Carson City, NV 89703  
(775) 883 7077

PO Box 3570  
225 Kingsbury Grade, Ste. A  
Stateline, NV 89449  
(775) 588 6490

Client: BURDICK Sheet 1 of 10  
Description: OPHIE HILL SUP  
PRELIM HYDRO. Job No. 9103.002  
By: ELT Date: 6-15-22  
Checked By: \_\_\_\_\_ Date: \_\_\_\_\_

ESTIMATE OVERLAND FLOW VELOCITIES  
IN SWALES USING MANNING'S EQUATION  
PROPOSED CONDITIONS

AREA D-5 - INCLUDES ENTRY DRIVE & ROADSIDE  
DITCH  
- NO OVERLAND FLOW (ALL CHANNELIZED)

$$L = 8912 \text{ FT}$$

$$\Delta \text{ELEV} \approx 41.5 \text{ FT}$$

$$S = 4.65\%$$

ASSUME: 1. RIPRAP V-DITCH  
2.  $n = 0.035$   
3. 5:1 SIDE SLOPES

$$Q_s = 0.64 \text{ cfs}$$

$$V_s = 2.22 \text{ fps}$$

AREA D-6 - SOUTH SWALE TO SOUTH CULVERT ON SW LOT

$$S = 2.20\%$$

ASSUME: 1. EARTH SWALE  
2. 5:1 SIDE SLOPES  
3.  $n = 0.025$

$$Q_s = 0.54 \text{ cfs}$$

$$V_s = 2.23 \text{ fps}$$



9222 Prototype Drive  
Reno, NV 89521  
(775) 827.6111

178 South Maine Street  
Fallon, NV 89406  
(775) 423.2188

308 N. Curry Street, Ste. 200  
Carson City, NV 89703  
(775) 883 7077

PO Box 3570  
225 Kingsbury Grade, Ste. A  
Stateline, NV 89449  
(775) 588 6490

Client: BURNICK Sheet 2 of 10  
Description: DAIR HILL SUP  
PRELIM. HYDRO Job No. 9103.002  
By: ELT Date: 6-15-22  
Checked By: \_\_\_\_\_ Date: \_\_\_\_\_

AREA D-7 - NORTH SWALE TO N. CULVERT SW LOT

$$L = 306 \text{ FT}$$

$$\Delta \text{ELEV} = 4.5 \text{ FT}$$

$$S = 1.47\%$$

USE SAME ASSUMPTIONS AS D-6

$$Q_s = 0.57 \text{ cfs}$$

$$V_s = 1.82 \text{ fps}$$

AREA D-8 - N SWALE TO CULVERT NW LOT

$$L = 274 \text{ FT}$$

$$\Delta \text{ELEV} = 3 \text{ FT}$$

$$S = 1.09\%$$

USE SAME ASSUMPTIONS AS D-6

$$Q_s = 0.59 \text{ cfs}$$

$$V_s = 1.62 \text{ fps}$$

AREA D-10 - USE FLOW RATE AND ASSUMPTIONS FROM D-6, D-7, AND D-8, COMBINED WITH D-10

$$L = 177 \text{ FT}$$

$$Q_{SD6} + Q_{SD7} + Q_{SD8} = 1.70 \text{ cfs}$$

$$\Delta \text{ELEV} = 3.5 \text{ FT}$$

$$S = 1.69\%$$

$$n = 0.035 \text{ (RIPRAP)}$$

$$Q_s = 2.41 \text{ cfs}$$

$$V_s = 2.18 \text{ fps}$$



9222 Prototype Drive  
Reno, NV 89521  
(775) 827.6111

178 South Maine Street  
Fallon, NV 89406  
(775) 423.2188

308 N. Curry Street, Ste. 200  
Carson City, NV 89703  
(775) 883.7077

PO Box 3570  
225 Kingsbury Grade, Ste. A  
Stateline, NV 89449  
(775) 588.6490

Client: BURDICK Sheet 3 of 10  
Description: PRELIM. HYDRO  
OPHIR HILL SUP Job No. 9103.002  
By: EC Date: 6-15-22  
Checked By: \_\_\_\_\_ Date: \_\_\_\_\_

AREA D-11 - E SWALE NE LOT

$$L = 472 \text{ FT}$$

$$\Delta \text{ELEV} = 6 \text{ FT}$$

$$S = 1.27 \%$$

USE SAME ASSUMPTIONS AS D-5 ( $n = 0.035$ )

$$Q = 0.66 \text{ cfs}$$

$$V_s = 1.37 \text{ fps}$$

AREA CONTRIBUTING TO DETENTION POND

$$L = 600 \text{ FT}$$

$$\Delta \text{ELEV} = 12 \text{ FT}$$

$$S = 2 \%$$

ASSUME: 1.  $n = 0.030$  ( $1/2$  DISTANCE  $n = 0.025$ ,  $1/2$  DISTANCE,  $n = 0.035$ )

2. 5:1 V-SWALE

$$Q_s = 3.5 \text{ cfs}$$

$$V_s = 2.8 \text{ fps}$$

**AREA D-5**

<b>South Swale SE Lot</b>	
Shape	Triangular
Solve For	Depth of Flow
Flow Rate	0.64 cfs
Max. Flow	28.54 cfs
% Full	24 %
Velocity	2.22 fps
Left Side Z	5
Right Side Z	5
Channel Depth	1 ft
Depth of Flow	0.24 ft
Slope	0.0465 ft/ft
Manning's n:	
Channel Composite	0.035
Left Side	
Right Side	
Area	0.29 sf
Top Width	2.4 ft
Wetted Perimeter	2.45 ft
Hydraulic Radius	0.12 ft
Froude Number	1.13
Flow State	SuperCritical
Critical Slope	0.0363 ft/ft
Critical Depth	0.25 ft
Critical Velocity	2.02 fps

**AREA D-6****To S Culvert on SW Lot**

Shape	Triangular
Solve For	Depth of Flow
Flow Rate	0.54 cfs
Max. Flow	27.48 cfs
% Full	22 %
Velocity	2.23 fps
Left Side Z	5
Right Side Z	5
Channel Depth	1 ft
Depth of Flow	0.22 ft
Slope	0.022 ft/ft
Manning's n:	
Channel Composite	0.025
Left Side	
Right Side	
Area	0.24 sf
Top Width	2.2 ft
Wetted Perimeter	2.24 ft
Hydraulic Radius	0.11 ft
Froude Number	1.19
Flow State	SuperCritical
Critical Slope	0.019 ft/ft
Critical Depth	0.24 ft
Critical Velocity	1.95 fps

**AREA D-7**

<b>To N Culvert SW Lot</b>	
Shape	Triangular
Solve For	Depth of Flow
Flow Rate	0.57 cfs
Max. Flow	22.47 cfs
% Full	25 %
Velocity	1.82 fps
Left Side Z	5
Right Side Z	5
Channel Depth	1 ft
Depth of Flow	0.25 ft
Slope	0.0147 ft/ft
Manning's n:	
Channel Composite	0.025
Left Side	
Right Side	
Area	0.31 sf
Top Width	2.5 ft
Wetted Perimeter	2.55 ft
Hydraulic Radius	0.12 ft
Froude Number	0.91
Flow State	SubCritical
Critical Slope	0.0188 ft/ft
Critical Depth	0.24 ft
Critical Velocity	1.97 fps



**AREA D-8**

<b>To Culvert NW Lot</b>	
Shape	Triangular
Solve For	Depth of Flow
Flow Rate	0.59 cfs
Max. Flow	19.34 cfs
% Full	27 %
Velocity	1.62 fps
Left Side Z	5
Right Side Z	5
Channel Depth	1 ft
Depth of Flow	0.27 ft
Slope	0.0109 ft/ft
Manning's n:	
Channel Composite	0.025
Left Side	
Right Side	
Area	0.36 sf
Top Width	2.7 ft
Wetted Perimeter	2.75 ft
Hydraulic Radius	0.13 ft
Froude Number	0.78
Flow State	SubCritical
Critical Slope	0.0187 ft/ft
Critical Depth	0.24 ft
Critical Velocity	1.99 fps

**AREA D-10**

<b>N Swale SE Lot</b>	
Shape	Triangular
Solve For	Depth of Flow
Flow Rate	2.41 cfs
Max. Flow	17.21 cfs
% Full	47 %
Velocity	2.18 fps
Left Side Z	5
Right Side Z	5
Channel Depth	1 ft
Depth of Flow	0.47 ft
Slope	0.0169 ft/ft
Manning's n:	
Channel Composite	0.035
Left Side	
Right Side	
Area	1.1 sf
Top Width	4.7 ft
Wetted Perimeter	4.79 ft
Hydraulic Radius	0.23 ft
Froude Number	0.79
Flow State	SubCritical
Critical Slope	0.0305 ft/ft
Critical Depth	0.43 ft
Critical Velocity	2.63 fps

**AREA D-11**

<b>E Swale NE Lot</b>	
Shape	Triangular
Solve For	Depth of Flow
Flow Rate	0.66 cfs
Max. Flow	14.92 cfs
% Full	31 %
Velocity	1.37 fps
Left Side Z	5
Right Side Z	5
Channel Depth	1 ft
Depth of Flow	0.31 ft
Slope	0.0127 ft/ft
Manning's n:	
Channel Composite	0.035
Left Side	
Right Side	
Area	0.48 sf
Top Width	3.1 ft
Wetted Perimeter	3.16 ft
Hydraulic Radius	0.15 ft
Froude Number	0.61
Flow State	SubCritical
Critical Slope	0.0362 ft/ft
Critical Depth	0.26 ft
Critical Velocity	2.03 fps

### Overall to Pond Inlet

Shape	Triangular
Solve For	Depth of Flow
Flow Rate	3.5 cfs
Max. Flow	21.84 cfs
% Full	50 %
Velocity	2.8 fps
Left Side Z	5
Right Side Z	5
Channel Depth	1 ft
Depth of Flow	0.5 ft
Slope	0.02 ft/ft
Manning's n:	
Channel Composite	0.03
Left Side	
Right Side	
Area	1.25 sf
Top Width	5 ft
Wetted Perimeter	5.1 ft
Hydraulic Radius	0.25 ft
Froude Number	0.99
Flow State	SubCritical
Critical Slope	0.0213 ft/ft
Critical Depth	0.5 ft
Critical Velocity	2.83 fps



9222 Prototype Drive  
Reno, NV 89521  
(775) 827.6111

178 South Maine Street  
Fallon, NV 89406  
(775) 423.2188

308 N. Curry Street, Ste. 200  
Carson City, NV 89703  
(775) 883.7077

PO Box 3570  
225 Kingsbury Grade, Ste. A  
Stateline, NV 89449  
(775) 588.6490

Client: Burdick Sheet 1 of     

Description: OPNIE HILL SUP  
PRELIM HYDRO Job No. 9103.002

By: ELT Date: 6-16-22

Checked By:      Date:     

## PRELIMINARY CULVERT DESIGN

### SOUTH CULVERT ON SW LOT

$$Q_{100} = 2.75 \text{ cfs}$$

$$\text{AVAILABLE HEAD ABOVE IB} \approx 3 \text{ FT}$$

$$\text{CULVERT LENGTH} = 50 \text{ FT}$$

$$\text{CULVERT SLOPE} = 0.5\%$$

$$\text{FOR 12" RCP, TOTAL HEAD} = 1.09 \text{ FT}$$

$$\text{FOR 18" RCP, TOTAL HEAD} = 0.87 \text{ FT}$$

### NORTH CULVERT ON SW LOT

$$Q_{100} = 3.13 \text{ cfs}$$

$$\text{AVAILABLE HEAD ABOVE IB} \approx 2.2 \text{ FT}$$

$$\text{CULVERT LENGTH} = 52 \text{ FT}$$

$$\text{CULVERT SLOPE} = 1\%$$

$$\text{FOR 12" RCP, TOTAL HEAD} = 1.19 \text{ FT}$$

$$\text{FOR 18" RCP, TOTAL HEAD} = 0.93 \text{ FT}$$



9222 Prototype Drive  
Reno, NV 89521  
(775) 827.6111

178 South Maine Street  
Fallon, NV 89406  
(775) 423.2188

308 N. Curry Street, Ste. 200  
Carson City, NV 89703  
(775) 883.7077

PO Box 3570  
225 Kingsbury Grade, Ste. A  
Stateline, NV 89449  
(775) 588.6490

Client: BURDICK Sheet 2 of       
Description: OPAH HILL SUP  
PRELIM. HYDRO Job No. 9103.002  
By: ELT Date: 6-17-22  
Checked By:      Date:     

### CULVERT ON NW LOT

$$Q_{100} = 3.0 \text{ cfs}$$

AVAILABLE HEAD ABOVE IE  $\approx 2 \text{ FT}$

CULVERT LENGTH = 100 FT

CULVERT SLOPE = 1.8%

FOR 12" RCP, TOTAL HEAD = 1.16 FT

FOR 18" RCP, TOTAL HEAD = 0.61 FT

### POND OUTLET

$$Q_{100} = 11.96 \text{ cfs}$$

AVAILABLE HEAD ABOVE IE  $\approx 3 \text{ FT}$

CULVERT LENGTH = 48 FT

CULVERT SLOPE  $\approx 0.5\%$

FOR 18" RCP, TOTAL HEAD = 1.66 FT



# Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc.

Thursday, Jun 16 2022

## South Culvert on Southwest Lot (100-year)

Invert Elev Dn (ft) = 83.25  
Pipe Length (ft) = 50.00  
Slope (%) = 0.50  
Invert Elev Up (ft) = 83.50  
Rise (in) = 12.0  
Shape = Circular  
**Span (in) = 12.0**  
No. Barrels = 1  
n-Value = 0.012  
Culvert Type = Circular Concrete  
Culvert Entrance = Groove end projecting (C)  
Coeff. K,M,c,Y,k = 0.0045, 2, 0.0317, 0.69, 0.2

### Embankment


Top Elevation (ft) = 86.50  
Top Width (ft) = 20.00  
Crest Width (ft) = 50.00

### Calculations

Qmin (cfs) = 2.70  
Qmax (cfs) = 2.80  
Tailwater Elev (ft) =  $(dc+D)/2$

### Highlighted

Qtotal (cfs) = 2.75  
Qpipe (cfs) = 2.75  
Qovertop (cfs) = 0.00  
Veloc Dn (ft/s) = 3.85  
Veloc Up (ft/s) = 4.61  
HGL Dn (ft) = 84.11  
HGL Up (ft) = 84.21  
Hw Elev (ft) = 84.59  
Hw/D (ft) = 1.09  
Flow Regime = Inlet Control



# Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc.

Thursday, Jun 16 2022

## South Culvert on Southwest Lot (100-year)

Invert Elev Dn (ft) = 83.25  
Pipe Length (ft) = 50.00  
Slope (%) = 0.50  
Invert Elev Up (ft) = 83.50  
**Rise (in) = 18.0**  
Shape = Circular  
Span (in) = 18.0  
No. Barrels = 1  
n-Value = 0.012  
Culvert Type = Circular Concrete  
Culvert Entrance = Groove end projecting (C)  
Coeff. K,M,c,Y,k = 0.0045, 2, 0.0317, 0.69, 0.2

### Embankment


Top Elevation (ft) = 86.50  
Top Width (ft) = 20.00  
Crest Width (ft) = 50.00

### Calculations

Qmin (cfs) = 2.70  
Qmax (cfs) = 2.80  
Tailwater Elev (ft) = (dc+D)/2

### Highlighted

Qtotal (cfs) = 2.75  
Qpipe (cfs) = 2.75  
Qovertop (cfs) = 0.00  
Veloc Dn (ft/s) = 2.05  
Veloc Up (ft/s) = 3.91  
HGL Dn (ft) = 84.31  
HGL Up (ft) = 84.13  
Hw Elev (ft) = 84.37  
Hw/D (ft) = 0.58  
Flow Regime = Inlet Control



# Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc.

Thursday, Jun 16 2022

## North Culvert on Southwest Lot (100-year)

Invert Elev Dn (ft) = 85.00  
Pipe Length (ft) = 52.00  
Slope (%) = 1.96  
Invert Elev Up (ft) = 86.02  
**Rise (in) = 12.0**  
Shape = Circular  
Span (in) = 12.0  
No. Barrels = 1  
n-Value = 0.012  
Culvert Type = Circular Concrete  
Culvert Entrance = Groove end projecting (C)  
Coeff. K,M,c,Y,k = 0.0045, 2, 0.0317, 0.69, 0.2

### Embankment


Top Elevation (ft) = 88.22  
Top Width (ft) = 20.00  
Crest Width (ft) = 50.00

### Calculations

Qmin (cfs) = 3.10  
Qmax (cfs) = 3.16  
Tailwater Elev (ft) =  $(dc+D)/2$

### Highlighted

Qtotal (cfs) = 3.13  
Qpipe (cfs) = 3.13  
Qovertop (cfs) = 0.00  
Veloc Dn (ft/s) = 4.28  
Veloc Up (ft/s) = 4.90  
HGL Dn (ft) = 85.88  
HGL Up (ft) = 86.78  
Hw Elev (ft) = 87.21  
Hw/D (ft) = 1.19  
Flow Regime = Inlet Control



# Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc.

Friday, Jun 17 2022

## North Culvert on Southeast Lot (100-year)

Invert Elev Dn (ft) = 85.00  
Pipe Length (ft) = 52.00  
Slope (%) = 1.96  
Invert Elev Up (ft) = 86.02  
**Rise (in) = 18.0**  
Shape = Circular  
Span (in) = 18.0  
No. Barrels = 1  
n-Value = 0.012  
Culvert Type = Circular Concrete  
Culvert Entrance = Square edge w/headwall (C)  
Coeff. K,M,c,Y,k = 0.0098, 2, 0.0398, 0.67, 0.5

### Embankment


Top Elevation (ft) = 88.22  
Top Width (ft) = 20.00  
Crest Width (ft) = 50.00

### Calculations

Qmin (cfs) = 3.10  
Qmax (cfs) = 3.15  
Tailwater Elev (ft) = (dc+D)/2

### Highlighted

Qtotat (cfs) = 3.13  
Qpipe (cfs) = 3.13  
Qovertop (cfs) = 0.00  
Veloc Dn (ft/s) = 2.28  
Veloc Up (ft/s) = 4.08  
HGL Dn (ft) = 86.09  
HGL Up (ft) = 86.69  
Hw Elev (ft) = 86.97  
Hw/D (ft) = 0.63  
Flow Regime = Inlet Control





# Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc.

Friday, Jun 17 2022

## Culvert on Northwest Lot (100-year)

Invert Elev Dn (ft) = 85.00  
Pipe Length (ft) = 102.00  
Slope (%) = 1.80  
Invert Elev Up (ft) = 86.84  
**Rise (in) = 12.0**  
Shape = Circular  
Span (in) = 12.0  
No. Barrels = 1  
n-Value = 0.012  
Culvert Type = Circular Concrete  
Culvert Entrance = Groove end projecting (C)  
Coeff. K,M,c,Y,k = 0.0045, 2, 0.0317, 0.69, 0.2

### Embankment


Top Elevation (ft) = 89.00  
Top Width (ft) = 20.00  
Crest Width (ft) = 50.00

### Calculations

Qmin (cfs) = 3.00  
Qmax (cfs) = 3.05  
Tailwater Elev (ft) =  $(dc+D)/2$

### Highlighted

Qtotal (cfs) = 3.01  
Qpipe (cfs) = 3.01  
Qovertop (cfs) = 0.00  
Veloc Dn (ft/s) = 4.14  
Veloc Up (ft/s) = 4.81  
HGL Dn (ft) = 85.87  
HGL Up (ft) = 87.58  
Hw Elev (ft) = 88.00  
Hw/D (ft) = 1.16  
Flow Regime = Inlet Control



# Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc.

Friday, Jun 17 2022

## Culvert on Northwest Lot (100-year)

Invert Elev Dn (ft) = 85.00  
Pipe Length (ft) = 102.00  
Slope (%) = 1.80  
Invert Elev Up (ft) = 86.84  
**Rise (in) = 18.0**  
Shape = Circular  
Span (in) = 18.0  
No. Barrels = 1  
n-Value = 0.012  
Culvert Type = Circular Concrete  
Culvert Entrance = Groove end projecting (C)  
Coeff. K,M,c,Y,k = 0.0045, 2, 0.0317, 0.69, 0.2

### Embankment


Top Elevation (ft) = 89.00  
Top Width (ft) = 20.00  
Crest Width (ft) = 50.00

### Calculations

Qmin (cfs) = 3.00  
Qmax (cfs) = 3.05  
Tailwater Elev (ft) =  $(dc+D)/2$

### Highlighted

Qtotal (cfs) = 3.01  
Qpipe (cfs) = 3.01  
Qovertop (cfs) = 0.00  
Veloc Dn (ft/s) = 2.21  
Veloc Up (ft/s) = 4.03  
HGL Dn (ft) = 86.08  
HGL Up (ft) = 87.50  
Hw Elev (ft) = 87.75  
Hw/D (ft) = 0.61  
Flow Regime = Inlet Control



# Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc.

Friday, Jun 17 2022

## Detention Pond Outlet (100-year)

Invert Elev Dn (ft) = 76.75  
Pipe Length (ft) = 50.00  
Slope (%) = 0.50  
Invert Elev Up (ft) = 77.00  
**Rise (in) = 18.0**  
Shape = Circular  
Span (in) = 18.0  
No. Barrels = 1  
n-Value = 0.012  
Culvert Type = Circular Concrete  
Culvert Entrance = Groove end projecting (C)  
Coeff. K,M,c,Y,k = 0.0045, 2, 0.0317, 0.69, 0.2

### Embankment


Top Elevation (ft) = 80.00  
Top Width (ft) = 20.00  
Crest Width (ft) = 50.00

### Calculations

Qmin (cfs) = 11.95  
Qmax (cfs) = 12.00  
Tailwater Elev (ft) = (dc+D)/2

### Highlighted

Qtotal (cfs) = 11.96  
Qpipe (cfs) = 11.96  
Qovertop (cfs) = 0.00  
Veloc Dn (ft/s) = 6.95  
Veloc Up (ft/s) = 6.77  
HGL Dn (ft) = 78.16  
HGL Up (ft) = 78.71  
Hw Elev (ft) = 79.48  
Hw/D (ft) = 1.66  
Flow Regime = Inlet Control





9222 Prototype Drive  
Reno, NV 89521  
(775) 827.6111

178 South Maine Street  
Fallon, NV 89406  
(775) 423.2188

308 N. Curry Street, Ste. 200  
Carson City, NV 89703  
(775) 883.7077

PO Box 3570  
225 Kingsbury Grade, Ste. A  
Stateline, NV 89449  
(775) 588.6490

Client: BURNICK Sheet 1 of 7  
Description: OPHIR HILL SUP  
PRELIM. HYDRO Job No. 9103.002  
By: ELT Date: 6-16-22  
Checked By: \_\_\_\_\_ Date: \_\_\_\_\_

## RETENTION REQUIREMENT

### EXISTING CONDITIONS

AREA DRAINING TO  
PRIVATE PROPERTY  
TO NORTH OF SITE :  $A = 0.53 \text{ ac}$ ,  $C_s = 0.35$   $C_{100} = 0.45$   
 $T_c = 10 \text{ min}$   
 $i_s = 1.66 \text{ in/hr}$   
 $i_{100} = 3.97 \text{ in/hr}$

$$Q_s = 0.31 \text{ cfs}$$
$$Q_{100} = 0.95 \text{ cfs}$$

TOTAL ONSITE ONLY TO BLM :  $A = 10.76 \text{ ac}$   
 $C_s = 0.35$   
 $C_{100} = 0.45$   
 $T_c = 18.60 \text{ min}$   
 $i_s = 1.24 \text{ in/hr}$   
 $i_{100} = 3.00 \text{ in/hr}$

$$Q_s = 4.73 \text{ cfs}$$
$$Q_{100} = 14.59 \text{ cfs}$$

TOTAL (ONSITE + OFFSITE) TO BLM :  $A = 11.17 \text{ ac}$   
 $C_s = 0.31$   
 $C_{100} = 0.44$   
 $T_c = 24.69 \text{ min}$   
 $i_s = 1.06 \text{ in/hr}$   
 $i_{100} = 2.56 \text{ in/hr}$

$$Q_s = 4.58 \text{ cfs}$$
$$Q_{100} = 15.88 \text{ cfs}$$





9222 Prototype Drive  
Reno, NV 89521  
(775) 827.6111

178 South Maine Street  
Fallon, NV 89406  
(775) 423.2188

308 N. Curry Street, Ste. 200  
Carson City, NV 89703  
(775) 883.7077

PO Box 3570  
225 Kingsbury Grade, Ste. A  
Stateline, NV 89449  
(775) 588.6490

Client: BURDICK Sheet 2 of 7  
Description: OPNIE HILL SUP  
PRELIM. HYDRO Job No. 9103.002  
By: ECT Date: 6/16/22  
Checked By: \_\_\_\_\_ Date: \_\_\_\_\_

## PROPOSED CONDITIONS

AREA DRAINING TO  
PRIVATE PROPERTY  
NORTH OF SITE

$$\begin{aligned} &: A = 0.12 \text{ ac} \\ &C_s = 0.20 \\ &C_{100} = 0.50 \\ &T_c = 10 \text{ min} \\ &\lambda_s = 1.66 \text{ in/hr} \\ &\lambda_{100} = 3.97 \text{ in/hr} \end{aligned}$$

$$\begin{aligned} Q_s &= 0.04 \text{ cfs} \\ Q_{100} &= 0.24 \text{ cfs} \end{aligned} \quad \left. \vphantom{\begin{aligned} Q_s &= 0.04 \text{ cfs} \\ Q_{100} &= 0.24 \text{ cfs} \end{aligned}} \right\} \text{REDUCTION FROM EXISTING}$$

ONSITE ONLY TO BLM (UN-DETAINED):

$$\begin{aligned} &A = 2.51 \text{ ac} \\ &C_s = 0.20 \\ &C_{100} = 0.50 \\ &T_c = 24.33 \text{ min} \\ &\lambda_s = 1.07 \text{ in/hr} \\ &\lambda_{100} = 2.58 \text{ in/hr} \end{aligned}$$

$$\begin{aligned} Q_s &= 0.54 \text{ cfs} \\ Q_{100} &= 2.58 \text{ cfs} \end{aligned}$$

TOTAL (OFFSITE + ONSITE) UNDETAINED  
TO BLM

$$\begin{aligned} &: A = 5.69 \text{ ac} \\ &C_s = 0.18 \\ &C_{100} = 0.44 \\ &T_c = 22.9 \text{ min} \\ &\lambda_s = 1.11 \text{ in/hr} \\ &\lambda_{100} = 2.69 \text{ in/hr} \end{aligned}$$

$$\begin{aligned} Q_s &= 1.14 \text{ cfs} \\ Q_{100} &= 6.73 \text{ cfs} \end{aligned}$$



9222 Prototype Drive  
Reno, NV 89521  
(775) 827.6111

308 N. Curry Street, Ste. 200  
Carson City, NV 89703  
(775) 883.7077


178 South Maine Street  
Fallon, NV 89406  
(775) 423.2188

PO Box 3570  
225 Kingsbury Grade, Ste. A  
Stateline, NV 89449  
(775) 588.6490

Client: BORDICK Sheet 3 of 7  
Description: OPHIR Hill SUP  
PRELIM HYDRO Job No. 9103.002  
By: ELT Date: 6/16/22  
Checked By: \_\_\_\_\_ Date: \_\_\_\_\_

TOTAL TO DETENTION POND:  $A = 8.97 \text{ ac}$   
 $C_s = 0.28$   
 $C_{100} = 0.54$   
 $T_c = 14.16 \text{ min}$   
 $i_s = 1.40''/\text{hr}$   
 $i_{100} = 3.36''/\text{hr}$

$Q_s = 3.50 \text{ cfs}$   
 $Q_{100} = 16.29 \text{ cfs}$



\_\_\_\_\_ = UNDETAINED TO BLM  
\_\_\_\_\_ = POND INFLOW  
\_\_\_\_\_ = TOTAL PROPOSED (PRE-DETENTION)



9222 Prototype Drive  
Reno, NV 89521  
(775) 827.6111

178 South Maine Street  
Fallon, NV 89406  
(775) 423.2188

308 N. Curry Street, Ste. 200  
Carson City, NV 89703  
(775) 883.7077

PO Box 3570  
225 Kingsbury Grade, Ste. A  
Stateline, NV 89449  
(775) 588.6490

Client: BURDICK Sheet 4 of 7  
Description: Opair Hill SOP  
PRELIM. Hydro Job No. 9103.002  
By: ELT Date: 6-16-22  
Checked By: \_\_\_\_\_ Date: \_\_\_\_\_

TOTAL EXISTING :  $Q_s = 4.58 \text{ cfs}$   
TO BLM :  $Q_{100} = 15.88 \text{ cfs}$

TOTAL PROPOSED :  $Q_s = 4.15 \text{ cfs}$   
PRE-DETENTION :  $Q_{100} = 20.21 \text{ cfs}$   
TO BLM

DETENTION REQUIREMENT :

NO DETENTION REQUIRED FOR 5-YEAR  
-  $Q_s \text{ PROPOSED} < Q_s \text{ EXISTING}$

REDUCE 100-YEAR RUNOFF  
BY 4.33 cfs


RUNOFF CAN ONLY BE CONTROLLED AT  
DETENTION POND

PROPOSED DETENTION POND  
INFLOW (100-YR) = 16.29 cfs

ALLOWABLE DETENTION POND OUTFLOW = 11.96 cfs

## MODIFIED RATIONAL METHOD

## EQUATIONS FOR ESTIMATING REQUIRED STORAGE

"I" METHOD

$T_c$  = CONCENTRATION TIME (min)

$D$  = RAINFALL DURATION (min)

$Q_p$  = PEAK RUNOFF AT  $D = T_c$  (cfs)

$Q_i$  = PEAK RUNOFF AT  $D$  (cfs)

$Q_o$  = ALLOWABLE PEAK OUTFLOW RATE (cfs)

$$t_1 = \left( \frac{Q_i - Q_o}{Q_i} \right) (T_c) + D$$

$V_i$  = INFLOW VOLUME (cf)

$V_o$  = OUTFLOW VOLUME (cf)

$$S = \text{STORAGE (cf)} = V_i - V_o$$

OBJECT

PRO. #

SUBJECT

DATE 12-13-16

BY

SHEET 1 OF 2



$$\dot{V}_i = [2(1/2)(T_c)(Q_i)(60 \text{ s/min})] + [(Q_i)(D - T_c)(60 \text{ s/min})]$$

$$\dot{V}_i = (Q_i)(D)(60 \text{ s/min})$$

$$\dot{V}_o = [1/2(t_1)(Q_o)(60 \text{ s/min})] + [1/2(D + T_c - t_1)(Q_o)(60 \text{ s/min})]$$

$$\dot{V}_o = (Q_o)(D + T_c)(30 \text{ s/min})$$

$$S = [(Q_i)(D)(60 \text{ s/min})] - [(Q_o)(D + T_c)(30 \text{ s/min})]$$

PROJECT

PRO. #

SUBJECT

DATE

BY

SHEET 2 OF 2



9222 Prototype Drive  
Reno, NV 89521  
(775) 827.6111

178 South Maine Street  
Fallon, NV 89406  
(775) 423.2188

308 N. Curry Street, Ste. 200  
Carson City, NV 89703  
(775) 883.7077

PO Box 3570  
225 Kingsbury Grade, Ste. A  
Stateline, NV 89449  
(775) 588.6490

Client: BURNICK Sheet 7 of 7  
Description: DPHIL HILL SUP  
PRELIM HYDRO Job No. 9103.002  
By: ELT Date: 6-16-22  
Checked By: \_\_\_\_\_ Date: \_\_\_\_\_

ROUGH DETENTION ESTIMATE USING  
MODIFIED RATIONAL "I" METHOD

DESIGN FOR 100-YR STORM

$A = 8.97 \text{ ac}$   
 $C_{100} = 0.54$

<u>DURATION</u>	<u><math>I_{100}</math></u>	<u>REQUIRED STORAGE</u>
$T_L = 14.16 \text{ min}$	$3.36 \text{ in/hr}$	$3679 \text{ FT}^3$
15 min	$3.28 \text{ in/hr}$	$3838 \text{ FT}^3$
20 min	$2.92 \text{ in/hr}$	$4711 \text{ FT}^3$
30 min	$2.21 \text{ in/hr}$	$3415 \text{ FT}^3$
25 min	$2.57 \text{ in/hr}$	$4459 \text{ FT}^3$
19 min	$2.90 \text{ in/hr}$	$4644 \text{ CF}$
21 min	$2.85 \text{ in/hr}$	$4785 \text{ CF}$
22 min	$2.78 \text{ in/hr}$	$4806 \text{ CF}$
23 min	$2.71 \text{ in/hr}$	$4772 \text{ CF}$
22.5 min	$2.75 \text{ in/hr}$	$4801 \text{ CF}$
21.5 min	$2.82 \text{ in/hr}$	$4801 \text{ CF}$

00 MAXIMUM STORAGE OCCURS AT  $D = 22 \text{ min}$

$V_{100 \text{ MAX}} = 4806 \text{ FT}^3$



## APPENDIX C

- DRAINAGE EXHIBITS



# Ophir Hill Offsite

C5 = 0.20

C100 = 0.50

5-year intensity = 0.94 in/hr

100-year intensity = 2.31 in/hr

## Legend

 Ophir Hill Catchment

 Ophir Hill Rd

48.6 Ac

Q5 = 9.18 cfs  
Q100 = 56.19 cfs

36" Culvert

Ophir Hill Rd


Davis Creek

Ophir Creek




2000 ft





June 6, 2022




Washoe County  
Washoe County GIS  
Source: Esri, Maxar, Earthstar Geographics, and the GIS User  
Community






June 6, 2022





Washoe County  
Washoe County GIS  
Source: Esri, Maxar, Earthstar Geographics, and the GIS User Community






PRE-DEVELOPMENT DRAINAGE AREAS								
BASIN	AREA (AC)	C <sub>5</sub>	C <sub>100</sub>	T <sub>c</sub> (MIN)	i <sub>5</sub> (IN/HR)	i <sub>100</sub> (IN/HR)	Q <sub>5</sub> (CFS)	Q <sub>100</sub> (CFS)
A1	3.04	0.13	0.37	22.79	1.11	2.69	0.45	3.02
A2	0.09	0.14	0.39	10.00	1.66	3.97	0.02	0.14
A3	0.23	0.44	0.65	10.00	1.66	3.97	0.17	0.59
A4	0.05	0.20	0.50	10.00	1.66	3.97	0.02	0.10
B1	0.09	0.35	0.45	10.00	1.66	3.97	0.05	0.16
B2	3.18	0.35	0.45	20.26	1.19	2.87	1.33	4.11
B3	6.87	0.36	0.45	18.60	1.24	3.00	3.04	9.35
B4	0.53	0.35	0.45	10.00	0.66	3.97	0.31	0.95
B5	0.62	0.35	0.45	16.80	1.31	3.14	0.28	0.88





PROPOSED DRAINAGE AREAS								
BASIN	AREA (AC)	C <sub>5</sub>	C <sub>100</sub>	T <sub>c</sub> (MIN)	i <sub>5</sub> (IN/HR)	i <sub>100</sub> (IN/HR)	Q <sub>5</sub> (CFS)	Q <sub>100</sub> (CFS)
C1	3.14	0.16	0.39	18.92	1.23	2.97	0.63	3.65
C2	0.23	0.50	0.69	10.00	1.66	3.97	0.19	0.63
C3	0.04	0.20	0.50	10.00	1.66	3.97	0.01	0.08
D1	0.06	0.20	0.05	10.00	1.66	3.97	0.02	0.12
D2	1.74	0.20	0.50	24.33	1.07	2.58	0.37	2.25
D3	0.27	0.20	0.50	10.00	1.66	3.97	0.09	0.54
D4	0.44	0.20	0.50	18.63	1.24	2.99	0.11	0.66
D5	0.74	0.44	0.62	6.70	1.97	4.73	0.64	2.17
D6	1.50	0.25	0.52	12.94	1.46	3.50	0.54	2.75
D7	1.77	0.22	0.50	12.75	1.47	3.52	0.57	3.13
D8	1.55	0.25	0.52	11.43	1.55	3.72	0.59	3.01
D9	0.12	0.20	0.50	10.00	1.66	3.97	0.04	0.24
D10	1.30	0.35	0.59	11.63	1.54	3.68	0.71	2.82
D11	1.84	0.25	0.52	13.41	1.44	3.44	0.66	3.31



9222 PROTOTYPE DRIVE  
RENO, NEVADA 89521  
PH. (775) 827-6111 | INFO@LUMOSINC.COM

BURDICK EXCAVATING CO., INC.

PRELIMINARY HYDROLOGY  
PROPOSED CONDITION AND DRAINAGE AREAS

WASHOE

COUNTY

NEVADA

Date: JUNE, 2022  
Scale: 1"=100'  
Job No: 9103.002  
FIGURE H-2



# GEOTECHNICAL INVESTIGATION REPORT

## OPHIR HILL GRADING SUP

JN: 9103.002

NEW WASHOE CITY, NEVADA

MAY 2022

**PREPARED FOR:**

BURDICK EXCAVATING  
5 BROWN DRIVE  
MOUND HOUSE, NV 89706

**PREPARED BY:**

LUMOS & ASSOCIATES, INC.  
808 E. COLLEGE PARKWAY, SUITE 101  
CARSON CITY, NEVADA 89706  
775.883.7077



## TABLE OF CONTENTS

	<b>Page</b>
<b>1.0 Introduction .....</b>	<b>1</b>
<b>2.0 Geologic Setting .....</b>	<b>3</b>
<b>3.0 Seismic Consideration .....</b>	<b>4</b>
<b>4.0 Site Conditions and Field Exploration .....</b>	<b>6</b>
Table 1 – Existing Depth of Debris Flow Material .....	7
<b>5.0 Field and Laboratory Test Data .....</b>	<b>8</b>
<b>6.0 Discussion and Recommendations.....</b>	<b>9</b>
6.1 General .....	9
6.2 General Site Grading.....	9
6.2.1 Clearing and Grubbing .....	9
6.2.2 Unsuitable Subgrade Mitigation .....	10
6.2.3 Structural Fill .....	11
Table 2 – Structural Fill/Trench Backfill Gradation.....	12
6.3 Debris Flow Protection and Remediation .....	13
<b>7.0 Foundation Design Criteria .....</b>	<b>14</b>
<b>8.0 Concrete Slab Design.....</b>	<b>16</b>
<b>9.0 Retaining Walls .....</b>	<b>17</b>
<b>10.0 Pavement Design .....</b>	<b>18</b>
Table 3– Recommended Asphalt Pavement Section.....	18
<b>11.0 Corrosion and Chemical Attack .....</b>	<b>19</b>
<b>12.0 Slope Stability and Erosion Control .....</b>	<b>20</b>
<b>13.0 Utility Excavations.....</b>	<b>20</b>
<b>14.0 Moisture Protection, Erosion, and Drainage .....</b>	<b>21</b>
<b>15.0 Construction Specifications .....</b>	<b>21</b>
<b>16.0 Limitations .....</b>	<b>22</b>
<b>17.0 References .....</b>	<b>24</b>

### List of Plates

- 1 Project Vicinity
- 2 Project Site Map
- 3 Project Geologic Map
- 4 Project Fault Map
- 5 Major Earthquake and Seismic Belts
- 6 Modified Mercalli Scale

### List of Appendices

- Appendix A – Field Exploration Logs
- Appendix B – Soils Laboratory Test Results
- Appendix C – Design Response Spectrum
- Appendix D – Pavement Design

---

### 1.0 INTRODUCTION

Submitted herewith are the results of Lumos and Associates, Inc. (Lumos) geotechnical investigation for the proposed residential Development to be located on parcels 046-032-02, -04 and, -05 in New Washoe City, Nevada. The properties are currently being utilized for the manufacture and excavation of landscape boulders and sand materials used in construction and landscaping. The properties are bounded by Old US 395 to the West and both privately and publicly owned parcels to the North, South, and East. A vicinity map is included as Plate 1 and a site map is included as Plate 2.

We understand improvements on the 11.29-acre site will consist of four (4) residential structures with conventional spread footings and concrete slabs-on-grade, with asphalt pavement and associated concrete hardscapes. The anticipated loads for the project have been assumed to be less than four (4) to five (5) kips/linear foot for continuous footings and sixty (60) to sixty-five (65) kips for isolated interior footings. We have assumed that the final grades will be within ten (10) feet of existing grades.

The purpose of our investigation was to characterize the site geology and soil conditions, describe the native soils, and determine their engineering properties as they relate to the proposed construction. The investigation was also intended to identify possible adverse geologic, soil, and or water table conditions. However, this study did not include an environmental assessment, a fault study, a liquefaction study or an evaluation for soil and/or groundwater contamination at the site.

This report concludes with recommendations for site grading, foundations, footing area preparation, utility installation, asphalt concrete pavement, and Portland cement concrete.



In addition, information such as logs of all test pits, allowable soil bearing capacities, estimated total and differential settlements, moisture and drainage protection and International Building Code (IBC) seismic site class designation are provided in this report.

The recommendations contained herein have been prepared based on our understanding and assumptions of the proposed construction, as outlined above. Re-evaluation of the recommendations presented in this report should be conducted after the final site grading and construction plans are completed, if there are any variations from the assumptions described herein.

It is possible that subsurface discontinuities may exist between and beyond exploration points. Such discontinuities are beyond the evaluation of the Engineer at this time. No guarantee of the consistency of site geology and sub-surface conditions is implied or intended.

## 2.0 GEOLOGIC SETTING

New Washoe city is located at the western portion of the Great Basin geomorphic province. The Great Basin is characterized by large normal fault-bounded valleys (grabens) that are separated by large mountain ranges (horst). The Sierra Nevada province to the west is characterized by large granite masses that have been uplifted and tilted a few degrees toward the west. Overlying the granites are older oceanic meta-sedimentary rocks. The geologic evolution of the region involves uplift, volcanism, extension, and sedimentation. All these factors have contributed to the current "Basin and Range" physiography.

Specifically the project site is located in a region historically known for landslides. The South East face of Slide Mountain, located approximately three miles from the site, periodically shears away from the greater mountain sending millions of cubic yards of granite rock and decomposed granite down Ophir Creek. Through geologic surveys, multiple landslides from Slide Mountain have been identified and dated at occurring all the way back to the Pleistocene era (2.6 million to 11,700 years ago). The most recent large scale landslide event took place in 1983, where an estimated 1.4 million cubic yards of material sweep into the Washoe Valley. In 2019 C. Carlson, R. Koehler, and C. Henry mapped the geologic conditions surrounding Washoe City. Their investigation determined soils conditions beneath the site to be younger alluvial fan deposits and historical debris flow deposits.



**Image 1: Slide Mountain**

### 3.0 SEISMIC CONSIDERATIONS

New Washoe City, similar to many areas in Nevada, is located near active faults that are capable of producing significant earthquakes. We reviewed the Quaternary Fault Map of Nevada's interactive map (<https://www.arcgis.com/apps/webappviewer/index.html>) which shows the nearest active fault of Holocene age (<15,000 years), the Mount Rose Fault Zone, to be two-thousand (2000) feet to the West of the site. No Holocene faults extend into the site and no evidence of faulting was noted during our site investigation. Refer to Plate 4. The maximum credible earthquake (MCE) for the vicinity of the project is estimated at 7.5 in moment magnitude and many large earthquakes have occurred near the site as presented on Plate 5. This correlates to a Modified Mercalli Intensity of IX-X. Refer to Plate 6.

Liquefaction is the phenomenon where loose saturated granular soils lose their shear strength when subjected to strong vibration or cyclical loading and become unstable. Large earthquakes, as described above, may provide that type of cyclical loading. Loose saturated sands are the most susceptible to this phenomena. These conditions were not encountered during our field investigation. The soils encountered on-site were primarily slightly moist to moist, loose to medium dense sands with a varying matrix of silts, gravel, cobbles, and boulders. Therefore, the liquefaction of subsurface soils at the site is not considered likely to occur. The majority of any structural damage to buildings at this site is most likely to be the result of strong seismic shaking rather than subsurface soil liquefaction.

2018 IBC Design: The mapped maximum considered earthquake spectral response acceleration at short periods ( $S_s$ ) is 2.15g corresponding to a 0.2 second spectral response acceleration at five percent (5%) of critical damping and for a Site Class B (IBC Figure 1613.2.1(1)). The mapped maximum considered earthquake spectral response acceleration at a 1-second period ( $S_1$ ) is 0.764g corresponding to a 1.0 second spectral response acceleration at five percent (5%) of critical damping and for a Site Class B (IBC Figure 1613.2.1(2)). At this time, the soil conditions are not known in sufficient detail to a depth of 100 feet, thus, a Site Class D-default may be assumed per the IBC. These spectral response accelerations are adjusted for site class effects

because Site Class D-default is assumed instead of Site Class B. The site coefficient for spectral response accelerations adjustment at short periods ( $F_a$ ) is 1.2 (IBC Table 1613.2.3(1) and Section 1613.2.2). The maximum considered earthquake spectral response acceleration parameter for short period ( $S_{MS}$ ) is 2.58g. This corresponds to design spectral response acceleration parameters of 1.72g for short period ( $S_{DS}$ ). Refer to Appendix C.

It is emphasized that the above values are the minimum requirements intended to maintain public safety during strong ground shaking. These minimum requirements are meant to safeguard against loss of life and major structural failures, but are not intended to prevent damage or insure the functionality of the structure during and/or after a large seismic event.

The seismic risks at this site are similar to other sites within western Nevada. The risks associated with this site can be mitigated utilizing widely accepted design and construction standards.



## **4.0 SITE CONDITIONS AND FIELD EXPLORATION**

At the time of our investigation, the site had been partially developed with utilities and non-permanent structures. The site slopes downwards towards Washoe Lake at approximately a 4.8% slope. Vegetation consists of sparsely located trees around the perimeter of the property.

The current field investigation included a site reconnaissance and subsurface exploration. During the site reconnaissance, surface conditions were noted, and the location of the exploratory test pits were determined by utilizing existing features on the site. Therefore, the approximate location of the test pits should be considered accurate only to the degree implied by the methods used.

Seven (7) test pits were excavated within the proposed improvement areas to a maximum depth of fifteen (15) feet below-ground-surface (bgs). The locations of the exploratory test pits within the site are shown on Plate 2. The subsurface soils were continuously logged and visually classified in the field by our Geotechnician in accordance with the Unified Soil Classification System (USCS). Along with classification of the subsurface soils, the current depth of debris flow material was identified and logged. Debris flow material depths were identified through the visual observation of the trench wall lithology during excavation and the presence of organic or otherwise non-native materials present in the trench spoils. Table 1 shows the identified depth of debris flow material determined in each test pit.



**Image 2: Clear Delineation Between Debris Flow Material**

**TABLE 1  
EXISTING DEPTH OF DEBRIS FLOW MATERIAL**

<b>Exploration</b>	<b>Depth of Debris Flow Material</b>
TP-1	8 Feet
TP-2	7 Feet
TP-3	No Certain Depth Identified
TP-4	8 Feet
TP-5	4 Feet
TP-6	6 Feet
TP-7	8 Feet

The subsurface soils encountered consisted generally of poorly graded to well graded sands (SP or SW) with varying amounts of silt, silty sands (SM), and poorly-graded sands (SP) to the total depths explored for this project. The debris flow material was clearly identified in all test pits except for test pit 3. The debris flow material contained varying amounts of cobbles and boulders with the maximum particle size encountered being approximately four (4) feet in diameter. Uncontrolled fill, containing debris, was encountered in test pit 3 to approximately four (4) feet below existing ground surface. Uncontrolled fill and disturbed soils are not suitable to provide direct structural support due to their settlement potential. Groundwater was not encountered at the time of our investigation and is not expected to impact the development of this site. However, seasonal groundwater fluctuations should be anticipated at the site.

## 5.0 FIELD AND LABORATORY TEST DATA

Field data was developed from samples taken and tests conducted during the field exploration and laboratory testing phases of this project. The test pits were excavated using a Caterpillar 330 DL excavator and samples of each material encountered were collected using bulk sampling techniques. All the samples were subsequently transported to our Carson City geotechnical laboratory for testing and analysis.

Laboratory tests performed on representative samples included sieve analysis (included fines), Atterberg limits, modified proctor, resistance value, direct shear, soluble sulfates, pH value, resistivity, and solubility. Much of this data is displayed on the "logs" of the exploratory test pits to facilitate correlation. Field descriptions presented on the logs have been modified, where appropriate, to reflect laboratory test results. The logs of the exploratory test pits are included in Appendix A of this report as Plates A-1 to A-7. A key to the logs is included as Plate A-8.

Individual laboratory test results are presented in Appendix B as Plates B-1 through B-6. Laboratory testing was performed per ASTM standards, except when test procedures are briefly described and no ASTM standard is specifically referenced in the report. Atterberg limits were determined using the dry method of preparation.

**Analytical Testing:** Silver State Laboratory, Inc. of Reno, Nevada, conducted this laboratory testing. Testing results are included (Silver State's letterhead) as Plate B-6.

The soil samples obtained during this investigation will be held in our laboratory for 30 days from the date of this report. The samples may be retained longer at an additional cost to the client or obtained from this office upon request.

## **6.0 DISCUSSION AND RECOMMENDATIONS**

### **6.1 General**

From a geotechnical viewpoint, the site is considered suitable for the proposed development when recommended herein.

The following recommendations are based upon the construction and our understanding and assumptions of the proposed improvements, as outlined in the introduction of this report, and based on our findings during the field exploration phase of this project. If changes in the construction project are proposed, they should be presented to Lumos & Associates, Inc., so that the recommendations provided herein can be reviewed and modified as necessary. As a minimum, final construction drawings should be submitted to Lumos for review prior to actual construction and verification that our Geotechnical design recommendations have been implemented

### **6.2 General Site Grading**

#### **6.2.1 Clearing and Grubbing**

Prior to placement of fill and/or the proposed improvements, the areas to receive fill and/or improvements shall be cleared and grubbed. Clearing and grubbing should be anticipated to be as much as eight (8) inches.

Root- or organic-laden soils encountered during excavations, should be stockpiled in a designated area on site for later use in landscaping, or removed off site as directed by the owner. Excavated soils free from any organics, debris or otherwise unsuitable material and with particles no larger than four (4) inches in maximum dimension may be stockpiled and moisture conditioned for later use as compacted fill provided it meets the criteria for structural fill soils.



Exposed excavation surfaces to support any of the proposed improvements should be observed and approved by a Lumos representative. Upon re-compaction and prior to placing any base, the re-compacted surface should be proof-rolled to identify any possible yielding surfaces. Proof-rolling should be conducted with a heavy rubber-tire loader with a fully loaded bucket, or a fully loaded water truck, and observed and approved by a Lumos representative.

### 6.2.2 Unsuitable Subgrade Mitigation

Unstable conditions due to yielding and/or pumping soils may be encountered on site. Additionally, the exposed soils may yield or pump under heavy equipment loads or where vibratory equipment draws up water. If yielding or pumping conditions are encountered, the soils should be scarified in place, allowed to dry as necessary and re-compacted, where applicable. Alternatively, unsuitable or saturated soil should be removed, the exposed surface leveled and compacted/tamped as much as practical without causing further pumping, and covered (including the sides) with geotextile stabilizing fabric (Mirafi HP370 or other equivalent). The fabric should then be covered with at least 12 inches of 4 to 8 inch **angular rock fill** with enough fines to fill the inter-rock pore spaces. Placement should be by end dumping. No traffic or other action should be allowed over the fabric, which may cause it to deflect/deform prior to cobble placement. Test sections should be used to determine the minimum thickness and/or number of layers required for stabilization.

Stabilization should be evaluated by proof-rolling standards commensurate with the equipment used, and approved by a Lumos representative. The placement of the stabilizing rock-fill may require additional over-excavation to maintain appropriate grading elevations. A filter fabric (Mirafi 180N or equal) should also be placed over the cobble rock fill to prevent piping of fines from covering soils into the stabilizing rock matrix.

The uncontrolled fill (Poorly Graded Sand with Silt Chunks (SM)), as encountered in the upper four (4) feet of test pit 3, shall be completely removed, when encountered, from below the structures and improvements and to a distance of two (2) feet beyond improvements/foundations horizontally. Once excavated the material may be screened to completely remove debris. This "screened" material may be utilized as structural fill/trench backfill provided it meets the criteria

stated in the following section (6.2.3). The exposed surface shall be scarified to a depth of twelve (12) inches, moisture conditioned to within two percent (2%) of optimum and compacted to at least ninety-five percent (95%) relative compaction as determined by the ASTM D 1557 Standard.

The landslide material (Poorly Graded Sands with Silt (SP-SM), Well Graded Sands with Silt (SW-SM) and, Silty Sand (SM)) as encountered in the upper four (4) to eight (8) feet of test pits 1, 2, 4, 5, 6, and 7, which are anticipated throughout the entire site, require mitigation due to the relatively low in-place density tests and large quantity of boulders encountered during our field investigation. Our recommended mitigation is to remove the upper three (3) feet of these soils from below future foundations and slabs and two (2) feet below future roadways. The removal shall extend a minimum of two (2) feet beyond the proposed improvements/foundations. These soils may be reutilized as structural fill provided the particles larger than four (4) inches are removed and they meet the criteria stated in the following section (6.2.3). The exposed surface shall be scarified to a depth of twelve (12) inches, moisture conditioned to within two percent (2%) of optimum and compacted to at least ninety-five percent (95%) relative compaction as determined by the ASTM D 1557 Standard.

### **6.2.3 Structural Fill and Trench Backfill**

Properly compacted structural fill and trench backfill soils to be used on site should consist of non-expansive materials [LL less than thirty-five (35) and/or a PI less than twelve (12) and/or Expansion Index less than twenty (20)], should be free of contaminants, organics [less than two (2) percent], rubble, or natural rock larger than four (4) inches in largest dimension and have a minimum R-Value of thirty (45). All structural fill and trench backfill soils shall also be non-corrosive and have a water soluble sulfate content of less than one-tenth (0.1) percent. Structural fill and trench backfill soils shall also meet the following gradation requirements:

**TABLE 2  
STRUCTURAL FILL/TRENCH BACKFILL GRADATION**

<b>Sieve Size</b>	<b>% Passing</b>
4"	100
¾"	70 - 100
#40	15 - 65
#200	5 - 25

Structural fill and trench backfill soils that do not meet the above requirements may be approved at the discretion of the Geotechnical Engineer. The site soils (SP-SM, SW-SM, and SM) encountered during the exploration are suitable for reuse as structural fill/trench backfill provided the particles larger than four (4) inches are removed and the recommendations that follow in this section are adhered to.

Prior to placement of structural fill, the site subgrade shall be scarified to a depth of twelve (12) inches, oversized material removed (+4"), moisture conditioned to within two percent (2%) of optimum, and recompact to a minimum of ninety-five percent (95%) as determined by the ASTM D1557 Standard.

Structural fill and trench backfill should be placed only on compacted sub-grade or on compacted fill in loose lifts not exceeding twelve (12) inches, moisture conditioned to within two percent (2%) of optimum and compacted to at least ninety-five percent (95%) relative compaction as determined by the ASTM D1557 Standard.

Fill material should not be placed, spread or compacted while the ground is frozen or during unfavorable weather conditions. When site grading is interrupted by heavy rain or snow, grading or filling operations should not resume until a Lumos representative approves the moisture content and density conditions of the subgrade or previously placed fill. When fill is placed on existing slopes steeper than 5:1, the existing slope shall be horizontally benched.

Landscape areas should be cleared of all objectionable material. In cut areas, no other work is necessary except grading to proper elevation. In landscape areas, fill should be placed in loose lifts not exceeding eight inches and compacted to at least ninety percent (90%) relative compaction to prevent erosion.

Water should not be allowed to pond on pavements or adjacent to structures, and measures should be taken to reduce surface water infiltration into the subgrade soils. A representative of Lumos should be present during site grading operations to ensure any unforeseen or concealed conditions within the site are identified and properly mitigated, and to test and observe earthwork construction. This testing and observation is an integral part of our service as acceptance of earthwork construction is dependent upon compaction and stability of the subgrade soils. The soils engineer may reject any material that does not meet engineering characteristics, compaction, and stability requirements. Further, recommendations of this report are based upon the assumption that earthwork construction will conform to recommendations set forth in this section of the report.

### **6.3 Debris Flow Protection and Remediation**

Due to the site's location directly in-line with the outflow of Ophir Creek results in the site requiring protection from possible debris flows generated from Slide Mountain. A number of debris flows have been identified to have crossed through the site. An engineered system should be developed in order to protect from the loss of life and property during a debris flow event. There are many accepted landslide protection systems including: gravity retaining walls, crib-block walls and, reinforced concrete walls. Due to the potential risk associated with the site's location we recommend a landslide hazard investigation and assessment in order to appropriately design a protective system.



## 7.0 FOUNDATION DESIGN CRITERIA

Conventional spread footings founded on properly prepared structural fill, as discussed earlier in the report, may be used to support the proposed buildings within the project site.

**Spread footings:** Footings should have a minimum embedment of twenty-four (24) inches below lowest adjacent grade for frost protection. Footings founded on properly prepared structural fill as discussed earlier in this report may be designed for a net allowable bearing pressure of 1,500 pounds-per-square-foot (psf). This relatively low bearing value allows for partial removal and recompaction of the debris flow material from beneath the foundations and roadway improvements, as previously discussed.

**Footing Settlements:** The maximum anticipated settlements, caused by static loading, for continuous or isolated footings bearing on properly prepared structural fill/suitable subgrade and designed for a 1,500 (psf) bearing pressure is estimated at one (1) inch or less. Differential settlements are generally expected to be half of the total settlements. Settlements in granular soils are primarily expected to occur shortly after dead and sustained live loads are applied.

**Lateral Loading:** Resistance to lateral loads can be provided by friction acting at the base of foundations and by lateral earth resistance. A coefficient of friction of 0.45 may be assumed at the base of footings supported by properly compacted structural fill. An allowable passive earth resistance of 250 psf per foot of depth starting six (6) inches below lowest adjacent grade may be used for the sides of footings poured against properly compacted structural fill. Passive resistance should not exceed 1,500 psf. The at-rest lateral pressure can be calculated utilizing an equivalent fluid pressure of 65 pcf.

**Dynamic Factors:** Vertical and lateral bearing values indicated above are for total dead-load and frequently applied live loads. If normal code requirements are applied for design, the above vertical bearing values may be increased by thirty-three percent (33%) for short duration loading due to wind or seismic forces. The additional Dynamic Lateral earth pressure can be calculated utilizing the following equation.

Dynamic Lateral Force (Non-Yielding Walls) =

$$\gamma K_h H^2 = 90H^2$$

Dynamic Lateral Force (Yielding Walls) =

$$3/8 \gamma K_h H^2 = 34H^2$$

Horizontal Acceleration =  $K_h$  =

$$SD_s/2.5 = 0.69$$

Unit Weight of Soil =  $\gamma$  = 130 pcf

Height of Wall = H

This force should be assumed to act at a height of 0.6H above the bottom of the wall.

## **8.0 CONCRETE SLAB DESIGN**

Interior concrete slabs should be underlain with at least six (6) inches of Type 2, Class B, Aggregate Base, compacted to a minimum of ninety-five percent (95%) and supported on at least thirty-six (36) inches of properly prepared structural fill. A vapor barrier should be provided for all interior concrete slabs where floor moisture is undesirable. The vapor barrier should be a synthetic plastic sheeting at least ten (10) mils thick and meet the requirements of the ASTM E1745 for Class A vapor retarder materials. The vapor barrier shall be installed per the manufacturer's recommendations. We recommend utility trenching be completed prior to vapor barrier and base placement.

Slab thickness design should be based on a Modulus of Subgrade Reaction equal to two hundred (200) pounds-per-cubic-inch (pci) for construction on properly compacted aggregate base/structural fill. Reinforcement of concrete slabs should be as specified by the Project Structural Engineer.

Exterior concrete slabs on grade for vehicular traffic and driveways should be underlain with at least six (6) inches of Type 2, Class B aggregate base and twenty-four (24) inches of properly compacted structural fill. All subgrade and fill should be prepared and placed as described in the grading section of this report, while the aggregate base should be compacted to at least ninety-five percent (95%) relative compaction.

## 9.0 RETAINING WALLS

Retaining structures over three (3) feet in height, if used, will require local code compliance and engineered based on parameters described in this section of the report. Retaining structures should be designed to resist the appropriate lateral earth pressures. Cantilevered walls, which are able to deflect at least 0.01 radians, can be designed using an equivalent fluid (backfill) unit weight of 45 pounds-per-cubic-foot (pcf). However, if the wall is fixed against rotation, the wall should be designed using an equivalent fluid (backfill) unit weight of 65 pcf. These design parameters are based upon the assumption that walls will retain only level backfill and no hydrostatic pressure will be present. Any other surcharge pressures (such as sloped backfill) should be added to the above recommended lateral earth pressures. Retaining walls should be backfilled with free draining granular material that extends vertically to the bottom of the stem and laterally at least six (6) inches beyond the face of the stem (wall) and wrapped with a Mirafi 180 N or equivalent non-woven filter fabric. Weep holes should be provided on the walls at regular intervals, or a slotted drainpipe placed at the bottom of the wall (bottom of granular material) to relieve any possible build-up of hydrostatic pressure. Backfill material within two (2) feet of the wall should be compacted with hand-held equipment only, to at least ninety percent (90%) of the maximum ASTM D1557 standard. A brow ditch shall be constructed in the pre-retained earth parallel to the retaining wall to divert surface runoff.



## **10.0 PAVEMENT DESIGN**

As previously discussed, the upper two (2) feet of soils shall be removed and recompact. Prior to the placement and recompaction of the excavated material, the subgrade soils should be scarified in place to a depth of at least twelve (12) inches, moisture conditioned to within two percent (2%) of optimum, and compacted to at least ninety-five percent (95%) of the laboratory maximum dry density determined by the ASTM D1557 standard. Pavement structural sections utilizing an R-value of forty-five (45) for structural fill/backfill, and seventy (70) for aggregate base, are provided in Table 2, "Recommended Pavement Section". A Traffic Index (TI) value of 5.0, for light traffic areas was utilized in design. Aggregate base should consist of Type 2, Class B material and meet the requirements of the Standard Specifications for Public Works Construction (SPPWC). Aggregate base material should be compacted to at least ninety-five percent (95%) of the laboratory maximum density as determined by the ASTM D1557 standard.

**TABLE 3  
RECOMMENDED ASPHALT PAVEMENT SECTION**

<b>Assumed Traffic Index</b>	<b>Minimum Asphalt Pavement</b>	<b>Minimum Aggregate Base</b>	<b>Properly Prepared Suitable Subgrade/Structural Fill</b>
Local Road TI = 5.0	3"	4"	24"

**\*See Appendix D for Calculations.**

In all areas of the project, asphalt concrete should consist of PG64-28NV, and Type 3 asphalt aggregate per the "Orange Book" standards. We recommend a 50-blow Marshall mix that targets three percent (3%) air voids. Asphalt concrete, in any case, should be compacted to between ninety-three percent (93%) and ninety-eight percent (98%) of the Rice theoretical maximum density.

**All mix designs for asphalt concrete should be submitted to the Geotechnical Engineer for review and approval a minimum of seven (7) days prior to paving.**

## **11.0 CORROSION AND CHEMICAL ATTACK**

On-site soils have a negligible water soluble sulfate content of less than 0.1% (0.01%). However, Type II cement (meeting ASTM C150) is recommended for concrete in direct contact with on-site soils.

All exterior concrete should have between 4.5 and 7.5 percent entrained air, a maximum water-cement ratio of 0.45 and comply with all other ACI recommendations for concrete placed in areas subject to freezing. A minimum compressive strength of 4,000 psi is recommended for all external concrete. All interior concrete shall be placed pursuant to ACI recommendations.

Native soils have a pH of 5.64 and have a resistivity of 17,000 ohm-cm under saturated conditions. This indicates mildly corrosive potential for ferrous metals in contact with these soils. However, corrosion prevention measures are recommended. If protective coatings are used, the type and quantity will depend on the kind of steel and specific construction application. Steel and wire concrete reinforcement cover of at least three (3) inches where cast against soil, unformed, is recommended.

Solubility of native soils was measured at 0.3% which indicates that the site soils have a low solubility.

## **12.0 SLOPE STABILITY AND EROSION CONTROL**

The results of our exploration and testing confirm that 3:1 (H:V) maximum slopes will be stable for on-site materials both in cut and fill. All slopes shall incorporate a brow ditch to direct surface drainage away from the slope face. Slopes steeper than 3:1 will require stabilization, such as retaining walls.

The potential for dust generation is high at this project. Dust control will be mandatory on this project in order to comply with air quality standards. The contractor shall be responsible for submitting a dust control plan and securing any required permits.

Stabilization of all slopes and areas disturbed by construction will be required to prevent erosion and to control dust. Stabilization may consist of rip-rap, revegetation, or dust palliative, depending on the inclination of the slope.

## **13.0 UTILITY EXCAVATIONS**

On-site soils are anticipated to be excavatable with conventional construction equipment. Compliance with OSHA regulations should be enforced for Type C soils. The site soils encountered during the exploration are anticipated to be suitable for backfill of utility trenches, provided oversized (+4") material and debris is removed as discussed earlier in this report. Trench backfill/structural fill shall be moisture conditioned, placed and compacted as previously discussed in the grading and filling section. On-site soils encountered during our field exploration are not suitable for bedding sand (Class A Backfill). Therefore, import of Class A Bedding materials is warranted. Bedding sand shall be placed in eight (8) inch maximum loose lifts and compacted to a minimum of ninety percent (90%) of the ASTM D1557 Standard.

## **14.0 MOISTURE PROTECTION, EROSION AND DRAINAGE**

The finish surfaces around all structures should slope away from the foundations and toward appropriate drop inlets or other surface drainage devices. It is recommended that within ten (10) feet of any structure a minimum slope of five percent (5%) be used for soil subgrade and a minimum of one percent (1%) be used for pavement. These grades should be maintained for the life of the structures.

## **15.0 CONSTRUCTION SPECIFICATIONS**

All work shall be governed by the 2018 International Building Code and Standard Specifications and Standard Details for Public Works Construction (SSPWC) 2012/Revision 8, as distributed by Washoe County, except as modified herein.



## **16.0 LIMITATIONS**

This report has been prepared in accordance with the currently accepted engineering practices in Northern Nevada and Northern California. The analysis and recommendations in this report are based upon exploration performed at the locations shown on the site plan, the proposed improvements as described in the Introduction section of this report and upon the property in its condition as of the date of this report. Lumos makes no guarantee as to the continuity of conditions as subsurface variations may occur between or beyond exploration points and over time. Any subsurface variations encountered during construction should be immediately reported to Lumos so that, if necessary, Lumos' recommendations may be modified.

This report has been prepared for and provided directly to Burdick Excavating ("The Client"), and any and all use of this report is expressly limited to the exclusive use of the Client. The Client is responsible for determining who, if anyone, shall be provided this report, including any designers and subcontractors whose work is related to this project. Should the Client decide to provide this report to any other individual or entity, Lumos shall not be held liable for any use by those individuals or entities to whom this report is provided. The Client agrees to indemnify, defend and hold harmless Lumos, its agents and employees from any claims resulting from unauthorized users.

If this report is utilized in the preparation of an Engineer's Estimate of Probable Construction Costs, then the preparer of the estimate acknowledges that the report recommendations are based on the subsurface conditions found at the specific locations investigated on site; that subsurface conditions may vary outside these locations; and that no guaranty or warranty, express or implied, is made that the conditions encountered are representative of the entire site. The preparer of the estimate agrees to indemnify, defend and hold harmless Lumos & Associates, its agents and employees from any and all claims, causes of action or liability arising from any claims resulting from the use of the report in the preparation of an Engineer's Cost Estimate.

## GEOTECHNICAL INVESTIGATION REPORT

This report is not intended for, nor should be utilized for, bidding purposes. If it is utilized for bidding purposes, Client acknowledges that the report recommendations are based on the subsurface conditions found at the specific locations investigated on site; that subsurface conditions may vary outside these locations; and that no guaranty or warranty, express or implied, is made that the conditions encountered are representative of the entire site. The Client agrees to indemnify, defend and hold harmless Lumos & Associates, Inc., its agents and employees from any and all claims, causes or action or liability arising from any claims resulting from the use of the report for bidding purposes.

As explained above, subsurface variations may exist and as such, beyond the express findings located in this report, no warranties express, or implied, are made by this report. No affirmation of fact, including but not limited to statements regarding suitability for use of performance shall be deemed to be a warranty or guaranty for any purpose.




Jeremy Macaluso, E.I.  
Field Technician II  
Lumos & Associates, Inc.



Mitch Burns, P.E., C.E.M.  
Materials Engineering Manager  
Lumos & Associates, Inc.

## 17.0 References

- American Society for Testing and Materials (ASTM), 2020, Annual Book of ASTM Standards, West Conshohoken
- Carlson, C.W., Koehler, R.D., and Henry, C.d., 2019, Geologic map of the Washoe City quadrangle, Washoe County, Nevada: Nevada Bureau of Mines and Geology open-File Report 19-4, scale 1:24,000, 7 p.
- International Conference of Building Officials, 1997, Uniform Building Code (UBC), ICBO, Whittier, CA
- International Conference of Building Officials, 2018, International Building Code (IBC), ICBO, Whittier, CA
- Naval Facilities Engineering Command, 1986, Design Manual 7.01
- Naval Facilities Engineering Command, 1986, Design Manual 7.02
- Occupational Safety and Health Administration (OSHA), 1995, Occupational Safety and Health Standards for the Construction Industry, Commerce Clearing House, Inc.
- USGS 2002 Website, [www.usgs.gov](http://www.usgs.gov)



5/13/2022, 8:54:34 AM

1:36,112  
0 0.23 0.45 0.9 mi  
0 0.38 0.75 1.5 km

Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand),



**Lumos & Associates**  
808 E. College Parkway, Suite 101  
Carson City, NV 89703  
775.883.7077  
Fax: 775.883.7114  
mburns@lumosinc.com


## Ophir Hills Grading SUP PROJECT VICINITY

Job Number: 9103.002

Date: May 2022

**PLATE**  
**1**





Test Pit Location



Project Limits



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP  
**PROJECT SITE MAP**

Job Number: 9103.002

Date: May 2022

**PLATE**  
**2**





- Qfy Young alluvial-fan deposits (late Holocene)
- Qdf<sub>1</sub> Debris-flow deposits (historical)



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## PROJECT GEOLOGIC MAP

Job Number: 9103.002

Date: May 2022

**PLATE**

**3**






5/13/2022, 10:08:39 AM

Linear Faults

- |                             |                          |
|-----------------------------|--------------------------|
| — Class B years             | — Less than 15,000 years |
| — Less than 1,600,000 years | — Less than 150 years    |
| — Less than 750,000 years   | — Unknown                |
| — Less than 130,000 years   |                          |



USGS The National Map: Orthoimagery and US Topo. Data refreshed January, 2022., Acknowledgment of the Quaternary Faults and Fold Database, the U.S. Geological Survey, and (or) the National Atlas of the United States of America would be appreciated in products derived from these data.



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## PROJECT FAULT MAP


Job Number: 9103.002

Date: May 2022

**PLATE**

**4**







# MODIFIED MERCALLI INTENSITY SCALE

INTENSITY	EFFECTS
I	Not felt except by a very few under especially favorable circumstances.
II	Felt only by a few persons at rest, especially on upper floors of buildings. Delicately suspended objects may swing.
III	Felt quite noticeable indoors, especially on upper floors of buildings, but many people do not recognize it as an earthquake. Standing motor cars may rock slightly. Vibration like passing of truck. Duration estimated.
IV	During the day felt indoors by many, outdoors by few. At night some awaken. Dishes, windows, doors disturbed; walls make cracking sound. Sensation like heavy truck striking building; standing motor cars rock noticeably.
V	Felt by nearly everyone; many awakened. Some dishes, windows, etc., broken; a few instances of cracked plaster; unstable objects overturned. Disturbance of trees, poles, and other tall objects sometimes noticed. Pendulum clocks may stop.
VI	Felt by all; many frightened and run outdoors. Some heavy furniture moved; a few instances of fallen plaster or damaged chimneys. Damage slight.
VII	Everybody runs outdoors. Damage negligible in buildings of good design and construction; slight to moderate in well-built ordinary structures; considerable in poorly built or badly designed structures; some chimneys broken. Noticed by persons driving motor cars.
VIII	Damage slight in specially designed structures; considerable in ordinary substantial buildings with partial collapse; great in poorly built structures. Panel walls thrown out of frame structures. Fall of chimneys, factory stacks, columns, monuments, walls. Heavy furniture overturned. Sand and mud ejected in small amounts. Changes in well water. Disturbs persons driving motor cars.
IX	Damage considerable in specially designed structures; well-designed frame structures thrown out of plumb; great in substantial buildings, with partial collapse. Buildings shifted off foundations. Ground cracked conspicuously. Underground pipes broken.
X	Some well-built wooden structures destroyed; most masonry and frame structures with foundations destroyed; ground badly cracked. Rails bent. Landslides considerable from river banks and steep slopes. Shifted sand and mud. Water splashed (sloped) over banks.
XI	Few, if any (masonry) structures remain standing. Bridges destroyed. Broad fissures in ground. Underground pipe lines completely out of service. Earth slumps and land slips in soft ground. Rails bent greatly.
XII	Damage total. Waves seen on ground surfaces. Lines of sight and level distorted. Objects thrown upward into the air.

From Wood and Newman, 1931, by U.S. Geological Survey, 1974, Earthquake Information Bulletin, v. 6, no. 5, p. 28

Richter Magnitude	Intensity (maximum expected Modified Mercalli)
3.0 - 3.9	II - III
4.0 - 4.9	IV - V
5.0 - 5.9	VI - VII
6.0 - 6.9	VII - VIII
7.0 - 7.9	IX - X
8.0 - 8.9	XI - XII



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## MODIFIED MERCALLI SCALE

Job Number: 9103.002

Date: May 2022

**PLATE**

**5**

# **APPENDIX A**

## **Field Exploration Logs**

# EXPLORATION No. TP #1

Logged By: **J. Macaluso**  
 Date Logged: **5/5/2022**  
 Equipment Type: **CAT. 330 DL Excavator**

Total Depth: **14 feet**  
 Water Depth: **No groundwater encountered**  
 Ground Elev.: **Existing Grade**

Depth in Feet	Graphic Log	Sample Type	<div><div><div><div></div></div><div>Percolation Test</div></div><div><div><div></div></div><div>Core Sampler</div></div></div> <div><div><div><div></div></div><div>Split Spoon</div></div><div><div><div></div></div><div>Bulk Sample</div></div></div> <div><div><div><div></div></div><div>Ziplock Sample</div></div><div><div><div></div></div><div>Static Water Table</div></div></div>	Natural Moisture Content, %	In-Place Moisture Content, %	In Place Dry Density, pcf	Liquid Limit, %	Plasticity Index, %	Gravel, % (3" - #4 Sieve)	Sand, % (#4 - #200 Sieve)	Fines, % (< #200 Sieve)	R-Value	Expansion Index
			SOIL DESCRIPTION										
1			<b>Medium Brown Poorly Graded SAND with Silt, Gravel, Cobbles, and Boulders (SP-SM)</b> Loose-Medium Dense, Slightly Moist Estimated: 20% Unclassifiable Rounded to Subangular Cobbles & Boulders Up to 4' in Diameter Remainder of Soil Matrix Consisting of 20% Coarse to Fine Gravel, 70% Coarse to Fine Sand, 10% Fines										
2													
3		B		3.1	101.7								
4				4.6	102.4								
5													
6													
7			Boulders Not Present After a Depth of 7' Organic Material (Tree Branches) at a Depth of 8' Bottom of Landslide Material	8.0									
8			<b>Tan Poorly Graded SAND (SP)</b> Loose-Medium Dense, Slightly Moist Estimated: 20% Coarse to Fine Gravel 80% Coarse to Fine Sand Trace Fines										
9		B											
10													
11		B											
12				Material Moist at a Depth of 12'									
13													
14				14.0									
			Test Pit terminated at 14 feet. Test Pit backfilled without compaction verification.										

LUMOS TP FULL PAGE OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/16/22



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## LOG OF EXPLORATORY TEST PIT

Job Number: 9103.002

Date: May 2022

PLATE

A-1

# EXPLORATION No. TP #2

Logged By: **J. Macaluso**  
 Date Logged: **5/5/2022**  
 Equipment Type: **CAT. 330 DL Excavator**

Total Depth: **13 feet**  
 Water Depth: **No groundwater encountered**  
 Ground Elev.: **Existing Grade**

Depth in Feet	Graphic Log	Sample Type	<div><div><div></div><div></div><div></div></div><div>Percolation Test</div></div> <div><div><div></div><div></div></div><div>Split Spoon</div></div> <div><div><div></div><div></div></div><div>Ziplock Sample</div></div> <div><div><div></div><div></div></div><div>Core Sampler</div></div> <div><div><div></div><div></div></div><div>Bulk Sample</div></div> <div><div><div></div><div></div></div><div>Static Water Table</div></div>	Natural Moisture Content, %	In-Place Moisture Content, %	In Place Dry Density, pcf	Liquid Limit, %	Plasticity Index, %	Gravel, % (3" - #4 Sieve)	Sand, % (#4 - #200 Sieve)	Fines, % (< #200 Sieve)	R-Value	Expansion Index
			SOIL DESCRIPTION										
1			<b>Medium Brown Poorly Graded SAND with Silt, Gravel, and Cobble (SP-SM)</b> Loose, Slightly Moist Estimated: 20% Unclassifiable Rounded to Subangular Boulders Up to 4' in Diameter										
2													
3		B		4.9	101.1					77			
4													
5		B	3.7	5.4	111.1	NP	NP	25.8	56.4	10.0			
6													
7			Clear Change in Strata at a Depth of 7' None to Few Boulders After 7' Bottom of Landslide Material	7.0									
8			<b>Whitish-Tan Poorly Graded SAND (SP)</b> Loose, Slightly Moist Estimated: 10% Coarse to Fine Gravel 90% Coarse to Fine Sand Trace Fines										
9													
10													
11			Material Moist at a Depth of 11'										
12		B											
13				13.0									
Test Pit terminated at 13 feet. Test Pit backfilled without compaction verification.													

Test Pit terminated at 13 feet.  
 Test Pit backfilled without compaction verification.

LUMOS TP FULL PAGE OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/16/22



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## LOG OF EXPLORATORY TEST PIT

Job Number: 9103.002

Date: May 2022

PLATE

**A-2**



# EXPLORATION No. TP #3

Logged By: **J. Macaluso**  
 Date Logged: **5/5/2022**  
 Equipment Type: **CAT. 330 DL Excavator**

Total Depth: **14.5 feet**  
 Water Depth: **No groundwater encountered**  
 Ground Elev.: **Existing Grade**

Depth in Feet	Graphic Log	Sample Type	<div><div><div></div></div> Percolation Test</div> <div><div><div></div></div> Core Sampler</div>	<div><div><div></div></div> Split Spoon</div> <div><div><div></div></div> Bulk Sample</div>	<div><div><div></div></div> Ziplock Sample</div> <div><div><div></div></div> Static Water Table</div>	Natural Moisture Content, %	In-Place Moisture Content, %	In Place Dry Density, pcf	Liquid Limit, %	Plasticity Index, %	Gravel, % (3" - #4 Sieve)	Sand, % (#4 - #200 Sieve)	Fines, % ( < #200 Sieve)	R-Value	Expansion Index
			SOIL DESCRIPTION												
1			<b>Olive Brown Silty SAND (SM)</b> <b>Non-Homogeneous Mix of Poorly Graded Sand and Silt Chunks</b> Loose-Medium Dense, Slightly Moist  Contains Debris: Asphalt and Metal <b>Maximum Dry Density and Optimum Moisture Content:</b> <b>Corrected - 123.5 p.c.f. at 10.5%</b> <b>Uncorrected - 121.4 p.c.f. at 11.2%</b>												
2															
3		B			7.3	9.6	100.2	NP	NP	13.9	67.4	18.7			
4			4.0												
5		B	<b>Whitish Tan Poorly Graded SAND with Silt (SP-SM)</b> Loose, Slightly Moist Estimated: 90% Medium to Fine Sand 10% Fines Tree Branch at a Depth of 6'   <												

LUMOS TP FULL PAGE OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/16/22



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## LOG OF EXPLORATORY TEST PIT

Job Number: 9103.002

Date: May 2022









PLATE

**A-3**

# EXPLORATION No. TP #4

Logged By: **J. Macaluso**  
 Date Logged: **5/5/2022**  
 Equipment Type: **CAT. 330 DL Excavator**

Total Depth: **15 feet**  
 Water Depth: **No groundwater encountered**  
 Ground Elev.: **Existing Grade**

Depth in Feet	Graphic Log	Sample Type	 Percolation Test	 Split Spoon	 Ziplock Sample	Natural Moisture Content, %	In-Place Moisture Content, %	In Place Dry Density, pcf	Liquid Limit, %	Plasticity Index, %	Gravel, % (3" - #4 Sieve)	Sand, % (#4 - #200 Sieve)	Fines, % (< #200 Sieve)	R-Value	Expansion Index
			 Core Sampler	 Bulk Sample	 Static Water Table										
1			<b>Medium Brown Poorly Graded SAND with Silt (SP-SM)</b> Loose-Medium Dense, Slightly Moist Estimated: 10% Coarse to Fine Gravel 80% Medium to Fine Sand 10% Fines												
2															
3															
4															
5															
6															
7															
8															
9			<b>Tan Poorly Graded SAND with Silt (SP-SM)</b> Loose-Medium Dense, Slightly Moist-Moist Estimated: Trace Gravel 90% Coarse to Fine Sand 10% Fines												
10															
11															
12															
13															
14															
15															
Test Pit terminated at 15 feet. Test Pit backfilled without compaction verification.															

LUMOS TP FULL PAGE OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/16/22



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## LOG OF EXPLORATORY TEST PIT

Job Number: 9103.002

Date: May 2022

PLATE

**A-4**

# EXPLORATION No. TP #5

Logged By: **J. Macaluso**  
 Date Logged: **5/5/2022**  
 Equipment Type: **CAT. 330 DL Excavator**

Total Depth: **13.5 feet**  
 Water Depth: **No groundwater encountered**  
 Ground Elev.: **Existing Grade**

Depth in Feet	Graphic Log	Sample Type	<div> <div> <div></div> <div></div> </div> <div> <div></div> <div></div> </div> </div> Percolation Test Core Sampler	<div> <div></div> <div></div> </div> <div> <div></div> <div></div> </div>
---------------	-------------	-------------	---	---

LUMOS TP FULL PAGE OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/16/22



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## LOG OF EXPLORATORY TEST PIT

Job Number: 9103.002

Date: May 2022




PLATE

**A-5**

# EXPLORATION No. TP #6

Logged By: **J. Macaluso**  
 Date Logged: **5/5/2022**  
 Equipment Type: **CAT. 330 DL Excavator**

Total Depth: **14 feet**  
 Water Depth: **No groundwater encountered**  
 Ground Elev.: **Existing Grade**

Depth in Feet	Graphic Log	Sample Type	<div><div><div></div><div></div><div></div></div><div>Percolation Test</div></div> <div><div><div></div><div></div><div></div></div><div>Split Spoon</div></div> <div><div><div></div><div></div><div></div></div><div>Ziplock Sample</div></div> <div><div><div></div><div></div><div></div></div><div>Core Sampler</div></div> <div><div><div></div><div></div><div></div></div><div>Bulk Sample</div></div> <div><div><div></div><div></div><div></div></div><div>Static Water Table</div></div>	Natural Moisture Content, %	In-Place Moisture Content, %	In Place Dry Density, pcf	Liquid Limit, %	Plasticity Index, %	Gravel, % (3" - #4 Sieve)	Sand, % (#4 - #200 Sieve)	Fines, % (< #200 Sieve)	R-Value	Expansion Index
SOIL DESCRIPTION													
1		<b><u>Yellow Brown Well Graded SAND with Silt, Cobbles, and Boulders (SW-SM)</u></b> Loose, Slightly Moist Estimated: 20% Unclassifiable Cobbles and Boulders up to 4' in Diameter											
2													
3		<b>Maximum Dry Density and Optimum Moisture Content:</b> <b>117.8 p.c.f. at 10.8%</b>	3.2	3.6	102.0	NP	NP	3.5	89.5	7.0			
4													
5		<b>Clear Change in Strata at a Depth of 6'</b> <b>Bottom of Landslide Material</b>		4.4	102.0								
6			6.0										
7		<b><u>Whitish Tan Poorly Grade SAND (SP)</u></b> Loose-Medium Dense, Slightly Moist Estimated: 10% Coarse to Fine Gravel, 90% Coarse to Fine Sand, Trace Fines											
8													
9		<b><u>Tan Poorly Graded SAND with Silt, Gravel, and Cobbles (SP-SM)</u></b> Loose-Medium Dense, Slightly Moist Estimated: 20% Unclassifiable Cobble up to 8" in Diameter with the Remainder of the Matrix Consisting of 20% Coarse to Fine Gravel 70% Coarse to Fine Sand 10% Fines											
10													
11													
12													
13													
14			14.0										
Test Pit terminated at 14 feet. Test Pit backfilled without compaction verification.													

LUMOS TP FULL PAGE OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/16/22



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## LOG OF EXPLORATORY TEST PIT

Job Number: 9103.002

Date: May 2022

PLATE

**A-6**



# EXPLORATION No. TP #7

Logged By: **J. Macaluso**  
 Date Logged: **5/5/2022**  
 Equipment Type: **CAT. 330 DL Excavator**

Total Depth: **14 feet**  
 Water Depth: **No groundwater encountered**  
 Ground Elev.: **Existing Grade**

Depth in Feet	Graphic Log	Sample Type	<div><div><div></div></div> Percolation Test</div> <div><div><div></div></div> Core Sampler</div>	<div><div><div></div></div> Split Spoon</div> <div><div><div></div></div> Bulk Sample</div>	<div><div><div></div></div> Ziplock Sample</div> <div><div><div></div></div> Static Water Table</div>	Natural Moisture Content, %	In-Place Moisture Content, %	In Place Dry Density, pcf	Liquid Limit, %	Plasticity Index, %	Gravel, % (3" - #4 Sieve)	Sand, % (#4 - #200 Sieve)	Fines, % (< #200 Sieve)	R-Value	Expansion Index		
			SOIL DESCRIPTION														
1		B	<b>Medium Brown Silty SAND (SM)</b> Loose-Medium Dense, Slightly Moist Estimated: Trace Gravel 80% Coarse to Fine Sand 20% Fines														
2																	
3							4.1	116.1									
4							4.0										
5		B	<b>Medium Brown Poorly Graded SAND with Silt, Gravel, Cobble, and Boulders (SP-SM)</b> Loose-Medium Dense, Slightly Moist Estimated: 20% Unclassifiable Cobble and Boulders up to 3' in Diameter with the Remainder of the Matrix Consisting of 20% Coarse to Fine Gravel 70% Coarse to Fine Sand 10% Fines Distinct Layer of Boulders at a Depth of 7', Boulders Sparsly Present Below 7' Possible Bottom of Landslide Material														
6																	
7																	
8							8.0										
9		B	<b>Whitish Tan Poorly Graded SAND (SP)</b> Loose-Medium Dense, Slightly Moist Estimated: 10% Coarse to Fine Gravel, 90% Coarse to Fine Sand, Trace Fines														
10																	
11																	
12																	
13			<b>Medium Brown Silty SAND with Gravel, Cobbles, and Boulders (SM)</b> Loose-Medium Dense, Slightly Moist Estimated: 5% Unclassifiable Cobble and Boulders up to 2' in Diameter with the Remainder of the Matrix Consisting of 20% Coarse to Fine Gravel 60% Coarse to Fine Sand 20% Fines														
14					14.0												
Test Pit terminated at 14 feet. Test Pit backfilled without compaction verification.																	

LUMOS TP FULL PAGE OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/16/22



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## LOG OF EXPLORATORY TEST PIT

Job Number: 9103.002

Date: May 2022

PLATE

**A-7**

# SOIL CLASSIFICATION CHART

MAJOR DIVISIONS			SYMBOLS		TYPICAL DESCRIPTIONS
			GRAPH	LETTER	
COARSE GRAINED SOILS  MORE THAN 50% OF MATERIAL IS LARGER THAN NO. 200 SIEVE SIZE	GRAVEL AND GRAVELLY SOILS  MORE THAN 50% OF COARSE FRACTION RETAINED ON NO. 4 SIEVE	CLEAN GRAVELS  (LITTLE OR NO FINES)		GW	WELL-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES
				GP	POORLY-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES
		GRAVELS WITH FINES  (APPRECIABLE AMOUNT OF FINES)		GM	SILTY GRAVELS, GRAVEL - SAND - SILT MIXTURES
				GC	CLAYEY GRAVELS, GRAVEL - SAND - CLAY MIXTURES
	SAND AND SANDY SOILS  MORE THAN 50% OF COARSE FRACTION PASSING ON NO. 4 SIEVE	CLEAN SANDS  (LITTLE OR NO FINES)		SW	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
				SP	POORLY-GRADED SANDS, GRAVELLY SAND, LITTLE OR NO FINES
		SANDS WITH FINES  (APPRECIABLE AMOUNT OF FINES)		SM	SILTY SANDS, SAND - SILT MIXTURES
				SC	CLAYEY SANDS, SAND - CLAY MIXTURES
FINE GRAINED SOILS  MORE THAN 50% OF MATERIAL IS SMALLER THAN NO. 200 SIEVE SIZE	SILTS AND CLAYS  LIQUID LIMIT LESS THAN 50			ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY
				CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
				OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
	SILTS AND CLAYS  LIQUID LIMIT GREATER THAN 50			MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILTY SOILS
				CH	INORGANIC CLAYS OF HIGH PLASTICITY
				OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS
HIGHLY ORGANIC SOILS				PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS

NOTE: DUAL SYMBOLS ARE USED TO INDICATE BORDERLINE SOIL CLASSIFICATIONS

Other Tests	
AN	ANALYTICAL TEST (pH, Soluble Sulfate, and Resistivity)
C	CONSOLIDATION TEST
DS	DIRECT SHEAR TEST
MD	MOISTURE DENSITY CURVE



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## LEGEND

Job Number: 9103.002


Date: May 2022

PLATE

A-8

# **APPENDIX B**

## **Soils Laboratory Test Results**



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen Identification		Date: 5/6/2022								
●	TP #2	Classification				LL	PL	PI	Cc	Cu
	Depth: 4.5	Poorly Graded SAND with Silt, Gravel, and Boulders				NP	NP	NP	0.8	29.0
	Sample Location	Test Pit #2, 4.5'-5.5'								
	USCS	SP-SM								
	AASHTO									
Specimen Identification										
●	TP #2	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay	
	Depth: 4.5	100	2.185	0.354	0.075	25.8	56.4	10.0		
	Natural Moisture	3.7 %		S.E.		Absorption %				
	R-Value			Durability Index		Soundness				
	Percentage of Wear (500 rev)	%		Specific Gravity		Direct Shear				



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## GRAIN SIZE DISTRIBUTION


Job Number: 9103.002

Date: May 2022

**PLATE**  
**B-1.1**

LUMOS GRAIN SIZE OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/13/22





COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen Identification		Date: 5/6/2022							
●	TP #3	Classification			LL	PL	PI	Cc	Cu
	Depth: 2.5	Silty SAND (SM)			NP	NP	NP		
	Sample Location	Test Pit #3, 2.5'-3.5'							
	USCS	SM							
	AASHTO								
Specimen Identification									
●	TP #3	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay
	Depth: 2.5	50	0.7	0.181		13.9	67.4	18.7	
	Natural Moisture	7.3 %		S.E.		Absorption %			
	R-Value			Durability Index		Soundness			
	Percentage of Wear (500 rev)	%		Specific Gravity		Direct Shear			



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## GRAIN SIZE DISTRIBUTION


Job Number: 9103.002

Date: May 2022

PLATE

B-1.2

LUMOS GRAIN SIZE OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/13/22



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen Identification		Date: 5/6/2022								
●	TP #6	Classification				LL	PL	PI	Cc	Cu
	Depth: 3	Well Graded SAND with Silt				NP	NP	NP	1.3	7.3
	Sample Location	Test Pit #6, 3'-4'								
	USCS	SW-SM								
	AASHTO									
Specimen Identification										
●	TP #6	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay	
	Depth: 3	25	0.736	0.312	0.101	3.5	89.5	7.0		
	Natural Moisture	3.2 %		S.E.		Absorption %				
	R-Value			Durability Index		Soundness				
	Percentage of Wear (500 rev)	%		Specific Gravity		Direct Shear				

**LUMOS & ASSOCIATES**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

**GRAIN SIZE DISTRIBUTION**


Job Number: 9103.002

Date: May 2022

**PLATE**

**B-1.3**

LUMOS GRAIN SIZE OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/13/22



**LUMOS ATTERBERG LIMITS OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/13/22**




## ATTERBERG LIMITS' RESULTS

Date: May 2022

**PLATE**  
**B-2**

DRY DENSITY, pcf

LUMOS COMPACTION OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/13/22



Date: 5/6/2022  
Sample ID: TP #3  
Sample Location: Test Pit #3, 2.5'-3.5'  
Depth: 2.5  
Description of Material: Silty SAND (SM)  
Test Method: AASHTO T-180/T-224

#### TEST RESULTS

Maximum Dry Density: **121.4 PCF**  
Optimum Water Content: **11.2 %**  
Natural Moisture: **7.3 %**  
R-Value: \_\_\_\_\_

USCS Classification: **SM**  
AASHTO Classification: \_\_\_\_\_

#### ATTERBERG LIMITS

LL	PL	PI
NP	NP	NP

#### FINES

19 % Passing #200 Sieve



**Lumos & Associates**  
808 E. College Parkway, Suite 101  
Carson City, NV 89703  
775.883.7077  
Fax: 775.883.7114  
mburns@lumosinc.com

Ophir Hills Grading SUP

### MOISTURE-DENSITY CURVE

Job Number: 9103.002


Date: May 2022

**PLATE**  
  
**B-3.1**



DRY DENSITY, pcf

LUMOS COMPACTION OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/13/22



**Lumos & Associates**  
808 E. College Parkway, Suite 101  
Carson City, NV 89703  
775.883.7077  
Fax: 775.883.7114  
mburns@lumosinc.com

Ophir Hills Grading SUP

## MOISTURE-DENSITY CURVE


Job Number: 9103.002

Date: May 2022

PLATE

**B-3.2**

SHEAR STRENGTH, ksf



NORMAL PRESSURE, ksf

Specimen Identification			Classification	$\gamma_d$	MC%	c	$\phi$
●	TP #6	3.0	Well Graded SAND with Silt	106	11	0.54	30.6



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com


Ophir Hills Grading SUP  
**DIRECT SHEAR TEST**

Job Number: 9103.002

Date: May 2022

**PLATE**  
**B-4**

LUMOS DIRECT SHEAR OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/13/22



### Test Data

Specimen No.	Water Content (%)	Dry Density (pcf)	Expansion (psf)	Exudation (psi)	Test R-Value*
1	10.7	123.7	0.0	105.0	72.0
2	9.6	124.6	0.0	304.0	77.0
3	8.7	569.0	0.0	569.0	83.0

\* Reported values have been corrected for sample height, where required.

### Test Result

Specimen Identification	Classification	R-Value
TP #2 2.5	Poorly Graded SAND with Silt, Gravel, and Boulders	77



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## RESISTANCE VALUE TEST

Job Number: 9103.002

Date: May 2022

**PLATE**  
  
**B-5**

R-VALUE OPHIR HILLS SUP GEO.GPJ US LAB.GDT 5/13/22



Silver State Labs-Reno  
1135 Financial Blvd  
Reno, NV 89502  
(775) 857-2400 FAX: (888) 398-7002  
www.ssalabs.com

## Analytical Report

Workorder#: 22050510  
Date Reported: 5/19/2022

**Client:** Lumos and Associates - Reno  
**Project Name:** 9103.002 / Ophir Hills Sup - TP-1 2.5' - 3.5'  
**PO #:** 9103.002/MTB

**Sampled By:** J. Macaluso

**Laboratory Accreditation Number:** NV015/CA2990

Laboratory ID	Client Sample ID	Date/Time Sampled	Date Received
22050510-01	Ophir Hills Sup - TP-1 2.5' - 3.5'	05/05/2022 0:00	5/9/2022

Parameter	Method	Result	Units	PQL	Analyst	Date/Time Analyzed	Data Flag
Chloride	EPA 9056	<50	mg/Kg	50	CTR	05/18/2022 13:11	
pH	SW-846 9045D	5.64	pH Units		AC	05/17/2022 10:31	
pH Temperature	SW-846 9045D	22.0	°C		AC	05/17/2022 10:31	
Resistivity	AASHTO T288	17000	Ohms-cm		SR	05/12/2022 13:34	
Sodium	ASTM D2791	< 0.01	%	0.01	AC	05/16/2022 10:00	
Sodium Sulfate as Na <sub>2</sub> SO <sub>4</sub>	Calculation	< 0.01	%	0.01	AC	05/18/2022 10:58	
Solubility	SM 2540C	0.036	%	0.01	DL	05/13/2022 10:04	
Sulfate	SM4500 SO <sub>4</sub> E	< 0.010	%	0.01	SR	05/17/2022 9:43	

Original

Page 2 of 8



**Lumos & Associates**  
808 E. College Parkway, Suite 101  
Carson City, NV 89703  
775.883.7077  
Fax: 775.883.7114  
mburns@lumosinc.com

Ophir Hills Grading SUP

## ANALYTICAL TESTING

Job Number: 9103.002

Date: May 2022

PLATE

B-6



# **APPENDIX C**

## **Design Response Spectrum**

# ATC Hazards by Location

## Search Information

**Coordinates:** 39.29280502470283, -119.82831037044527

**Elevation:** 5087 ft

**Timestamp:** 2022-05-13T17:27:17.686Z

**Hazard Type:** Seismic

**Reference Document:** ASCE7-16

**Risk Category:** II

**Site Class:** D-default



## Basic Parameters

Name	Value	Description
$S_S$	2.15	$MCE_R$ ground motion (period=0.2s)
$S_1$	0.764	$MCE_R$ ground motion (period=1.0s)
$S_{MS}$	2.58	Site-modified spectral acceleration value
$S_{M1}$	* null	Site-modified spectral acceleration value
$S_{DS}$	1.72	Numeric seismic design value at 0.2s SA
$S_{D1}$	* null	Numeric seismic design value at 1.0s SA

\* See Section 11.4.8

## Additional Information

Name	Value	Description
SDC	* null	Seismic design category
$F_a$	1.2	Site amplification factor at 0.2s
$F_v$	* null	Site amplification factor at 1.0s
$CR_S$	0.887	Coefficient of risk (0.2s)
$CR_1$	0.879	Coefficient of risk (1.0s)
PGA	0.923	$MCE_G$ peak ground acceleration
$F_{PGA}$	1.2	Site amplification factor at PGA
$PGA_M$	1.107	Site modified peak ground acceleration
$T_L$	6	Long-period transition period (s)

<https://hazards.atcouncil.org/#/seismic?lat=39.29280502470283&lng=-119.82831037044527&address=>

1/2



**Lumos & Associates**  
 808 E. College Parkway, Suite 101  
 Carson City, NV 89703  
 775.883.7077  
 Fax: 775.883.7114  
 mburns@lumosinc.com

Ophir Hills Grading SUP

## DESIGN RESPONSE SPECTRUM

Job Number: 9103.002

Date: May 2022

**PLATE**  
**C-1**

# **APPENDIX D**

## **Pavement Design**

Job Number: 9103.002  
Project: Ophir Hill Grading SUP  
Client: Burdick Excavating  
Description: Pavement Calculations  
By: J. Macaluso

R-Value for Native Subgrade = 77 (Laboratory Test Result)  
R-Value for Structural Fill = 45 (Specification)  
R-Value for Aggregate Base = 70 (Type 2 Class B Aggregate Base)  
TI (Traffic Index) = 5 (Light Truck/Car Traffic)

$$GE = 0.0032 * (TI) * (100 - R)$$

$$G_{f(AC)} = 2.5, \quad G_{f(Base)} = 1.1, \\ t_{layer} = GE / G_f$$

$$GE_{AC} = 0.0032 * (5) * (100 - 70) = 0.48' \\ t_{AC} = (0.48' / 2.50) * (12'' / 1') = 2.3'' \quad \text{USE 3'' Asphalt Concrete} \\ GE_{AC} = (3'' * 2.50) / (12'') = 0.63'$$

$$GE_{Base} = 0.0032 * (5) * (100 - 45) = 0.88' \\ t_{Base} = ((0.88' - 0.63') / 1.1) * (12'' / 1') = 2.8'' \quad \text{USE 4'' Aggregate Base}$$

Therefore, 3" of Asphalt Concrete (AC) underlain by a minimum of 4" of Aggregate Base, underlain by 24" of properly prepared sub-grade for car and light truck traffic



**Lumos & Associates**  
808 E. College Parkway, Suite 101  
Carson City, NV 89703  
775.883.7077  
Fax: 775.883.7114  
mburns@lumosinc.com

Ophir Hills Grading SUP  
**PAVEMENT DESIGN**

Job Number: 9103.002

Date: May 2022

**PLATE**  
**D-1**